

Illinois Tollway Standard Drawing Revisions


Section D	Roadway Appurtenances	
Standard	Modification Summary	Effective: 03-01-2022
D5-09	PERMANENT PAVEMENT MARKINGS, MAINLINE	
Sheet 1	Edge lines width changed to 6"	
Sheet 1	Revised offset of right edge lines to be 4"	
Sheet 1	Removed "min." from pavement marking width call outs	
D6-10	PERMANENT PAVEMENT MARKINGS, RAMPS	
Sheet 1	Edge lines width changed to 6"	
D7-01	SHOULDER RUMBLE STRIP DETAILS	
Sheet 1	Revised edge lines on sections C-C & D-D	
D10-02	TEMPORARY CONCRETE BARRIER WITH CROSS-BOLT CONNECTION	
Sheet 1	Revised Note 2.	




New Sheet



Retired Standard



RIGHT OF WAY FENCE, TYPE 1, 6'



GENERAL NOTES

- ON STRAIGHT RUNS OF FENCE, PULL POSTS SHALL BE USED AT 500' CENTERS FOR TYPE 1 AND 330' CENTERS FOR TYPE 2.
- WHERE R.O.W. FENCE FOLLOWS R.O.W. LINE IT SHALL BE INSTALLED PARALLEL TO AND 6" INSIDE THE R.O.W. LINE ON ILLINOIS TOLLWAY PROPERTY.
- LINE POSTS AND BRACES SHALL BE ON ILLINOIS TOLLWAY SIDE OF FENCE FABRIC.
- WHEN THE TENSION OF THE FENCE TENDS TO PULL THE POSTS FROM THE GROUND, THE LINE POSTS SHALL BE ANCHORED WITH ANCHORAGE SPECIFIED FOR CORNER POSTS.
- WHEN THE FENCE LINE HAS A CHANGE IN DIRECTION OF 10° OR MORE, A CORNER POST SHALL BE PLACED AT THE POINT OF CHANGE. WHERE THE ANGLE OF CHANGE IS LESS THAN 10° A PULL POST SHALL BE USED.
- WHERE GRADE LINE HAS A CHANGE IN SLOPE OF 10° OR MORE, A CORNER POST WITH BRACING AS REQUIRED SHALL BE PLACED. WHERE ANGLE IS LESS THAN 10° LINE POST MAY BE USED.
- WHERE RIGHT-OF-WAY FENCE, TYPE 1 IS USED, THE FABRIC SHALL BE KNUCKLED SELVAGE ON TOP AND TWISTED AND BARBED SELVAGE ON BOTTOM.
- PLACEMENT OF BRACED END POSTS OR CORNER POSTS WITHIN THE CLEAR ZONE SHALL BE AVOIDED.




DATE	REVISIONS
3-01-2020	ADDED GATE TO HEADWALL DETAIL
3-31-2017	REVISED NOTES
3-11-2015	REVISED NOTES
3-31-2014	REVISED ROLLED FORM SECTIONS
11-01-2012	REVISED NOTES

RIGHT OF WAY FENCE



STANDARD D1-06

APPROVED: *Paul Kovacs* DATE 7-1-2009
 CHIEF ENGINEERING OFFICER




STRETCHER BARS SHALL BE GALVANIZED FLAT STEEL BAR NOT LESS THAN 1/4" x 3/4" AND THE STRETCHER BAR BANDS SHALL BE GALVANIZED FLAT STEEL BAR NOT LESS THAN 1/8" x 1" WITH A 3/8" GALVANIZED CARRIAGE BOLT.

METHOD OF FASTENING STRETCHER BAR TO POST




LINE POST 'C' SECTION




TERMINAL POST SECTION
5.10 LBS/LF

DETAILS OF ROLL FORMED SECTIONS




METHOD OF TYING FABRIC TO TENSION WIRES



ABUTMENT CONNECTION DETAIL

NOTES FOR ABUTMENT CONNECTION:

1. WHEN ROLL FORMED SECTION IS USED IN LIEU OF PIPE AS END POST, THE POST SHALL BE BOLTED DIRECTLY TO THE ABUTMENT WALL WITH 2 1/2" x 5" BOLTS WITH STANDARD WASHERS MEETING THE APPROVAL OF THE ENGINEER.




STANDARD GROUND

COUNTERPOISE GROUND (ALTERNATE)

NOTES FOR STANDARD AND COUNTERPOISE GROUND:

1. THE INTERVALS FOR GROUNDING CONTINUOUS FENCING SHALL NOT EXCEED 500 FEET IN URBAN AREAS AND 1000 FEET IN RURAL AREAS. FENCE ADJACENT TO A GATE SHALL BE GROUNDED A MAXIMUM DISTANCE 100 FEET EACH SIDE OF THE GATE.
2. FENCE CROSSING UNDER A POWER LINE SHALL BE GROUNDED, ONCE DIRECTLY UNDER THE CROSSING AND ONE ON EACH SIDE AT 25 TO 50 FEET AWAY. FENCE LOCATED DIRECTLY UNDER A TELEPHONE WIRE OR CABLE CROSSING SHALL HAVE A SINGLE GROUND.
3. COUNTERPOISE GROUNDS SHALL BE USED AT LOCATIONS WHERE GROUND RODS CAN NOT BE DRIVEN DUE TO IMPERVIOUS EARTH MATERIALS.
4. THE GROUND WIRES SHALL BE CONNECTED TO FENCE FABRIC AND GROUND ROD BY STAINLESS STEEL BOLTS AND WASHERS. THE LOWER CONNECTION OF THE GROUND WIRE SHALL BE MADE TO THE BOTTOM TENSION WIRE.



ALTERNATE DRIVEN LINE POST ANCHORAGE WITH OR WITHOUT DRIVE ANCHORS


NOTE FOR FENCE POST:

ALTERNATE DRIVEN LINE POST ANCHORAGE IS OPTIONAL. DRIVEN LINE POST ANCHORAGE WITHOUT DRIVE ANCHORS MAY BE USED IN AVERAGE TO GOOD SOIL CONDITIONS. WHEN SOIL IS WEAKER ($Q_u < 1.25$ TONS/ SQ. FT.) AND STABILITY OF THE POST IS QUESTIONABLE, DRIVE ANCHORS SHALL BE USED. TYPES, SHAPES, DIMENSIONS AND COATING REQUIREMENTS OF DRIVE ANCHORS (ANCHOR BLADES AND COLLARS) FOR DIFFERENT TYPE OF POSTS SHALL BE AS RECOMMENDED BY THE MANUFACTURER.

ELECTRICAL GROUNDING DETAILS


APPROVED: *Paul Kovacs* DATE: 7-1-2009
CHIEF ENGINEERING OFFICER





NORMAL FLOW: NONE.
MAY BE VARIED FOR
STEEPER BANKS TO FIT
VARIOUS CHANNEL SECTIONS.


STREAM CROSSING, TYPE 1



STREAM CROSSING, TYPE 2


NOTES FOR STREAM CROSSING TYPE 1 AND TYPE 2:

1. THESE INSTALLATION CONDITIONS ARE TYPICAL AND ARE NOT TO BE CONSTRUED AS REPRESENTATIVE OF ALL CONDITIONS WHICH WILL BE ENCOUNTERED. CONSTRUCTION WILL BE VARIED AS REQUIRED OR DIRECTED TO MEET FIELD CONDITIONS.
2. FOR STREAM CROSSING OF THE TYPE REQUIRED THE BOTTOM BARBED WIRE SHALL BE ANCHORED TO CONCRETE FOOTING OR TO HOLES DRILLED IN POSTS, AND INTERMEDIATE WIRES SHALL BE TIED TO THE BOTTOM WIRE AND TO POSTS IN AN EVENLY SPACED FASHION TO PREVENT SLIPPAGE.
3. CONCRETE AND FITTINGS FOR ALL TYPES OF FENCE SHALL BE AS DETAILED FOR SIMILAR CONDITIONS PER STANDARD DRAWING.




THE FENCE FABRIC SHALL BE REPLACED BY BARBED WIRE STRANDS AT 12\"/>

DETAIL A




FENCE INSTALLATION OVER DITCH




NOTE:
"X" + "Y" SHALL NOT EXCEED 30" WHEN "X" IS 0" TO 15" "Y" =15", AND THE POST SHALL BE SHORTENED AS REQUIRED. WHEN "X" EXCEEDS 15" "Y" SHALL BE DECREASED ACCORDINGLY.

FOOTING FOR POST WHEN ROCK LEDGE IS ENCOUNTERED



PLAN AT HEADWALL



ELEVATION



NOTES FOR INSTALLATION AROUND HEADWALL:

1. THIS TYPE OF INSTALLATION IS TO BE USED ONLY WHEN SPECIFICALLY CALLED FOR IN THE CONTRACT PLANS.
2. WHEN THE WIDTH OF THE CULVERT MAKES IT NECESSARY TO ANCHOR A POST TO THE TOP OF THE CULVERT, A CAST IRON SHOE OR OTHER DEVICE APPROVED BY THE ENGINEER SHALL BE USED.

INSTALLATION AROUND HEADWALL



SURVEY AND ROADWAY ITEMS

<u>EXISTING</u>	<u>PROPOSED</u>	
		CONSTRUCTION JOINT W/DOWEL BARS
		BENCHMARK
		CANTILEVER SIGN STRUCTURE
		BUTTERFLY SIGN STRUCTURE
		DOUBLE COLUMN GROUND MOUNTED SIGN
		SINGLE COLUMN GROUND MOUNTED SIGN
		SPAN TYPE SIGN STRUCTURE
		TRIPLE COLUMN GROUND MOUNTED SIGN
		RUMBLE STRIP

DRAINAGE AND UTILITY ITEMS; ROADWAY LIGHTING AND SIGNS

<u>EXISTING</u>	<u>PROPOSED</u>	
		BOX CULVERT WITH HEADWALL
		CABLE IN DUCT W/O GROUND
		LOW POINT
		OVERHEAD ELECTRICAL
		OVERHEAD TELEPHONE
		PIPE CULVERT
		LAKE OR POND
		QUARRY
		STREAM
		SWAMP
		CABLE OR CONDUIT TAG
		ELECTRICAL MANHOLE
		LIGHT-DUTY BOX
		ROADWAY LUMINAIRE
		STEEL TOWER
		TELEPHONE MANHOLE
		UNDERPASS LUMINAIRE
		WATER POINT
		WATERMAIN VALVE VAULT
		WATER WELL
		WOOD POLE



DATE	REVISIONS
3-31-2016	UPDATED DITCH CHECK SYMBOL
3-11-2015	ADDED NEW SYMBOL
11-01-2012	ADDED NEW SYMBOLS
7-01-2009	REVISED SYMBOL & PATTERNS

SYMBOLS AND PATTERNS


STANDARD D2-04

Paul Kovacs
 APPROVED..... CHIEF ENGINEER..... DATE 7-1-2009

EROSION & SEDIMENT CONTROL, LANDSCAPING ITEMS

EXISTING

PROPOSED



CLEARING & GRADING LIMITS
(LIMITS OF CONSTRUCTION)

DIVERSION DIKE

DRAINAGE DIVIDE

DRAINAGE PATH

SEDIMENT BASIN
AGGREGATE BERM

CULVERT INLET
PROTECTION-STONE
CIP

CULVERT INLET
PROTECTION-FENCE

DB

DEWATERING BASIN

FIPB

FILTER FABRIC
INLET PROTECTION, BASKET TYPE

FIPC

FILTER FABRIC
INLET PROTECTION, COVER TYPE

FB

FLOTATION BOOM

IC

INITIAL CONSTRUCTION ITEM

RIP

RECTANGULAR INLET
PROTECTION

TEMPORARY ROCK CHECK DAM

T

TEMPORARY DITCH CHECK

SEDIMENT BASIN

SILT FENCE

SSF

SUPER SILT FENCE

STABILIZED CONSTRUCTION ENTRANCE

STONE OUTLET STRUCTURE
SEDIMENT TRAP

STREAM DIVERSION

TEMPORARY PIPE SLOPE DRAIN

TEMPORARY RIPRAP

TEMPORARY SWALE


TREES AND STUMP

TP

TREE PROTECTION

TEMPORARY STREAM CROSSING

PROPOSED



EROSION CONTROL BLANKET

OVER SEEDING CLASS B1

OVER SEEDING CLASS B2

SEEDING CLASS A1

SEEDING CLASS A2

SEEDING CLASS A3

SEEDING CLASS A4

SEEDING CLASS A5

SEEDING CLASS A6

SEEDING CLASS D1

SODDING (SALT TOLERANT)

TEMPORARY GROUND COVER

TURF REINFORCEMENT MAT



SYMBOLS AND PATTERNS

STANDARD D2-04

APPROVED *Paul Kovacs* CHIEF ENGINEER DATE 7-1-2009

ELECTRICAL AND MECHANICAL ITEMS

				EXISTING	PROPOSED	
	HOME RUN TO PANEL AS NOTED		STANDBY GENERATOR	_____ A _____	_____ A _____	COMPRESSED AIR (A)
	INDICATES CIRCUIT TURNING DOWN		PANEL CIRCUIT BREAKER	_____ AR _____	_____ AR _____	ACID RESISTANT WASTE OR DRAIN
	INDICATES CIRCUIT TURNING UP		MECHANICALLY HELD LIGHTING COIL	_____ ARV _____	_____ ARV _____	ACID RESISTANT VENT
	GROUND ROD		CONTROL RELAY COIL	_____ DS _____	_____ DS _____	STORM SEWER (DOWNSPOUT)
	GROUNDING TRIAD		SINGLE-POLE SWITCH	_____ G _____	_____ G _____	GAS LINE
	TRANSFORMER		DUPLEX RECEPTACLE	_____ HG _____	_____ HG _____	HOT GAS BYPASS LINE (HG)
	MOTOR		4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR, BACK BOX, & ANGLE ADAPTER	_____ HHWR _____	_____ HHWR _____	HEATING HOT WATER RETURN (HHWR)
	AUTOMATIC TRANSFER SWITCH (ATS)		4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR & BACK BOX	_____ HHWS _____	_____ HHWS _____	HEATING HOT WATER SUPPLY (HHWS)
	JUNCTION BOX		DUPLEX RECEPTACLE WITH GROUND FAULT PROTECTION	_____ IA _____	_____ IA _____	DRY COMPRESSED AIR (IA-INSTRUMENT AIR)
	DISCONNECT SWITCH		CONTROL BUILDING LIGHTING 1' X 4' INDUSTRIAL FLUORESCENT FIXTURE, PORCELAIN REFLECTOR, ELECTRONIC BALLAST.	_____ P _____	_____ P _____	PROCESS WATER ("P" WATER) LINE
	CIRCUIT BREAKER		COMPACT WALL-MOUNTED LOW WATTAGE HPS FIXTURE WITH WIRE GUARD & SINGLE FACTORY INSTALLED FUSE	_____ PW _____	_____ PW _____	PROTECTED WATER OR PLANT WATER (PW)
	MANUAL TRANSFER SWITCH		EMERGENCY LIGHT UNIT WITH 2-6 VOLT, 12 WATT SEALED BEAM HALOGEN LAMPS WITH WALL MOUNTING BRACKET	_____ RD _____	_____ RD _____	REFRIGERANT DISCHARGE LINE (RD)
	SELF CONTAINED UTILITY METERING		LANE LIGHTING - HEAVY DUTY ALUMINUM HOUSING WITH ENCLOSED REFLECTOR & TEMPERED GLASS LENS W/AUTO REGULATOR BALLAST. ASYMMETRIC PATTERN	_____ RS _____	_____ RS _____	REFRIGERANT SUCTION LINE (RS)
			WIRE	_____ V _____	_____ V _____	VENT LINE (V)
			CONDUIT			



SYMBOLS AND PATTERNS

STANDARD D2-04

NOTE:

ALL SYMBOLS AND PATTERNS ON THIS DRAWING ARE PROPOSED UNLESS OTHERWISE NOTED.

Paul Kovacs
 APPROVED..... CHIEF ENGINEER DATE 7-1-2009..

ELECTRICAL AND MECHANICAL ITEMS

	OR		QUANTITY AND DIRECTION OF THE AIR FLOW		OR		SPLITTER DAMPER		GLOBE VALVE
	OR		DUCT SIZE (FIRST FIGURE SIZE OF SHOWN, SECOND FIGURE SIZE OF SIDE NOT SHOWN.)				PLUG VALVE WITH MEMORY STOP (BALANCING)		BUTTERFLY VALVE
			SUPPLY DUCT SECTION				PLUG VALVE		CHECK VALVE
	OR		RETURN OR EXHAUST DUCT SECTION				SOLENOID VALVE		ANGLE GATE VALVE
	OR		DUCT DROPS IN THE DIRECTION OF FLOW				TEMPERATURE CONTROL VALVE		CONCENTRIC REDUCER
	OR		DUCT RISES IN THE DIRECTION OF FLOW				THREE-WAY TEMPERATURE CONTROL VALVE DIAPHRAGM		ECCENTRIC REDUCER
	OR		TURNING VANES				THREE-WAY TEMPERATURE CONTROL VALVE TOP VIEW		ORIFICE FLANGE
	OR		8" THROAT DIAMETER CEILING DIFFUSER; AIR FLOW -- 100 CFM				PRESSURE REDUCING VALVE (NOS. = INITIAL AND FINAL PRESSURE - PSIG)		CROSSOVER
	OR		BALANCING OR VOLUME DAMPER				AIR PRESSURE REDUCING STATION (NO. CORRESPONDS WITH AIR PRESSURE REDUCER SCHEDULE)		PIPE GUIDE
	OR		MOTOR OPERATED DAMPER				SAFETY VALVE (NOS. = PRESSURE SETTING - PSIG)		EXPANSION JOINT (SLIP TYPE)
			FLEXIBLE DUCT				QUICK COUPLING (QC)		EXPANSION JOINT (BELLOWS TYPE)
			FIRE DAMPER				HORIZONTAL UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)		AIR ELIMINATOR (AIR VENT)
			SOUND ATTENUATOR				VERTICAL UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)		PIPE CAP
			ZONE DAMPER				CABINET TYPE UNIT HEATER (NO. CORRESPONDS WITH UNIT HEATER SCHEDULE)		STRAIGHT CROSS
			FLEXIBLE CONNECTION AT FAN OR EQUIPMENT				THERMOSTAT OR ROOM TEMPERATURE SENSOR		90° ELBOW
			EXTRACTOR				GATE VALVE		90° ELBOW TURNED DOWN
							FLOW SWITCH		90° ELBOW TURNED UP
							VENTURI FLOW METER AND FLOW TO BE INDICATED		SIDE OUTLET ELBOW TURNED DOWN
							CONNECTION BETWEEN NEW AND EXISTING		SIDE OUTLET ELBOW TURNED UP

NOTE:

ALL SYMBOLS AND PATTERNS ON THIS DRAWING ARE PROPOSED UNLESS OTHERWISE NOTED.


Paul Kovacs
APPROVED..... CHIEF ENGINEER..... DATE 7-1-2009.....

SHEET 4 OF 4




SYMBOLS AND PATTERNS


STANDARD D2-04




RIGHT OF WAY MARKER



RIGHT OF WAY MARKER (SPECIAL)




LETTERING DETAIL



* METHOD A- 4'-2" LONG BARS
* METHOD B- 2'-6" LONG BARS
SECTION B-B


RIGHT OF WAY MARKER



TYPICAL CENTERLINE MONUMENT AT MEDIAN BARRIER




TOP VIEW




BRONZE DOMED CAP


PERMANENT SURVEY MONUMENT




ACCESS COVER (RECESSED HINGE)



ALUMINUM DOMED CAP



PERMANENT SURVEY MONUMENT (SPECIAL)



MONUMENT POST

APPROVED: *Paul Kovacs* CHIEF ENGINEERING OFFICER DATE: 1-1-2007

DATE	REVISIONS
3-01-2019	CHANGED TO CONSTANT-SLOPE MEDIAN BARRIER
7-01-2010	NEW MONUMENT AND BARRIER MARKERS



PERMANENT SURVEY MONUMENTS AND RIGHT-OF-WAY MARKERS STANDARD D3-02

PERMANENT DELINEATION SPACING				
REFLECTORS	MAINLINE		RAMP	
	TANGENT	CURVE	TANGENT	CURVE
* GUARDRAIL	100'	100'	100'	100' (R >= 1,050') 50' (R < 1,050')
* BARRIER WALL (DOUBLE FACE)	100'	100'	100'	100' (R >= 1,050') 50' (R < 1,050')
* BARRIER WALL (SINGLE FACE)	100'	100'	100'	100' (R >= 1,050') 50' (R < 1,050')
SHOULDER NARROWING	3 @ 15'	3 @ 15'	3 @ 15'	3 @ 15'
BRIDGE APPROACHES	3 @ 15'	3 @ 15'	3 @ 15'	3 @ 15'
* BRIDGE PARAPET	50'	50'	50'	50'
* NOISE ABATEMENT WALL (CRASH WORTHY)	100'	100'	100'	100' (R >= 1,050') 50' (R < 1,050')
ROADWAY DELINEATORS	MAINLINE		RAMP	
	TANGENT	CURVE	TANGENT	CURVE
POST MOUNTED DELINEATOR	200'	200'	200'	TABLE A
POST MOUNTED DELINEATOR (RAMP TAPERS AND TANGENTS)	100'	100'	NA	NA
TEMPORARY DELINEATION SPACING				
	TANGENT	REVERSE CURVE	SHIFT	TAPER
TEMPORARY CONCRETE BARRIER	50'	25'	25'	25'
* WHEN ADJACENT SHOULDER IS USED AS A TRAVELED LANE, USE SPACING REQUIREMENTS AS SHOWN FOR TEMPORARY DELINEATION.				

TABLE A	
REFLECTOR SPACING ON RAMP - CURVES	
RADIUS OF CURVE (FT.)	SPACING ALONG CURVE (FT.)
LESS THAN 1050	50
1050-1299	100
1300-1999	125
2000-2999	150
3000-3999	175
MORE THAN 3999	200

GENERAL NOTES:

EMERGENCY TURNAROUNDS DELINEATION - THE FOLLOWING DELINEATION SHOULD BE INSTALLED ON THE LEFT SIDE OF THE PAVEMENT APPROACHING EMERGENCY TURNAROUNDS.

- A. ONE-HALF OF A MILE IN ADVANCE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFLECTOR UNIT OVER THREE AMBER REFLECTOR UNITS.
- B. ONE-FOURTH OF A MILE IN ADVANCE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFLECTOR UNIT OVER TWO AMBER REFLECTOR UNITS.
- C. AT A POINT NEAR THE INTERSECTION OF THE EDGE OF THE LEFT SHOULDER AND NEAR EDGE OF THE EMERGENCY TURNAROUNDS ONE WHITE REFLECTOR UNIT OVER ONE AMBER REFLECTOR UNIT.

NOTES FOR ROADWAY DELINEATORS, POST MOUNTED INSTALLATION:


1. A. MAINLINE-SINGLE WHITE REFLECTOR UNITS SHALL BE PLACED CONTINUOUSLY ON THE RIGHT AND SINGLE AMBER REFLECTOR UNITS SHALL BE PLACED ON THE LEFT ON MAIN LINE SECTIONS WITHOUT BARRIER WALL.
- B. RAMPS-SINGLE REFLECTOR UNITS SHALL BE PLACED ON THE OUTSIDE OF ALL CURVED SECTIONS OF RAMPS, SINGLE WHITE SHALL BE PLACED ON THE RIGHT SIDE AND AMBER ON THE LEFT SIDE. THE DELINEATORS SHALL BE OVERLAPPED FOR A SHORT DISTANCE TO CLEARLY INDICATE WHERE DELINEATION ON ONE SIDE OF THE RAMP ENDS AND DELINEATION ON THE OTHER SIDE APPEARS.
- C. DOUBLE WHITE REFLECTOR UNITS SHALL BE PLACED ON THE RIGHT AT ALL ACCELERATION AND DECELERATION LANES.
2. REFLECTORS SHALL BE MOUNTED ON SUPPORTS SUCH THAT THE TOP OF REFLECTORS IS FOUR FEET ABOVE THE ROADWAY EDGE AND TWO FEET OUTSIDE THE OUTER EDGE OF THE PAVED SHOULDER OR TWO FEET MINIMUM AND SIX FEET MAXIMUM OUTSIDE THE BACKS OF CURBS OR GUTTERS.
3. IN ALL CASES, THE COLOR OF THE REFLECTORS SHALL BE THE SAME AS THE ADJACENT EDGE LINE EXCEPT AS SPECIFIED IN GENERAL NOTES.
4. POST MOUNTED REFLECTORS SHALL BE PLACED CONTINUOUSLY AS NOTED ABOVE IN CONJUNCTION WITH GUARDRAIL INSTALLED.
5. THE PLACEMENT OF ROADWAY DELINEATOR "CIRCULAR REFLECTORS" SHALL BE USED FOR ALL MINOR PROJECTS WHICH HAVE A LENGTH OF LESS THAN 5 MILES. THE PLACEMENT OF ROADWAY DELINEATOR "RECTANGULAR REFLECTORS" SHALL BE USED FOR ALL MAJOR PROJECTS WHICH HAVE A LENGTH GREATER THAN 5 MILES. ALL ROADWAY DELINEATORS WITHIN A ROADWAY SEGMENT SHALL BE OF THE SAME TYPE.

NOTES FOR GUARDRAIL AND BARRIER WALL REFLECTOR:


1. REFLECTORS TYPE B AND TYPE C SHALL HAVE REFLECTIVE SURFACE ON ONE SIDE ONLY.




DATE	REVISIONS
3-01-2019	CHANGED BARRIER TO CONSTANT-SLOPE SHAPE
3-31-2017	REVISED PERM. DELINEATION SPACING TABLE
3-31-2016	REVISED DELINEATOR ATTACHMENT TO POST
3-11-2015	REVISED NOTES
02-07-12	REVISED REFLECTOR MARKER TYPE C DIMENSION
11-01-12	REVISED NOTES, TABLE AND DELINEATION SPACING



TANGENT PLACEMENT



INTERCHANGE RAMP PLACEMENT




SINGLE UNIT DOUBLE UNIT


CIRCULAR REFLECTORS

SINGLE UNIT DOUBLE UNIT


RECTANGULAR REFLECTORS



ROADWAY DELINEATOR INSTALLATION



**SECTION A-A
STEEL- 1.12 LBS/FT.**



STEEL POST


NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.

APPROVED: *Paul Kovacs*
CHIEF ENGINEERING OFFICER
DATE: 7-1-2009


SHEET 2 OF 3

ROADWAY DELINEATORS AND REFLECTORS


STANDARD D4-07




CROSS-SECTION
TEMPORARY CONCRETE BARRIER




BARRIER OR PARAPET
REFLECTOR INSTALLATION




REFLECTOR, TYPE C




PLAN



SECTION A-A




SECTION B-B



REFLECTOR, TYPE B

REFLECTOR INSTALLATION ON GUARDRAIL
AT BRIDGE APPROACHES

ALSO SEE SHEET 1 IN THIS SERIES
FOR ADDITIONAL INFORMATION



SECTION C-C

NOTE:
SEE SHEET 1 OF THIS SERIES FOR NOTES.


SHEET 3 OF 3




ROADWAY DELINEATORS
AND REFLECTORS

STANDARD D4-07

APPROVED: *Paul Kovacs*
CHIEF ENGINEERING OFFICER DATE: 7-1-2009




PLAN



*FOR PREFERENTIAL LANE, SEE DETAIL A BELOW

SECTION A-A

ROADWAY AND SHOULDER STRIPING - NEW CONSTRUCTION



DETAIL A - PREFERENTIAL LANE STRIPING

GENERAL NOTES:

1. DIAGONAL SHOULDER STRIPING REQUIRED WHERE THE SHOULDER WIDTH IS LESS THAN STANDARD.
2. ROADWAY MARKING MATERIALS TO BE USED ON FINISHED CONCRETE SURFACE AND ASPHALT SURFACE SHALL BE AS SHOWN ON THE PLANS.
3. WHERE THE GUARDRAIL ENCROACHES ON THE SHOULDER THE DIAGONAL MARKINGS SHALL EXTEND AS CLOSE TO THE FACE OF THE RAIL AS POSSIBLE.
4. ALL PERMANENT LANE LINES AND EDGE LINES SHALL BE GROOVED, ON ROADWAY SURFACES, UNLESS OTHERWISE NOTED.
5. DIAGONAL STRIPING SHALL BE SURFACE APPLIED.
6. GORE STRIPING (CHEVRON) SHALL BE SURFACE APPLIED.
7. ALL LANE LINES AND EDGE LINES SHALL BE SURFACE APPLIED ON BRIDGES.
8. PAVEMENT MARKINGS SHALL NOT BE GROOVED AT THE CASH SIDE OF MAINLINE TOLL PLAZAS OR THE OPEN ROAD TOLLING (ORT), 100' CONTINUOUSLY REINFORCED CONCRETE (CRC) PAVEMENT SECTION OF MAINLINE UNDER MONOTUBES.


FOR RUMBLE STRIP DETAILS SEE STANDARD DRAWING D7

APPROVED, *Paul Kovacs* CHIEF ENGINEERING OFFICER DATE 7-1-2009


DATE	REVISIONS
3-01-22	REVISED EDGE LINES TO 6"
3-01-21	ADDED PREF. LANE STRIPING
3-01-20	REVISED EDGE LINE TO BE 4" MIN.
3-31-16	REVISED NOTES
3-31-14	REVISED NOTES
11-01-12	REVISED EDGE LINE OFFSET, REVISED NOTES
2-07-12	REVISED NOTES
7-01-09	ADDED LINE GROOVING NOTES

PERMANENT PAVEMENT MARKINGS
MAINLINE


STANDARD D5-09




**EXIT - SINGLE LANE RAMP
LANE THREE TERMINATION**




EXIT - SINGLE LANE LOOP RAMP - PARALLEL TYPE
SEE SHEET 4 FOR SPEED REDUCTION MARKINGS




EXIT - SINGLE LANE RAMP - LANE DROP




EXIT - TWO LANE PARALLEL RAMP




EXIT - SINGLE LANE RAMP - TAPER TYPE



EXIT - SINGLE LANE RAMP WITH AUX LANE - TAPER TYPE



EXIT - TWO LANE RAMP



NOTE:
PAVEMENT MARKING LETTERS AND SYMBOLS-ONLY AND ARROW ARE TO BE TYPICALLY PLACED AT 1/2 MILE EXIT ONLY GUIDE SIGN, AT GORE EXIT GUIDE SIGN AND APPROXIMATELY HALFWAY BETWEEN THE TWO.

GENERAL NOTES:

- RUMBLE STRIPS SHALL BE INSTALLED BETWEEN THE THEORETICAL GORE AND TAPER WHEN LENGTHS (L) OF AUXILIARY LANES, ACCELERATION LANES OR DECELERATION LANES, ARE GREATER THAN 1000'.
- ROADWAY MARKING MATERIALS TO BE USED ON FINISHED CONCRETE SURFACE AND ASPHALT SURFACE SHALL BE AS SHOWN ON THE PLANS.
- ALL LANE LINES AND EDGE LINES SHALL BE GROOVED.
- GORE STRIPING (CHEVRON) SHALL BE SURFACE APPLIED.
- LETTERS AND SYMBOL MARKING SHALL BE SURFACE APPLIED.
- DOTTED LINES SHALL CONSIST OF 3' LINE AND 9' GAPS.

Paul Kovacs
APPROVED DATE 7-1-2009
CHIEF ENGINEERING OFFICER





DATE	REVISIONS
3-01-2022	REVISED EDGE LINES TO 6"
3-01-2021	ADD SPEED REDUCTION MARKING DETAIL AND MOVED RUMBLE STRIP DETAILS TO D7
3-01-2019	UPDATE DIMENSION FOR 1-LANE ENTRANCE & ADD 1-LANE EXIT TERMINAL WITH AUX LANE
3-31-2017	REVISED NOTES
3-31-2016	REVISED NOTES, ADDED IPO PAVEMENT MARKING DETAIL.

SHEET 1 OF 4



**PERMANENT PAVEMENT MARKINGS
RAMPS**

STANDARD D6-10



* RUMBLE STRIP SHALL BE ADDED WHEN ALONG EXIT LOOP RAMP AND LEFT SHOULDER IS 10' WIDE


Paul Kovacs
 APPROVED CHIEF ENGINEERING OFFICER DATE 7-1-2009

SEE SHEET 1 IN THIS SERIES FOR GENERAL NOTES.


SHEET 3 OF 4

PERMANENT PAVEMENT MARKINGS
 RAMP

STANDARD D6-10




**SPEED REDUCTION MARKING FOR EXIT LOOP RAMP
SINGLE LANE, FROM PARALLEL TYPE EXIT**



* NUMBER OF SPACES MAY INCREASE WHEN INDICATED ON THE PLANS, OR WHEN JUSTIFIED BASED ON SIGHT DISTANCE OR OTHER FIELD CONDITIONS

**SPEED REDUCTION MARKING FOR EXIT LOOP RAMP
SINGLE LANE, FROM C-D ROAD**




SPEED REDUCTION MARKING DETAIL

SPEED REDUCTION MARKING NOTES:

- SR-1. SPEED REDUCTION MARKINGS SHALL BE WHITE IN COLOR, BE 12" WIDE AND BE PLACED PERPENDICULAR TO THE EDGE LINE. THE MARKINGS SHALL TOUCH THE EDGE LINE AND EXTEND INTO THE LANE BY THE LENGTH INDICATED. THE MARKINGS ARE NOT GROOVED INTO THE PAVEMENT.
- SR-2. SPACINGS SHALL VARY FROM LONGER SPACES TO SHORTER SPACES IN THE DIRECTION OF TRAFFIC. THE SPACES SHALL BE MEASURED ALONG THE RAMP BASELINE AND SHALL BE AS INDICATED ON THE DETAIL.
- SR-3. SPEED REDUCTION MARKINGS SHALL ONLY BE USED ON EXIT LOOP RAMPS. PAYMENT FOR SPEED REDUCTION MARKINGS WILL BE FOR PAVEMENT MARKING LINE, 12" OF THE PERMANENT PAVEMENT MARKING TYPE USED ON THE RAMP.
- SR-4. THIS DETAIL SHOWS PLACEMENT OF SPEED REDUCTION MARKINGS. FOR PLACEMENT AND TYPE OF EDGE LINES AND OTHER RAMP PAVEMENT MARKINGS, REFER TO OTHER DETAILS ON THE STANDARD DRAWINGS AND PLANS.


APPROVED: *Paul Kovacs* DATE 7-1-2009
CHIEF ENGINEERING OFFICER






PREFERENTIAL LANE RUMBLE STRIP PLACEMENT - PLAN VIEW

USE WHEN SHOWN ON PLANS, MAINLINE MEDIAN SHOULDER IS AT LEAST 16' WIDE AND USED AS PREFERENTIAL LANE



SECTION C-C

PREFERENTIAL LANE RUMBLE STRIP PLACEMENT - SECTION VIEW




PLAN DETAIL A


SECTION A-A

SECTION B-B

ASPHALT SHOULDER RUMBLE STRIP DETAILS




TYPICAL MAINLINE RUMBLE STRIP PLACEMENT - PLAN VIEW



SECTION D-D

TYPICAL MAINLINE RUMBLE STRIP PLACEMENT - SECTION VIEW



PLAN DETAIL A

SECTION A-A

SECTION B-B

CONCRETE SHOULDER RUMBLE STRIP DETAILS


APPROVED: *Paul Kovacs* DATE: 3-1-2021
CHIEF ENGINEERING OFFICER

DATE	REVISIONS
3-01-2022	REVISED EDGE LINES ON SECTIONS C-C & D-D


Illinois Tollway

SHOULDER RUMBLE STRIP DETAILS


STANDARD D7-01



DETAIL A




DETAIL B



* MARKER TO BE INSTALLED WHEN LENGTHS OF AUXILIARY LANES ARE GREATER THAN 1000'.

DETAIL C



MAINLINE

RAISED PAVEMENT LANE MARKER DETAILS

NOTES:

1. USE OF RAISED PAVEMENT LANE MARKERS SHALL BE IN ACCORDANCE WITH THE IL TOLLWAY, ROADWAY SIGNING AND PAVEMENT MARKING GUIDELINES.
2. FOR COLLECTOR-DISTRIBUTOR (C-D) ROADWAYS, PLACE ONE-WAY CRYSTAL MARKER, 2 EACH AT 100' CENTERS. USE DETAIL A.
3. FOR MULTI LANE DIRECTIONAL RAMPS, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 50' CENTERS. USE DETAIL B.
4. FOR AUXILIARY LANES, PLACE ONE-WAY CRYSTAL MARKER, 1 EACH AT 48' CENTERS. USE DETAIL C.





APPROVED *Paul Kovacs* CHIEF ENGINEERING OFFICER DATE 7-1-2009

DATE	REVISIONS
3-01-2019	ADDED NEW NOTE 1
3-31-2016	REVISED NOTES 1.
11-01-2012	REVISED DETAIL C.




RAISED PAVEMENT
LANE MARKER


STANDARD D8-03




CROSS-BOLT CONNECTION DETAIL




CROSS-BOLT CONNECTION HARDWARE
2 SETS OF HARDWARE NEEDED FOR EACH BARRIER




LEAVE-OUT BLOCK TOP



LEAVE-OUT BLOCK BOTTOM



TOP SLEEVE
PIPE, 1-1/2" SCH. 40 PVC



BOTTOM SLEEVE
PIPE, 1-1/2" SCH. 40 PVC

NOTES




1. EACH F SHAPE BARRIER UNIT SHALL BE CLEARLY MARKED WITH "IL TOLLWAY F SHAPE", THE PRODUCER'S MARK AND THE DATE OF MANUFACTURE. THE MARKING SHALL BE RECESSED IN THE BARRIER BY 1/2" OR PAINTED THEREON WITH WATERPROOF PAINT/INK.
2. THE INSERT FOR THE 1/2" BOLT AT THE TOP OF THE BARRIER SHALL BE CAPABLE OF 3000 LB PULL-OUT STRENGTH.
3. AT LOCATIONS WHERE THE BARRIER SEPARATES OPPOSING FLOWS OF TRAFFIC, TYPE C REFLECTORS SHALL BE ON BOTH SIDES OF BARRIER. SEE STANDARD D4 FOR DIMENSIONS OF TYPE C REFLECTOR.
4. ALL EXPOSED CONCRETE EDGES SHALL HAVE A 3/4" CHAMFER, EXCEPT WHERE SHOWN OTHERWISE.
5. REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-31 (ASTM A706), GRADE 60, DEFORMED BARS.
6. REINFORCEMENT BAR BENDING DETAILS SHALL BE IN ACCORDANCE WITH THE LATEST "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES, ACI 315.
7. REINFORCEMENT BAR BENDING DIMENSIONS ARE OUT TO OUT.
8. COVER (CL) IS 1-1/2" UNLESS OTHERWISE INDICATED.
9. CONCRETE SHALL BE PORTLAND CEMENT CONCRETE, CLASS PS (4000 PSI).
10. TWO OF EACH LEAVE-OUT BLOCK AND TWO OF EACH SLEEVE NEEDED FOR EACH BARRIER.

REVISIONS	
DATE	DESCRIPTION
03-01-2022	REVISED NOTE 2.
03-01-2021	LEAVE-OUT BLOCKS ADDED TO ELEV. VIEW-END, AND TEXT TO PLAN VIEW.
	LEAVE-OUT BLOCK TOLERANCE ADDED.


TEMPORARY CONCRETE BARRIER WITH CROSS-BOLT CONNECTION

VERSION: 2022-03 STANDARD: D10-02 SHEET: 1 OF 2


APPROVED BY: *Paul Kovacs* DATE: 01/13/2021
CHIEF ENGINEERING OFFICER




s1 BAR
No. 5 REBAR




d3 BAR
No. 4 REBAR




d1 BAR
No. 4 REBAR




u2 BAR
No. 4 REBAR



u1 BAR
No. 4 REBAR



d2 BAR
No. 4 REBAR



ISOMETRIC VIEW
(REINFORCEMENT)

APPROVED BY: *Paul Kovacs*
CHIEF ENGINEERING OFFICER
DATE: 01/13/2021

Illinois Tollway

TEMPORARY CONCRETE BARRIER WITH CROSS-BOLT CONNECTION

VERSION: 2022-03 STANDARD: D10-02 SHEET: 2 OF 2