


Illinois Tollway Base Sheet Revisions

Section M Base Sheet Drawings	
Drawing	Modification Summary
	Effective: 03-01-2026
Drainage (DRN)-Series 600	
M-DRN-602	BIOSWALE
Sheet 1	Added Note to Designer 3.
M-DRN-607	NOISE ABATEMENT WALL DRAINAGE DETAILS (ROADWAY SIDE)
Sheet 1	Added a 1'-0" minimum clearance between the drilled shaft and the edge of trench for concrete pipe in plan view.
	Changed drainage structures to Catch Basin, Type G-3, Modified.
	Added Note to Designer 3.
M-DRN-609	STATION AND OFFSET FOR DRAINAGE STRUCTURES
M-DRN-610	SINGLE FACE CONCRETE BARRIER WITH DRAINAGE STRUCTURE


 **New Sheet**

 **Retired Standard**




PROFILE VIEW


DESIGN ELEMENTS	UNITS	VALUES
DRAINAGE AREA	X (ACRES)	
STORAGE VOLUME	V (CU. YD.)	
CHECK DAM TOP WIDTH	A (FEET)	
CHECK DAM HEIGHT	B (FEET)	
MANHOLE	D (DIAMETER)	
MANHOLE-GRATE	TYPE	
HORIZONTAL PIPE (RCP) ₁	P ₁ (DIAMETER)	
HORIZONTAL PIPE (RCP) ₁	L ₁ (FEET)	
HORIZONTAL PIPE (RCP) ₁	S ₁ (SLOPE)	
HORIZONTAL PIPE (RCP) ₂	P ₂ (DIAMETER)	
HORIZONTAL PIPE (RCP) ₂	L ₂ (FEET)	
HORIZONTAL PIPE (RCP) ₂	S ₂ (SLOPE) (%)	
RESTRICTOR PLATE-DETAIL	SHAPE	
2-YEAR RELEASE RATE	CFS	
100-YEAR RELEASE RATE	CFS	
HEADWALL TYPE III (1:10)	PIPE DIAMETER	
SLOPED HEADWALL TYPE III (1:4)	PIPE DIAMETER	
HIGH WATER ELEVATION	HWL (FEET)	
TOP OF STRUCTURE ELEVATION	T/STR (FEET)	
UPSTREAM FLOWLINE	U F/L (FEET)	
DOWNSTREAM FLOWLINE	D F/L (FEET)	
2-YEAR ORIFICE INVERT ELEV.	(FEET)	
100-YEAR ORIFICE INVERT ELEV.	(FEET)	




RESTRICTOR PLATE DETAIL



RESTRICTOR PLATE DETAIL



RESTRICTOR PLATE DETAIL



RESTRICTOR PLATE DETAIL

SAMPLE RESTRICTOR PLATE DETAILS

OUTLET CONTROL STRUCTURE (CHECK DAM)

NOTES:

1. ALL SLOPES ARE EXPRESSED AS UNITS OF VERTICAL DISPLACEMENT TO UNITS OF HORIZONTAL DISPLACEMENT. (V:H).
2. THE CONTRACTOR HAS THE OPTION TO USE A CONCRETE RESTRICTOR PLATE THAT IS PRECAST WITHIN THE DRAINAGE STRUCTURE.

NOTE TO DESIGNER
 THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTE TO DESIGNER
 1. DSE SHALL DESIGN STEEL ANGLE BOLTS AND FASTENERS FOR THE STEEL RESTRICTOR PLATES. DETAILS ARE TO BE PROVIDED ON THIS SHEET.




OUTLET CONTROL STRUCTURE CHECK DAM DETAILS

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTES TO DESIGNER

- FOR SLOPES 1:3 OR FLATTER, PLACE A MINIMUM OF ONE CONCRETE COLLAR AT THE MIDDLE PIPE JOINT IF SLOPE DRAIN LENGTH \leq 80 FEET. IF SLOPE DRAIN LENGTH $>$ 80 FEET, PLACE CONCRETE COLLARS AT A MAXIMUM 40 FOOT SPACING.
- FOR SLOPES STEEPER THAN 1:3, PLACE CONCRETE COLLARS AT A MAXIMUM 20 FOOT SPACING.
- THE AIR VENT IS REQUIRED WHEN $HW/D \geq 0.8$ TO PREVENT CAVITATION.




SLOPE DRAIN



CATCH BASIN, TYPE G-3 DRAINAGE STRUCTURE PLAN

RESTRICTOR PLATE DETAIL




SECTION A-A


NOTES:

- THE STORM SEWERS, CONCRETE COLLAR, CATCH BASIN, TYPE G-3, RESTRICTOR PLATE, ANGLES AND HARDWARE AND FRAME AND GRATE, SHALL BE INCLUDED IN THE COST OF SLOPE DRAIN OF THE DIAMETER SPECIFIED.
- SEE ILLINOIS TOLLWAY STANDARD B8 FOR DIMENSION OF CATCH BASIN, TYPE G-3 STRUCTURE.
- THE TOP OF THE CATCH BASIN, TYPE G-3 SHALL BE CUT IN THE FIELD TO MATCH THE PROPOSED EMBANKMENT SLOPE.
- THE CONTRACTOR HAS THE OPTION TO USE A CONCRETE RESTRICTOR PLATE THAT IS PRECAST WITHIN THE DRAINAGE STRUCTURE.
- PIPE MATERIAL SHALL BE HDPE WITH SMOOTH INTERIOR OR EPOXY COATED CORRUGATED GALVANIZED STEEL PIPE OF THE SIZE SPECIFIED.
- THE MINIMUM CONCRETE COLLAR WIDTH SHALL BE $D + 24"$.
- ALL STEEL ANGLES AND PLATES SHALL BE GALVANIZED AFTER FABRICATION.
- STEEL PLATE AND ANGLES SHALL BE IN ACCORDANCE WITH AASHTO M 270 GRADE 36.
- ANGLES SHALL BE 3" X 3" X 3/8".
- VERTICAL ANGLES SHALL EXTEND FROM THE BOTTOM OF THE CATCH BASIN TO THE TOP OF THE RESTRICTOR PLATE.
- HORIZONTAL ANGLES SHALL EXTEND FROM VERTICAL ANGLE TO VERTICAL ANGLE.

SLOPE DRAIN PIPE NO.	DIAMETER (D) (IN)	LENGTH (FT)	CONCRETE COLLAR			CATCH BASIN, TYPE G-3			INV.	TOP OF RESTRICTOR PLATE ELEVATION	U/S DRAINAGE STRUCTURE NO.	D/S DRAINAGE STRUCTURE NO.	PAY ITEM
			STATION	OFFSET (FT)	OFFSET (LT/RT)	STATION	OFFSET (FT)	OFFSET (LT/RT)					




ANGLE FASTENER DETAIL



STEEL ANGLE BOLTING DETAILS



SLOPE DRAIN




BIOSWALE NO.	BIOSWALE TYPE	BEGIN STATION	END STATION	PREP/AMENDED TOPSOIL THICKNESS (t)	BIOSWALE BASE (D)

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTES TO DESIGNER

- ALL PIPE UNDERDRAINS SHALL EITHER OUTLET AT GRADE OR TO A DRAINAGE STRUCTURE AND GRAVITY DRAIN.
- ALL PIPE UNDERDRAINS SHALL HAVE AN INLET ON THE UPSTREAM END AND EVERY 500' MINIMUM TO SERVE AS A CLEAN-OUT.
- ARTICULATED CONCRETE BLOCK REVETMENT SYSTEM (ACBRS) SHALL NOT BE PLACED WITHIN BIOSWALES UNLESS USED FOR MAINTENANCE ACCESS CROSSINGS PER DDM ARTICLE 6.3.2.




NOTES:

- THE ENDS OF THE PIPE UNDERDRAIN OUTLET AT GRADE SHALL BE PROTECTED BY A PERMANENT RODENT SHIELD IN ACCORDANCE WITH STANDARD B24.


Illinois Tollway

BIOSWALE


VERSION: 2026-03	BASE SHEET: M-DRN-602	SHEET: 1 OF 1
---------------------	--------------------------	------------------



TOP VIEW




SECTION A-A



SECTION B-B

RESTRICTOR TYPE					
1	2	3	4	5	6
RE - ENTRANT TUBE	SHARP EDGES	SQUARE EDGED	RE - ENTRANT TUBE	SQUARE EDGED	ROUNDED
LENGTH 1/2 TO 1 DIA.		STREAM CLEARS SIDES	LENGTH: 2-1/2 DIA.	LENGTH: 2-1/2 DIA.	
C=.52	C=.61	C=.61	C=.73	C=.82	C=.98

RESTRICTOR TYPES
VALUES OF "C" FOR CIRCULAR
AND SQUARE ORIFICES




- NOTES TO DESIGNER**
- DSE SHALL DESIGN STEEL ANGLE BOLTS AND FASTENERS FOR THE RESTRICTOR PLATES. DETAILS ARE TO BE PROVIDED ON THIS SHEET.
 - DSE SHALL PROVIDE REINFORCEMENT DETAILS. DESIGN SHALL BE IN ACCORDANCE WITH AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, LATEST EDITION, WITH IL-120 OR HL-93 LOADING REQUIREMENTS, WHICHEVER GOVERNS (REFER TO STRUCTURE DESIGN MANUAL).
 - ALL DIMENSIONS DESIGNATED "X" ARE REQUIRED AND SHALL BE UPDATED BY THE DSE.
- NOTE TO DESIGNER**
- THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

STRUCTURE NUMBER	* STATION	* OFFSET (FT.)	OFFSET LT/RT	STRUCTURE TYPE	FRAME AND GRATE TYPE	F&G RIM ELEV		INV D ₁₀₀	D ₁₀₀ (IN.)	INV D ₂	D ₂ (IN.)	INLET PIPE DIAMETER (IN.)	OUTLET PIPE DIAMETER (IN.)	TOP OF RESTRICTOR PLATE ELEV	RESTRICTOR TYPE	CLEARANCE (FT.)	2 YEAR WATER SURFACE ELEVATION	100 YEAR WATER SURFACE ELEVATION
						LT	RT											


* SEE TOP VIEW FOR STRUCTURE STATION AND OFFSET



CATCH BASIN TYPE G (SPECIAL) WITH RESTRICTOR



PLAN - STRUCTURE MOUNTED NOISE ABATEMENT WALL EXAMPLE



PLAN - RETAINING WALL EXAMPLE




NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.


- NOTES TO DESIGNER**
- THIS BASE SHEET REPRESENTS THE TYPICAL DETAILS FOR BUMP-OUT RETAINING WALLS OR MOUNTED, NOISE ABATEMENT WALLS. THE DSE IS RESPONSIBLE FOR COMPLETING THE TABLES AND INCLUDING THEM IN THEIR CONTRACT PLANS. IF ANY OF THE DESIGN PARAMETERS IN THE ILLINOIS TOLLWAY STANDARD ARE EXCEEDED, THE DSE WILL BE RESPONSIBLE FOR DESIGN CALCULATIONS AND DETAILS FOR THOSE COMPONENTS. THE GP&E SHEET AND REMAINING NAW PLANS SHALL BE IN ACCORDANCE WITH ILLINOIS TOLLWAY STRUCTURE DESIGN MANUAL ARTICLES 6.2.5 AND 23.3.
 - USE SPECIALTY PANEL AND POST SPACING AT END OF WALL TO ACCOMMODATE TYPICAL 11'-8" POST SPACING ALONG THE STRAIGHT LENGTH OF WALL. POST SPACING SHOULD NOT EXCEED LIMITS WITHIN THE ILLINOIS TOLLWAY STANDARD. IF LIMITS ARE EXCEEDED, DSE TO DESIGN AND DETAIL ALL COMPONENTS. THE "SPX" DESIGNATION FOR SPECIALTY PANELS SHOULD BE USED FOR ALL PANELS WITHIN BAY WITH THE SAME WIDTH.
 - BUMP-OUT MOUNTED NAW DETAILS MAY BE USED WITH SYSTEMWIDE STRUCTURE MOUNTED NAW DETAILS SHOWN IN STANDARD G12 AND M-BRG-529. DSE TO UPDATE ACCORDINGLY FOR SYSTEMWIDE GEOMETRY.
 - THIS SHEET IS NOT TO SCALE. DESIGNER TO DETERMINE APPROPRIATE SCALE ON GENERAL PLAN AND ELEVATION SHEET TO ACCURATELY REPRESENT REQUIRED INFORMATION.
 - A BYPASS STRUCTURE IS REQUIRED IF THE PEAK FLOW EXCEEDS THE CAPACITY OF THE STORMWATER TREATMENT SYSTEM'S INTERNAL OVERFLOW WEIR OR TO REDUCE THE SIZE OF THE STORMWATER TREATMENT SYSTEM.
 - ALL DIMENSIONS DESIGNATED "X" ARE REQUIRED AND SHALL BE UPDATED BY THE DSE.
 - TAPER RATE FOR MAINLINE INSTALLATIONS SHALL BE 30:1. TAPER RATE FOR RAMP AND C-D ROADWAYS SHALL NOT EXCEED THE RATES SHOWN IN AASHTO RDG TABLE 5-9.
 - THE CURB SHALL BE PAID FOR AS CONCRETE SUPERSTRUCTURE.

NOTE:


WORK POINTS (WP) ARE REFERENCED ALONG CENTERLINE OF NAW PANELS AND CENTERLINE OF POSTS. STATIONS AND OFFSETS ARE MEASURED AT WP.




TYPICAL SECTION - GUTTER, TYPE G-3 OR GUTTER, TYPE G-2
(GUTTER, TYPE G-3 SHOWN)
(BALANCED SOIL LOAD, WHEN PANEL EMBEDMENT DEPTH IS ≤ 1 FT)



SECTION A-A
GUTTER, TYPE G-2N
(UNBALANCED SOIL LOAD, WHEN DRAINAGE STRUCTURE IS ON HIGH SIDE)



SECTION B-B
GUTTER, TYPE G-3N
(UNBALANCED SOIL LOAD, WHEN DRAINAGE STRUCTURE IS ON HIGH SIDE)




TYPICAL SECTION - GUTTER, TYPE G-3N OR GUTTER, TYPE G-2N
(GUTTER TYPE G-3N SHOWN)
(BALANCED SOIL LOAD, WHEN PANEL EMBEDMENT DEPTH IS > 1 FT.)


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.


- NOTES TO DESIGNER**
- FOR NOISE ABATEMENT WALL DETAILS, REFER TO ILLINOIS TOLLWAY STANDARD DRAWINGS G15 AND G16.
 - FOR THE SELECTION OF GUTTER TYPE, REFER TO ROADWAY DESIGN CRITERIA MANUAL, ARTICLE 2.6.6.
 - DESIGNER SHALL VERIFY SUFFICIENT CLEARANCE IS PROVIDED BETWEEN STORM SEWERS AND DRAINAGE STRUCTURES RELATIVE TO THE DRILLED SHAFTS. DRAINAGE STRUCTURE SHALL BE SIZED TO ACCOMMODATE STORM SEWER WALL PENETRATION.




TYPICAL SECTION - PIPE UNDERDRAIN




TYPICAL SECTION - DITCH AT THE TOP OF BACKSLOPE




TYPICAL SECTION - PIPE UNDERDRAIN ON HIGH FILL SLOPE



TYPICAL SECTION - GUTTER, TYPE G-3 OR GUTTER, TYPE G-2 (GUTTER, TYPE G-3 SHOWN)
(UNBALANCED SOIL LOAD, WHEN DRAINAGE STRUCTURE IS ON HIGH SIDE)



PLAN VIEW - PIPE UNDERDRAIN (AT SAG SHOWN)



TYPICAL SECTION - GUTTER, TYPE G-3 OR GUTTER, TYPE G-2 (GUTTER, TYPE G-3 SHOWN)
(BALANCED SOIL LOAD, WHEN PANEL EMBEDMENT DEPTH IS ≤ 1 FT)

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTES TO DESIGNER

- THE DETAILS SHOWN ARE ACCEPTABLE OPTIONS TO DRAIN THE AREA ADJACENT TO A NOISE ABATEMENT WALL (RESIDENTIAL SIDE). THE MOST FEASIBLE OPTION IS SITE SPECIFIC. IF GUTTER IS USED, REFER TO ROADWAY DESIGN CRITERIA MANUAL, ARTICLE 2.6.6 FOR THE SELECTION OF GUTTER TYPE. THE DESIGNER IS RESPONSIBLE FOR PROVIDING SUPPORTING DRAINAGE CALCULATIONS TO DETERMINE THE MOST FEASIBLE OPTION. THE DESIGNER IS ALSO RESPONSIBLE FOR DESIGNING AND DETAILING ALL DITCHES, DRAINAGE STRUCTURES AND STORM SEWERS ON THE DRAINAGE PLAN AND PROFILES.
- DETERMINE DIMENSION X TO OFFSET PIPE UNDERDRAIN TO AVOID CONFLICT WITH THE DRILLED SHAFTS.
- PIPE UNDERDRAINS SHALL MEET THE REQUIREMENTS OF DDM ARTICLE 9.7.2, DDM TABLE 9.3 AND STANDARD B24.
- FOR NOISE ABATEMENT WALL DETAILS, REFER TO ILLINOIS TOLLWAY STANDARD DRAWINGS G15 AND G16.

NOTES:


- FILL GAP WITH CLSM, GROUT OR CLASS SI CONCRETE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.
- PROVIDE JOINT FILLER BETWEEN THE STEEL POST AND GUTTER.




NOISE ABATEMENT WALL DRAINAGE DETAILS (RESIDENTIAL SIDE)

NOTES:


- FOR DRAINAGE STRUCTURES TYPE 4 OR TYPE 5, THE STORM SEWER SHALL BE TYPICALLY OFFSET 2.5' FROM THE CENTERLINE OF THE STRUCTURE FOR 15" OR 18" STORM SEWERS IN ORDER TO AVOID LIGHT POLE FOUNDATION CONFLICTS. 24" (MAXIMUM) STORM SEWERS SHALL BE CENTERED ON THE DRAINAGE STRUCTURE, UNLESS OTHERWISE NOTED IN THE DRAINAGE STRUCTURE SCHEDULE. STORM SEWER OFFSETS MAY VARY. STORM SEWER OFFSETS LISTED IN THE DRAINAGE STRUCTURE SCHEDULE "LT" AND "RT" ARE INTENDED AS MEANING RELATIVE TO THE DIRECTION OF THE ROADWAY ALIGNMENT. REFER TO STANDARD H1.
- UNLESS OTHERWISE INDICATED ON THE PLANS, THE PROPOSED STORM SEWER IS TO BE INSTALLED AT THE STRUCTURE CENTERLINE.




CATCH BASIN, TYPE G-3, MODIFIED WITH TYPE 20A FRAME AND GRATE




HEADWALL OR SLOPED HEADWALL



DRAINAGE STRUCTURES, TYPE 4 OR TYPE 5




PLAN VIEW



SECTION D-D


TYPE 20A, TYPE 22A FRAME & GRATE



PLAN VIEW
FRAME AND GRATE TYPE G-3 (CATCH BASINS TYPE G-2, G-3, G-3(M), G-4 AND G-5 ALL FOLLOW THE SAME DETAIL)

SECTION A-A


TYPE G-SERIES FRAME AND GRATE



PLAN VIEW

SECTION B-B

TYPE 8 GRATE



PLAN VIEW

SECTION C-C

TYPE 1 LID

CATCH BASINS AND MANHOLES WITH TYPE 8 GRATES AND CIRCULAR LIDS

NOTE TO DESIGNER
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



STATION AND OFFSET FOR DRAINAGE STRUCTURES

