

Illinois Tollway Base Sheet Revisions

| Section<br>M | Base Sheet Drawings                                 |  |                       |
|--------------|---|--|-----------------------|
|              | Drawing   | Modification Summary   | Effective: 03-01-2025 |
|              |   |  |                       |
|              | Plaza Electrical Work (Business System)-Series 2500 |  |                       |
|              |   |  |                       |
|              | M-BUS-2503  | Single Line Power Diagram  |                       |
|              |   | Removed reference to air compressor: VES Wash cabinet has a built-in compressor for nitrogen generator.<br>Revised to one UPS per plaza building to provide emergency power to IT, ITS and Tolling equipment.  |                       |
|              |   |  |                       |
|              | M-BUS-2505  | Fiber Interconnections Between Main and Remote Plazas  |                       |
|              |   | Added Watch Dog camera to security camera identification.<br>Added identification for MTS-1 manual transfer switch and MTS-2 manual transfer switch.   |                       |
|              |   |  |                       |
|              | M-BUS-2509  | Exterior Elevations - Main Plaza   |                       |
|              | Sheet 1   | Added the air terminal (lighting rods) on roof of plaza building.<br>Added note to designer: "Air terminal rods are to be installed and fixed to roof..."  |                       |
|              | Sheet 2   | Added exterior wall and roof details   |                       |
|              |   |  |                       |
|              | M-BUS-2512  | Mechanical Plan - Main Plaza   |                       |
|              |   | Updated details of Manual Transfer Switch MTS-1 and MTS-2.<br>Revised HVAC-01 and HVAC-02 model number for new refrigerant gas in BARD HVAC unit.  |                       |
|              |   |  |                       |
|              | M-BUS-2514  | Control Building Grounding Details - Main Plaza  |                       |
|              | Sheet 1   | Rearranged the original M-BUS-2514 to keep layout on Sheet 1 and moved grounding details to Sheet 2 for clarity<br>Added details for facility grounding of lighting protection system to improve efficiency of grounding triad loop  |                       |
|              | Sheet 2   | Moved grounding details from original M-BUS-2514 to this Sheet 2 for clarity   |                       |
|              |   |  |                       |
|              | M-BUS-2515  | Panelboard Schedules - Main Plaza  |                       |
|              |   | Convert breaker #31 from Air Compressor to Spare.<br>Convert breaker #37 from Line Conditioner to Spare.<br>Convert breakers #30 and #32 Line Conditioner to UPS-1 (Tolling).<br>Convert breaker #2 from UPS-1 to Spare.<br>For Panel UPS-1 change voltage to 120V/208V, change phase/wire to 1/3, change bus rating to 60A. |                       |
|              |   |  |                       |
|              | M-BUS-2516  | Video Power Junction Box Detail - Main Plaza   |                       |
|              |   | Added option for four power supplies (one per VES camera to connect).<br>Added air vents to enclosure.   |                       |

Illinois Tollway Base Sheet Revisions

| Section<br>M | Base Sheet Drawings                                 |  |                       |
|--------------|---|--|-----------------------|
|              | Drawing   | Modification Summary   | Effective: 03-01-2025 |
|              |   |  |                       |
|              | Plaza Electrical Work (Business System)-Series 2500 |  |                       |
|              |   |  |                       |
|              | M-BUS-2518A   | Loop Plan - AET 3-Lane Layout  |                       |
|              |   | Revised representation of pavement marking as solid lines and no RRPM within the limits of the CRC pavement.<br>Revised details of the piezo sensors and loops in each lane.<br>Added Legend for antennas, mainline loops, narrow loops and piezo sensors.             |                       |
|              |   |  |                       |
|              | M-BUS-2518B   | Loop Plan - AET 1-Lane Layout  |                       |
|              |   | Added Legend for antennas, mainline loops, narrow loops and piezo sensors.<br>Revised details of the piezo sensors and loops in each lane.   |                       |
|              |   |  |                       |
|              | M-BUS-2518C   | Loop Plan - AET 1-Lane Layout Single Monotube  |                       |
|              |   | Created details for single monotube with loops and piezo sensors.<br>Added mounting details of the junction box at the top of the vertical section of the monotube.<br>Added routing of the conduit for VES wash tubing .<br>Add details for VES wash tubing cut-out.  |                       |
|              |   |  |                       |
|              | M-BUS-2518D   | Ground Mounted VES Camera with VES Wash Tubing   |                       |
|              |   | Added details for ground mounted VES cameras on pedestal.<br>Added mounting details to attach the conduit for VES Wash tubing to the VES camera pedestal.  |                       |
|              |   |  |                       |
|              | M-BUS-2520  | Exterior Elevations - Remote Plaza   |                       |
|              |   | Added the air terminal (lighting rods) on roof of plaza building.<br>Added note to designer for lighting rods on top of the building   |                       |
|              |   |  |                       |
|              | M-BUS-2523  | Mechanical Plan - Remote Plaza   |                       |
|              |   | Revised HVAC-01 and HVAC-02 model number for new refrigerant gas in BARD HVAC unit.  |                       |
|              |   |  |                       |
|              | M-BUS-2526  | Panelboard Schedules- Remote Plaza AET Lanes   |                       |
|              |   | Convert breakers #25 and #27 to Spare.<br>Convert breakers #30 and #32 to UPS-2 spare.<br>Convert breaker #36 to Spare.<br>Change voltage on UPS-2 panelboard to 120V/208V.<br>Change phase/wire to 1/3.<br>Change bus rating to 60A.<br>Change mains to 30A, 2P, MCB. |                       |
|              |   |  |                       |

Illinois Tollway Base Sheet Revisions

| Section<br>M | Base Sheet Drawings                                 |  |                       |
|--------------|---|--|-----------------------|
|              | Drawing   | Modification Summary   | Effective: 03-01-2025 |
|              |   |  |                       |
|              | Plaza Electrical Work (Business System)-Series 2500 |  |                       |
|              | M-BUS-2527  | Video Power Junction Box Detail - Remote Plaza   |                       |
|              |   | Added option for four power supply (one per VES camera to connect).  |                       |
|              |   | Added air vents to enclosure.  |                       |
|              |   |  |                       |
|              | M-BUS-2536A   | Overhead Conduit Tray  |                       |
|              |   | Revised layout to show details of mounting provisions for the cable tray with all the parts and assembly required.   |                       |
|              |   | Added note to designer: " All values designated "X" are required..."   |                       |
|              |   | The old Note 1 was removed and Note 2 was renamed the new Note 1, the old Note 3 has been renamed Note 2   |                       |
|              |   |  |                       |
|              | M-BUS-2536B   | Overhead Conduit Tray  |                       |
|              |   | Part summary list was created and some notes revised and added new notes   |                       |
|              |   |  |                       |
|              | M-BUS-2538  | VES Wash System Single Cabinet Detail  |                       |
|              |   | Revised layout of VES Wash single cabinet to position the nitrogen tank and washing liquid reservoir from the left side to the right side of the cabinet assembly drawing. |                       |
|              |   | Remove exterior box for manual switches.   |                       |
|              |   | Revised assembly model number to: NS-GEN-SY-Y-0300   |                       |
|              |   | Revised Item A to be stainless steel enclosure.  |                       |
|              |   | Revised VES Wash cabinet manufacturer model number.  |                       |
|              |   | Expanded the Bil of Materials  |                       |
|              |   |  |                       |
|              | M-BUS-2539  | VES Wash System Panel Detail   |                       |
|              |   | Revised layout of the VES Wash cabinet to show two front doors and rearranged of components  |                       |
|              |   | Notes and layout revised of the VES Wash single cabinet.   |                       |
|              |   | Revised assembly model number to: NS-GEN-SY-Y-0300   |                       |
|              |   | Revised part number for Liquid Tank: NG-ECD-00314  |                       |
|              |   | Model of the VES cabinet revised to 48" wide with two doors configuration model Hammond # HN4FM604818S16 NEMA 3R   |                       |
|              |   | Modified equipment layout to fit a bigger washing liquid reservoir   |                       |
|              |   |  |                       |
|              | M-BUS-2540  | VES Wash System Flow Diagram and System  |                       |
|              |   | Revised Bill of Material spreadsheet   |                       |
|              |   | Revised several notes  |                       |
|              |   | Inlet valves details removed   |                       |
|              |   | Remove details for external switches   |                       |
|              |   |  |                       |

Illinois Tollway Base Sheet Revisions

| Section<br>M | Base Sheet Drawings                                 |   |                       |
|--------------|---|---|-----------------------|
|              | Drawing   | Modification Summary  | Effective: 03-01-2025 |
|              |   |   |                       |
|              | Plaza Electrical Work (Business System)-Series 2500 |   |                       |
|              | M-BUS-2542  | VES Wash System Miscellaneous Power Wiring Diagram                        |                       |
|              |   | Revised wiring diagram of the VES Wash single cabinet final configuration |                       |

 New Sheet

 Retired Standard

| CONDUIT SIZES |   |
|---------------|---|
| ①             | RIGID METALLIC CONDUIT ¾"                                     |
| ②             | RIGID METALLIC CONDUIT 1"                                     |
| ③             | RIGID METALLIC CONDUIT 1¼"                                    |
| ④             | RIGID METALLIC CONDUIT 1½"                                    |
| ⑤             | RIGID METALLIC CONDUIT 2"                                     |
| ⑥             | RIGID METALLIC CONDUIT 2½"                                    |
| ⑦             | RIGID METALLIC CONDUIT 3"                                     |
| ⑨             | RIGID METALLIC CONDUIT 4"                                     |
| ⑫             | RIGID NON-METALLIC CONDUIT 1" SCHEDULE 40                     |
| ⑮             | RIGID NON-METALLIC CONDUIT 2" SCHEDULE 40                     |
| ⑰             | RIGID NON-METALLIC CONDUIT 3" SCHEDULE 40                     |
| ⑱             | NOT USED  |
| ⑲             | RIGID NON-METALLIC CONDUIT 4" SCHEDULE 40                     |
| ㉒             | RIGID NON-METALLIC CONDUIT 1" SCHEDULE 80                     |
| ㉔             | RIGID NON-METALLIC CONDUIT 1½" SCHEDULE 80                    |
| ㉕             | RIGID NON-METALLIC CONDUIT 2" SCHEDULE 80                     |
| ㉗             | RIGID NON-METALLIC CONDUIT 3" SCHEDULE 80                     |
| ㉙             | RIGID NON-METALLIC CONDUIT 4" SCHEDULE 80                     |
| ㉚             | RIGID METALLIC CONDUIT PVC COATED 1"                          |
| ㉛             | RIGID METALLIC CONDUIT PVC COATED 1¼"                         |
| ㉜             | RIGID METALLIC CONDUIT PVC COATED 1½"                         |
| ㉝             | RIGID METALLIC CONDUIT PVC COATED 2"                          |
| ㉟             | RIGID METALLIC CONDUIT PVC COATED 3"                          |
| ㊸             | RIGID METALLIC CONDUIT PVC COATED 4"                          |
| ④①            | 1½" COILABLE PVC CABLE DUCT                                   |
| ④①            | RIGID NON-METALLIC CONDUIT 4" SCHEDULE 80 WITH 1" INNER DUCTS |
| ④②            | 1" COILABLE NON-METALLIC CONDUIT                              |
| ④③            | 2" COILABLE NON-METALLIC CONDUIT                              |
| ④④            | 4" COILABLE NON-METALLIC CONDUIT                              |
| ④⑤            | 3" COILABLE NON-METALLIC CONDUIT                              |
| ④⑥            | 1 ½" COILABLE NON-METALLIC CONDUIT                            |


| TOLL EQUIPMENT WIRING<br>CABLE/CONDUIT SCHEDULE |  |               |
|---|--|---------------|
| SYMBOL  | CABLE DESCRIPTION                                | REMARKS       |
| ①   | 1-6PR #22 SHLD                                   | NOTE 8        |
| ②   | 1-3/C #12 SHLD                                   | NOTE 3        |
| ③   | 1-3PR #22 SHLD                                   | NOTE 8        |
| ④   | 1-4/C #12 SHLD                                   | NOTES 1 & 3   |
| ⑤   | 2-1/C #12, 1-1/C #12(GRD)                        | NOTE 1        |
| ⑥   | 1-1PR #14 SHLD<br>(LOOP LEAD IN)                 |               |
| ⑦   | 1-1/C #14 (LOOP WIRE)                            |               |
| ⑧   | 1-1/C #6 BARE TINNED (GRD)                       |               |
| ⑨   | 1-7/C #12 SHLD                                   | NOTE 3        |
| ⑩   | 1-3/C #12 SHLD                                   | NOTE 3        |
| ⑪   | 2-1PR #22 SHLD                                   | NOTE 1        |
| ⑫   | 1-2/C #12 SHLD                                   | NOTE 3        |
| ⑬   | 1-2 PR #24 (RS 422)                              | NOTE 7        |
| ⑭   | NOT USED   |               |
| ⑮   | 1-COAXIAL ANTENNA CABLE                          |               |
| ⑯   | 1- 9/C #22 IND SHLD                              |               |
| ⑰   | 1-1/C #4/0 (GRD BARE<br>TINNED COPPER CONDUCTOR) |               |
| ⑱   | 1-1/C #8 (GRD BARE<br>TINNED COPPER CONDUCTOR)   |               |
| ⑲   | 1-1/C #2 (GRD BARE<br>TINNED COPPER CONDUCTOR)   |               |
| ㉒   | 1-4PR #24 (CATEGORY 6)                           |               |
| ㉔   | 1-6 STRAND, SINGLE MODE<br>FIBER OPTIC CABLE     | ARMORED CABLE |
| ㉔   | 1-24 STRAND, SINGLE MODE<br>FIBER OPTIC CABLE    | ARMORED CABLE |
| ㉔   | 1-36 STRAND, SINGLE MODE<br>FIBER OPTIC CABLE    | ARMORED CABLE |
| ㉔   | 1-48 STRAND, SINGLE MODE<br>FIBER OPTIC CABLE    | ARMORED CABLE |
| ㉕   | 1-12PR #22 SHLD                                  |               |
| ㉕   | 1-9/C #18 SHLD                                   | NOTE 4        |
| ㉗   | 2-2/C #18 SHLD                                   | NOTE 4        |
| ㉘   | 1-6PR #22 SHLD                                   |               |
| ㉙   | 1-3PR #24 SHLD                                   | NOTE 6        |
| ㉚   | 1-3/C #10 SHLD                                   |               |
| ㉛   | 1-2PR #22 SHLD                                   |               |
| ㉜   | OEM CABLE (POWER<br>AND VIDEO)                   | NOTE 10       |
| ㉝   | 1 - 1PR #22 SHLD<br>(SENSE WIRE VES CAM)         |               |
| ㉞ THRU ㉟  | RESERVED FOR<br>STANDARD DRAWINGS                |               |
| ⑤①  | CAT6 CABLE                                       | OUTDOOR RATED |
| ⑤①  | SYNC CABLE, TWISTED PAIR<br># 24. BELDEN 89730   | NOTE 11       |

| TOLL EQUIPMENT WIRING CABLE/CONDUIT SCHEDULE |  |              |                        |                      |
|--|--|--------------|------------------------|----------------------|
| SYMBOL                                       | CABLE DESCRIPTION                                      | CONDUIT SIZE |                        | REMARKS              |
|  |  | EXPOSED      | EMBEDED OR UNDERGROUND |                      |
| 101  | (4) 1/C #3/0<br>(1) 1/C #4 (GRD)                       |              | 4"                     |                      |
| 102  | (4) 1/C 250 MCM<br>(1) 1/C #1/0 (GRD)                  |              | 4"                     |                      |
| 103  | (4) 1/C #2<br>(1) 1/C #8 (GRD)                         |              | 2"                     |                      |
| 104  | (3) 1/C #10<br>(1) 1/C #10 (GRD)                       | 1"           | 1"                     |                      |
| 105  | (4) 1/C #10<br>(1) 1/C #10 (GRD)                       | 1"           | 1"                     |                      |
| 106  | (2) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 107  | (4) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 108  | (4) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 109  | (5) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 110  | (5) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 2"                     |                      |
| 111  | (6) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 112  | (8) 1/C #12<br>(1) 1/C #12 (GRD)                       | 1"           | 1"                     |                      |
| 113  | 1" CABLE DUCT WITH<br>(2) 1/C #12<br>(1) 1/C #12 (GRD) | 1"           | 1"                     |                      |
| 114  | 1" CABLE DUCT WITH<br>(3) 4/C #12 (SHLD)               | 1"           | 1"                     |                      |
| 115  | (3) 1/C #2/0 & 1 #8 (GND)                              |              | 4"                     |                      |
| 116  | (2) 1/C #8<br>(1) 1/C #8 (GRD) 600V                    |              |                        |                      |
| 117  | (3) 1/C #250MCM 600V<br>(1) 1/C #1/0 (GRD) 600V        |              | 3"                     |                      |
| 118  | (2) 1/C #4<br>(1) 1/C #8 (GRD) 600V                    |              | 2"                     |                      |
| 119  | (1) 16 AWG 6C FPLR<br>(6) 1PR #22 SHLD                 | 1"           | 1"                     | SECURITY-CARD ACCESS |
| 120  | (2) 1/C #16 SHIELDED PAIR                              | 1"           | 1"                     | FIRE ALARM           |
| 121  | (2) 1/C #10<br>(1) 1/C #10 (GRD)                       | 1"           | 1"                     |                      |
| 122  | (3) 1/C #3/0<br>(1) 1/C #1/0 (GRD)                     |              | 3"                     |                      |
| 123  | (3) 1/C #1/0<br>(1) 1/C #4 (GRD)                       |              | 3"                     |                      |
| 124  | (1) 1/C #6 SHLD  |              |                        | NOTE 10              |
| 125  | 144 STRANDS SM,<br>FIBER OPTIC                         |              |                        | ARMORED CABLE        |
| 126  | 12 STRANDS SM,<br>FIBER OPTIC                          |              |                        | ARMORED CABLE        |
| 127  | 2#2, 1#6   |              | 2"                     |                      |
| 128  | 2#1, 1#6   |              | 2"                     |                      |
| 129  | 3#8, 1#8   |              | 2"                     |                      |
| 130  | 2#6, 1#8   |              | 1¼"                    |                      |

| TOLL EQUIPMENT WIRING CABLE/CONDUIT SCHEDULE |                                       |              |                           |               |
|--|---------------------------------------|--------------|---------------------------|---------------|
| SYMBOL                                       | CABLE DESCRIPTION                     | CONDUIT SIZE |                           | REMARKS       |
|  |                                       | EXPOSED      | EMBEDED OR<br>UNDERGROUND |               |
| ⑬①   | 48 STRANDS SM.<br>FIBER OPTIC         |              |                           | ARMORED CABLE |
| ⑬②   | (3) 1/C #1<br>(1) 1/C #8 (GRD)        |              |                           |               |
| ⑬③   | (3) 1/C #2<br>(1) 1/C #8 (GRD)        |              |                           |               |
| ⑬④   | (3) 1/C #4<br>(1) 1/C #8 (GRD)        |              |                           |               |
| ⑬⑤   | (3) 1/C #12                           | 1"           | 1"                        |               |
| ⑬⑥   | (4) 1/C 500 MCM<br>(1) 1/C #1/0 (GRD) |              |                           |               |
| ⑬⑦   | (4) 1/C 500 MCM<br>(1) 1/C #4 (GRD)   |              |                           |               |

NOTES:

- MINIMUM SIZE OF EXPOSED CONDUIT IS ¾". MINIMUM SIZE OF EMBEDDED CONDUIT IS 1". EMBEDDED CONDUIT SHALL BE PVC COATED RIGID STEEL.
- STANDARD AND QUANTUM LOOPS SHALL BE FURNISHED AND INSTALLED BY THE ILLINOIS TOLLWAY. LOOP LEAD-IN CABLING IS FURNISHED AND INSTALLED BY THE CONTRACTOR.
- MULTI-CONDUCTOR SHIELDED CABLE #12 AWG FOR NORMAL AND UPS POWER, SHALL BE COLOR CODED AS SPECIFIED IN THE SPECIAL PROVISIONS OF THE CONTRACT.
- MULTI-CONDUCTOR SHIELDED CABLE #14 AWG THROUGH #18 AWG FOR CONTROL USE SHALL BE COLOR CODED PER ICEA-NEC (K-2) STANDARD.
- NOT USED
- PROVIDE SPD PROTECTION ADAPTERS FOR ALL ANTENNA CABLES ENTERING BUILDING. IN-LINE ADAPTERS MUST BE INSTALLED AT ALL CONNECTIONS TO THE RACK, ELPAC AND IPASS EQUIPMENT. THE SPD PROTECTION ADAPTERS SHALL BE PHOENIX CONTACT (OR EQUIVALENT) "COAXTRAX SERIES" CATALOG NUMBER C-UFB-5DC/E.
- PROVIDE SPD PROTECTION ADAPTERS FOR ALL RS-422 AND CATEGORY 6 CABLES ENTERING THE BUILDING. IN-LINE ADAPTERS MUST BE INSTALLED AT ALL CONNECTIONS TO THE CISCO SWITCH, ELPAC AND IPASS EQUIPMENT. THE SPD ADAPTER FOR RS-422 CABLES SHALL BE PHOENIX CONTACT (OR EQUIVALENT) DATATRAB D-UFB-V11/BS-B. THE SPD ADAPTER FOR CATEGORY 6 CABLES SHALL BE PHOENIX CONTACT (OR EQUIVALENT) DATATRAB D-LAN-CAT.6+.
- PLENUM RATED CABLE INSTALLED IN EMBEDDED CONDUIT.
- LANE VIOLATION CAMERA IS MOUNTED ON MONOTUBE.
- PROVIDE SURGE PROTECTION DEVICE FOR ALL CABLES FROM EXTERNAL DEVICES ROUTED INTO THE PLAZA BUILDING INCLUDING ALL CAT6, ANTENNA AND POWER CABLES.
- ANTENNA READER SYNC CABLE IN CONDUIT MUST BE INSTALLED BETWEEN TWO PLAZAS WHEN THEIR ANTENNAS ARE WITHIN 500FT. OF EACH OTHER.



DESIGNATION KEY


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



CABLE / CONDUIT  
SCHEDULE AND GENERAL  
NOTES

| LEGEND |  |
|--------|--|
|        | EXPOSED CONDUIT  |
|        | CONDUIT IN SLAB  |
|        | UNDERGROUND CONDUIT OR CABLE DUCT                            |
|        | CONDUIT OR CABLE DUCT IN CASING                              |
|        | HOME RUN TO PANEL AS NOTED                                   |
|        | INDICATES CIRCUIT TURNING DOWN                               |
|        | INDICATES CIRCUIT TURNING UP                                 |
|        | GROUND ROD   |
|        | GROUNDING TRIAD  |
|        | EXPOSED GROUND CONDUCTOR                                     |
|        | UNDERGROUND GROUND CONDUCTOR                                 |
|        | 4'X4' HEAVY DUTY HANDHOLE (POWER) EXISTING/PROPOSED          |
|        | 4'X4' HEAVY DUTY HANDHOLE (COMMUNICATIONS) EXISTING/PROPOSED |
|        | 72"X48"X36" TORSION ASSIST FIBER HANDHOLE EXISTING/PROPOSED  |



LIGHT STANDARD DESCRIPTION  
LED LUMINAIRES

| SYMBOL LIST                       |   |
|-----------------------------------|---|
| SYMBOL                            | DESCRIPTION   |
| 30 KVA<br>480-208Y/120V<br>3), 4W | TRANSFORMER.<br>30 KVA DENOTES TRANSFORMER RATING.<br>480-208Y/120V DENOTES VOLTAGE.<br>3) DENOTES 3 PHASE.<br>4W DENOTES 4 WIRE.   |
| ①                                 | LEGEND NUMBER FOR CABLE & CONDUIT.<br>(SEE CABLE AND CONDUIT SCHEDULES).  |
| ①                                 | MOTOR.<br>NUMBER 1 DENOTES HORSEPOWER.  |
| N E<br>L 260A<br>3P,4W            | AUTOMATIC TRANSFER SWITCH (ATS).<br>N DENOTES NORMAL SOURCE.<br>E DENOTES EMERGENCY SOURCE.<br>L DENOTES LOAD.<br>260A DENOTES 260 AMPERE ATS RATING.<br>3P DENOTES 3 POLE.<br>4W DENOTES 4 WIRE. |
| JB OR                             | JUNCTION BOX.   |
| 60A                               | DISCONNECT SWITCH.<br>60A DENOTES 60 AMPERES.   |
| 50A                               | CIRCUIT BREAKER.<br>50A DENOTES 50 AMPERES.   |
| 200A<br>3PDT. SW.                 | MANUAL TRANSFER SWITCH.<br>200A DENOTES 200 AMPERES.<br>3PDT DENOTES 3 POLE DOUBLE-THROW.   |
| (WH)                              | SELF CONTAINED UTILITY METERING.  |
| G                                 | STANDBY GENERATOR.  |
| 30A<br>2P                         | PANEL CIRCUIT BREAKER.<br>30A DENOTES 30 AMPERES.<br>2P DENOTES 2 POLES.  |
| E                                 | ELECTRICALLY HELD LIGHTING CONTACTOR.   |
| C                                 | MECHANICALLY HELD LIGHTING COIL.  |
| CR                                | CONTROL RELAY COIL.   |
| SPD<br>WITH LP                    | TRANSIENT VOLTAGE SURGE SUPPRESSION<br>WITH LIGHTNING PROTECTION  |

| ABBREVIATIONS |                                    |
|---------------|------------------------------------|
| ACM           | AUTOMATIC COIN MACHINE             |
| AET           | ALL ELECTRONIC TOLL                |
| AFF           | ABOVE FINISH FLOOR                 |
| ATPM          | AUTOMATIC TOLL PAYMENT MACHINE     |
| ATS           | AUTOMATIC TRANSFER SWITCH          |
| AVI           | AUTOMATED VEHICLE IDENTIFICATION   |
| BF            | BARRIER WARNING LIGHT              |
| C/B           | CIRCUIT BREAKER                    |
| CCTV          | CLOSED CIRCUIT TELEVISION          |
| CKT           | CIRCUIT                            |
| CNC           | COILABLE NON-METALLIC CONDUIT      |
| DHH           | DOUBLE HANDHOLE                    |
| FACP          | FIRE ALARM CONTROL PANEL           |
| FLPC          | FRONT LICENSE PLATE CAMERA         |
| GCS           | GENERATOR CONTROL SWITCH           |
| GFI           | GROUND FAULT INTERRUPTER           |
| HDPE          | HIGH DENSITY POLYETHYLENE          |
| HH            | HANDHOLE                           |
| IPO           | I-PASS ONLY                        |
| JB            | JUNCTION BOX                       |
| LA            | LIGHTNING ARRESTER                 |
| LC            | LINE CONDITIONER                   |
| LCC           | LANE CONTROLLER CABINET            |
| LP            | LIGHTNING PROTECTION               |
| MCB           | MAIN CIRCUIT BREAKER               |
| MDP           | MAIN DISTRIBUTION PANEL            |
| MLO           | MAIN LUG ONLY                      |
| MMF           | MULTI-MODE FIBER                   |
| MSD           | MAIN SERVICE DISCONNECT            |
| MTS           | MANUAL TRANSFER SWITCH             |
| OCR           | OPTICAL CHARACTER RECOGNITION      |
| RLPC          | REAR LICENSE PLATE CAMERA          |
| SDR           | STANDARD DIMENSION RATIO           |
| SMF           | SINGLE MODE FIBER                  |
| SPD           | SURGE PROTECTION DEVICE            |
| TOC           | TRAFFIC OPERATION CENTER           |
| TSIC          | TERMINAL STRIP INTERCONNECT CENTER |
| UPS           | UNINTERRUPTIBLE POWER SUPPLY       |
| VES           | VIOLATION ENFORCEMENT SYSTEM       |
| WP            | WEATHERPROOF                       |

- NOTES:
- ALL TYPE 'B' FIXTURES SHALL BE MOUNTED AT THE SAME ELEVATION WITH A MINIMUM MOUNTING HEIGHT AS INDICATED.

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

| WIRING DEVICE SCHEDULE |  |               |  |                   |
|------------------------|--|---------------|--|-------------------|
| SYMBOL                 | DESCRIPTION  | RATING        | MFR. AND CAT. NO.                        | MOUNTING HEIGHT   |
| a<br>OC                | SINGLE-POLE SWITCH<br>a-SWITCH LEG (LOWER CASE LETTER)                         | 20A,<br>120V  | HUBBELL #LHIR                            | 4'-0"             |
| X                      | DUPLEX RECEPTACLE<br>X - CIRCUIT NUMBER  | 20A,<br>120V  | HUBBELL #HBL5362                         | 18" AS NOTED      |
| X                      | QUAD RECEPTACLE<br>X - CIRCUIT NUMBER  | 20A,<br>120V  | (2) HUBBELL #HBL5362                     | 18" AS NOTED      |
| C                      | 4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR, BACK BOX, & ANGLE ADAPTER    | 200A,<br>600V | CROUSE-HINDS "ARKTITE" SERIES #AREA20417 | 3'-0" ABOVE GRADE |
| B                      | 4P, 4W, WEATHERPROOF RECEPTACLE WITH SPRING DOOR & BACK BOX                    | 30A,<br>600V  | CROUSE-HINDS "ARKTITE" SERIES #ARE3413   | 3'-0" ABOVE GRADE |
| WP<br>GFI              | DUPLEX RECEPTACLE WITH GROUND FAULT PROTECTION<br>WP - IDENTIFIES WEATHERPROOF | 20A,<br>120V  | HUBBELL #GF5362SG                        | 3'-0" ABOVE GRADE |
| A                      | 3P, 3W, WEATHERPROOF RECEPTACLE  | 30A,<br>240V  |  | 3'-0" ABOVE GRADE |

| LIGHTING FIXTURE SCHEDULE |   |         |       |   |   |
|---------------------------|---|---------|-------|---|---|
| SYMBOL                    | DESCRIPTION   | VOLTAGE | LAMPS | MFR. AND CAT. NO.                                     | REMARKS                                     |
| A                         | 4' LED LOW PROFILE INDUSTRIAL LUMINAIRE               | 120 V   | LED   | H.E. WILLIAMS<br>96-4-L62/840-HIAFR-<br>DRV-UNV       | MOUNT 8' ABOVE FINISHED FLOOR               |
| B                         | LED LOW PROFILE WALL PACK                             | 120 V   | LED   | H.E. WILLIAMS<br>VWPV-L30/740-TFT-<br>DBZ-CGL-DIM-UNV | MOUNT 10'-0" ABOVE FINISHED GRADE<br>NOTE 1 |
| C                         | EMERGENCY LED LIGHT WITH NICKEL METAL HYBRIDE BATTERY | 120 V   | LED   | H.E. WILLIAMS<br>EMER/LED-WHT-SDT-D                   | MOUNT 8' ABOVE FINISHED FLOOR               |



LEGEND AND SYMBOL LIST  
ABBREVIATIONS AND  
EQUIPMENT SCHEDULES



**NOTES:**


1. TO PROPOSED COMED SERVICE.
2. CONDUIT ROUTING SHOWN DIAGRAMMATICALLY. THE CONTRACTOR IS RESPONSIBLE FOR FINAL ROUTING.
3. ALL EMPTY CONDUITS UNDERGROUND OR ABOVE GRADE SHALL HAVE A PULL CORD.
4. UNDERGROUND CABLE/CONDUIT MARKING TAPE IS TO BE INSTALLED OVER UNDERGROUND CONDUITS.
5. GROUND MOUNTED LIGHT POLE, ALUMINUM, 50 FT., 15 FT. MAST ARM, LED LUMINAIRE (AS PER ROADWAY LIGHTING PLAN) AND LIGHT POLE FOUNDATION (ROADWAY) STEEL HELIX (7 FT) OR CONCRETE.
6. PROVIDE (2) 6" SDR 11 HDPE SLEEVES, EACH SLEEVE SHALL HAVE:  
(1) 1 1/2" CNC DUCT (SOLID GREEN)  
(1) 1 1/2" CNC DUCT (GREEN/WHITE STRIPE)  
(1) 1 1/2" CNC DUCT (BLACK/RED STRIPE)

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



**ELECTRICAL SITE PLAN AET LANES**



ELECTRICAL SITE PLAN AET LANES - DETAIL

NOTES:

- SEE LEGEND SHEET FOR SYMBOL LEGEND.
- SEE CABLE/CONDUIT SCHEDULE SHEET FOR CABLE TAGS.
- ALL EMPTY CONDUITS UNDERGROUND OR ABOVE GRADE SHALL HAVE A PULL CORD.
- UNDERGROUND CABLE/CONDUIT MARKING TAPE IS TO BE INSTALLED OVER UNDERGROUND CONDUITS.
- GROUND MOUNTED LIGHT POLE, ALUMINUM, 50 FT., 15 FT. MAST ARM, LED LUMINAIRE (AS PER ROADWAY LIGHTING PLAN) AND LIGHT POLE FOUNDATION (ROADWAY) STEEL HELIX (7 FT) OR CONCRETE.
- DATA LOGGER CAMERA SHALL BE INSTALLED ON STEEL ITS POLE. SEE CAMERA DETAILS.
- PROVIDE (2) 6" SDR 11 HDPE SLEEVES, EACH SLEEVE SHALL HAVE:  
(1) 1 1/2" CNC DUCT (SOLID GREEN)  
(1) 1 1/2" CNC DUCT (GREEN/WHITE STRIPE)  
(1) 1 1/2" CNC DUCT (BLACK/RED STRIPE)

NOTE TO DESIGNER

- THE DESIGNER MUST PROVIDE A CONTRACT SPECIFIC ELECTRICAL SITE PLAN. THIS DRAWING IS TO BE USED AS A GUIDE IN DEVELOPING THE CONTRACT ELECTRICAL SITE PLAN.
- THE POWER FEEDER MUST BE SIZED BY THE DESIGNER TO PROVIDE A MAXIMUM 3% VOLTAGE DROP.
- THE DESIGNER MUST PROVIDE PAY ITEMS, QUANTITIES AND UNIT BID PRICES FOR THE WORK SHOWN ON THIS DRAWING NOT INCLUDED IN THE PLAZA LUMP SUM PRICE.
- IF DISTANCE BETWEEN MAIN AND REMOTE PLAZA ANTENNAS IS LESS THAN 500 FT., PROVIDE CONDUIT AND SYNC CABLE TO CONNECT ANTENNA READERS IN THE MAIN AND REMOTE CONTROL BUILDINGS.
- MAIN AND REMOTE PLAZA BUILDING DOORS MUST FACE PAY ZONES.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



ELECTRICAL SITE PLAN AET LANES - DETAIL






1. SEE CABLE/CONDUIT SCHEDULE SHEET FOR CABLE TAGS.
2. PROVIDE 3/4" SCHEDULE 40 PVC CONDUITS FOR GROUND CABLES CONNECTING UPS-1 AND LC-1 TO MASTER GROUND BUSBAR.
3. PROVIDE EXOTHERMIC CONNECTION TO INTERNAL PERIMETER BUS CONDUCTOR.
4. GROUNDING SHALL BE PER SPECIAL PROVISION.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.





SMF AND NETWORK CONNECTIVITY BETWEEN MAIN PLAZA AND REMOTE PLAZA

NOTES:

1. EQUIPMENT SHOWN ON THIS DRAWING MUST BE COORDINATED WITH THE ILLINOIS TOLLWAY IT DEPARTMENT.
2. ALL CABLING AND CONNECTORS REQUIRED SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.
3. ALL FIBER OPTIC PATCH CORDS SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.
4. ALL FIBER OPTIC SFP'S REQUIRED FOR TERMINATING FIBER OPTIC CABLES AT CISCO SWITCHES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.
5. PROVIDE IN-LINE SPD PROTECTION ADAPTERS FOR ALL CATEGORY 6 CABLES ENTERING THE BUILDING INCLUDING ALL CONNECTIONS TO THE CISCO SWITCH, EPAC, I-PASS EQUIPMENT AND RACK.

NOTE TO DESIGNER

WHETHER A RAMP PLAZA BUILDING CONNECTS TO THE FIBER BACKBONE DIRECTLY OR THROUGH A MAIN CONTROL BUILDING IS SITUATIONAL BASED ON THE NUMBER OF BUILDINGS, DISTANCE BETWEEN THEM, AND OTHER FACTORS. DETERMINE FIBER ROUTING IN COORDINATION WITH ILLINOIS TOLLWAY I.T. AND BUSINESS SYSTEMS.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



FIBER INTERCONNECTIONS BETWEEN MAIN AND REMOTE PLAZAS

- NOTES
1.

SEE CABLE AND CONDUIT SCHEDULE SHEET FOR CABLE TAGS.
2.

SEE AET WIRING DIAGRAM SHEET FOR MONOTUBE WIRING.
3.

CAP ALL CONDUIT STUBS FOR FUTURE USE.
4.

FINAL LOCATION OF ALL HANDHOLES AND JUNCTION BOXES SHALL BE APPROVED BY THE ENGINEER.
5.

NOT USED.
6.

ROUTE PLAZA ROADWAY LIGHTING CIRCUITS TO LIGHTING CONTACTOR. THESE STAY ON PLAZA CIRCUITS, THAT ARE POWERED FROM PLAZA EMERGENCY GENERATOR. ROUTE 2-1/C #8 AND 1/C #8 GROUND WIRE FROM LIGHTING CONTACTOR LOCATED IN THE POWER CABINET TO THE LIGHT POLE FOR PLAZA LIGHTING CONTROL CIRCUIT. PROVIDE PHOTOCELL ON SAME POLE.
7.

ALL EXCESS (SLACK) POWER AND DATA CABLES MUST BE COILED IN THE HANDHOLE. NO EXCESS CABLE WILL BE COILED INSIDE THE BUILDING.
8.

EXOTHERMICALLY WELD THE GROUND WIRE TO THE MONOTUBE'S BASE.
9.

REFER TO TSIC TERMINAL BLOCK LAYOUT SHEET. LOW VOLTAGE WIRE FROM VES AND SECURITY CAMERAS LAND ON SURGE PROTECTION DEVICES.
10.

PVC CONDUIT SHALL BE USED WHEN THE CONDUIT IS EITHER COVERED OR ENCASED IN CONCRETE. ANY EXPOSED CONDUIT SHALL BE PVC COATED RGS. SLEEVES SHALL BE USED WHEN CROSSING WALL FOUNDATIONS.
11.

LOCATION OF LANE STUB UPS TO BE APPROVED BY THE ILLINOIS TOLLWAY PRIOR TO CONCRETE POUR. FINAL LOCATION OF EQUIPMENT TO BE APPROVED BY THE ENGINEER.
12.

PROVIDE (2) 4" PVC COATED RGS 5FT PAST RETAINING WALL UP TO ComEd TRANSFORMER FOR ComEd INCOMING PRIMARY CABLES. INSTALL SLEEVE IN COORDINATION WITH STRUCTURAL AND STUB UP NEAR ComEd TRANSFORMER LOCATION. PROVIDE WATER PROOF SEALING AT RETAINING WALL.
13.

NOT USED.
14.

CONTRACTOR SHALL FURNISH AND INSTALL PROPOSED TRANSFORMER PAD AND CONDUIT/TRENCH FOR ComEd. ComEd WILL FURNISH AND INSTALL TRANSFORMER AND GROUND ROD/WIRING. ALL WORK SHALL CONFORM TO ComEd STANDARD. THIS WILL BE PAID UNDER PAY ITEM: JS804100 - ELECTRIC SERVICE INSTALLATION.
15.

SEE VES CAMERA WASH SYSTEM SHEETS FOR DETAILS.
16.

FOR LIGHT POLE AND FOUNDATION DETAILS, SEE ILLINOIS TOLLWAY STANDARD DRAWINGS H1 AND H2.
17.

CONTRACTOR SHALL PROVIDE (1) 4" PVC COATED RGS SLEEVE FROM BUILDING SOUTHEAST CORNER SOUTH UP TO NICOR METER PAD TO INSTALL GAS PIPING TO BUILDING. STUB UP SLEEVE NEAR GAS METER LOCATION. PROVIDE WATERPROOF SEALING AT RETAINING WALL.
18.

RIGID METALLIC CONDUIT PVC COATED FOR MONOTUBE POWER/DATA/ANTENNA CABLING SHALL RUN IN OVERHEAD CONDUIT TRAY. SEE OVERHEAD CONDUIT TRAY DETAILS.
19.

PROVIDE (2) 6" SDR 11 HDPE SLEEVES, EACH SLEEVE SHALL HAVE:  
(1) 1 1/2" CNC DUCT (SOLID GREEN)  
(1) 1 1/2" CNC DUCT (GREEN/WHITE STRIPE)  
(1) 1 1/2" CNC DUCT (BLACK/RED STRIPE)
20.


PROVIDE LIGHTING CONTROLLER SERVICE CONDUIT 3"C PVC-SCH 40 AND STUP UP INTO METER 3"C RGS PVC COATED FOR SERVICE TO THE CONTROLLER.

NOTE TO DESIGNER





THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



UNDERGROUND CONDUIT  
PLAN - MAIN PLAZA



UNDERGROUND CONDUIT PLAN MAIN PLAZA




**NOTE TO DESIGNER:**

AIR TERMINAL RODS ARE TO BE INSTALLED AND FIXED TO ROOF WITHOUT INTERFERING WITH THE INTEGRITY OF THE STRUCTURE


- NOTES:**
- TREAD RISERS SHALL BE EQUAL AND NO GREATER THAN 7".
  - BOND BASE OF BIRD SPIKE ASSEMBLY TO GROUNDING CONDUCTOR FOR THE LIGHTNING PROTECTION SYSTEM.
  - CONNECT CABLE TO NEAREST GROUND ROD ON THE BUILDING GROUND GRID.




**EXTERIOR ELEVATIONS - MAIN PLAZA**




ROOF TO WALL SECTION




ROOF TO WALL WELD




TYPICAL DOOR SECTION DETAIL



WALL TO WALL SECTION




WALL TO WALL WELD




|                     |                           |
|---------------------|---------------------------|
| THICKNESS:          | 6 1/8"                    |
| APPROXIMATE WEIGHT: | 12 PSF                    |
| FIRE TEST:          | SWRI 01-5920-614, 12-5-94 |
| SOUND TEST:         | NGC 2363, 4-1-70          |

2 HOUR INTERIOR WALL DETAIL  
GA FILE WP NO. 4136


BASE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR VENEER BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE OF 2 X 4 WOOD STUDS 16" O.C. WITH 1 1/4" TYPE W DRYWALL SCREWS 12" O.C. FACE LAYER 5/8" TYPE X GYPSUM WALLBOARD OR VENEER BASE APPLIED PARALLEL OR AT RIGHT ANGLES TO EACH SIDE WITH 1 7/8" TYPE W DRYWALL SCREWS 12" O.C. AND OFFSET 6" FROM SCREWS IN BASE LAYER. JOINTS STAGGERED 16" EACH LAYER AND SIDE. (LOAD-BEARING)




MOUNTING BRACKET



WALL TO FLOOR SECTION



WALL TO FLOOR WELD



TYPICAL FLOOR REBAR LAYOUT

CONSTRUCTION MATERIALS:

INTERIOR FINISH:

FLOOR: 1/8" X 12" X 12" VINYL TILE WITH 4" BASE COVE  
WALLS: 3/4" PANELING (1 1/16" OSB W/.030 FRP COATING) (CLASS "C" MINIMUM)  
CEILING: 3/4" PANELING (1 1/16" OSB W/.030 FRP COATING) (CLASS "C" MINIMUM)

INSULATION:

WALLS: 3" THERMAX FOAM INSULATION (R-19) ESR-1659  
CEILING: 5" THERMAX FOAM INSULATION (R-32) ESR-1659

FRAMING:

WALLS: 2" X 6" FURRING STRIPS ON END AT 24" O.C.  
CEILING: 2" X 6" FURRING STRIPS ON END AT 24" O.C.

CONCRETE:


FLOOR: 5000 PSI SAND LIGHTWEIGHT  
WALLS: 5000 PSI SAND LIGHTWEIGHT  
CEILING: 5000 PSI SAND LIGHTWEIGHT

CONSTRUCTION NOTES:


- FLOORS ARE TO BE WAXED AND SEALED BEFORE SHIPPING.



EXTERIOR ELEVATIONS -  
MAIN PLAZA



|                     |                           |                  |
|---------------------|---------------------------|------------------|
| VERSION:<br>2021-03 | BASE SHEET:<br>M-BUS-2510 | SHEET:<br>1 OF 1 |
|---------------------|---------------------------|------------------|



WALL ELEVATIONS  
NOT TO SCALE  
NOTE 2

EQUIPMENT LEGEND

ITEM DESCRIPTION


- 1 MAIN SERVICE DISCONNECT 200A/3P
- 2 MTS-2 FOR GENERATOR CONTROL
- 3 LIGHTING CONTRACTOR 120V, 30A, 1 PHASE, 4-POLE IN A NEMA 1 ENCLOSURE WITH A THREE POSITION SELECTOR SWITCH HAND-OFF-AUTO MOUNTED ON THE COVER. TRANSFORMER DRY TYPE, 2KVA, 120V PRIMARY, 480V SECONDARY, 1-PHASE, 3-WIRE ROADWAY LIGHTING.
- 5 VIDEO JB POWER #1
- 6 BYPASS SWITCH.
- 7 UPS-1 PANEL.
- 8 LIGHTNING ARRESTOR SYSTEM
- 13 MAIN DISTRIBUTION PANEL (MDP-1), 208Y/120V, 3 PHASE, 4W 250 AMP, MAIN CIRCUIT BREAKER
- 14 ITS-1 PANEL
- 19 UPS / LINE CONDITIONER CONTRACTOR SHALL INSTALL THE 3KVA UPS ABOVE GROUND, ON A SHELVING SYSTEM AS DIRECTED BY THE ENGINEER
- 23 ATS
- 24 MTS-1 FOR GENERATOR POWER
- 27 VIDEO JB POWER #2

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



INTERIOR ELEVATIONS -  
CONTROL BUILDING



BUILDING MECHANICAL PLAN  
NOT TO SCALE

NOTES:

- UNIT SHALL HAVE ARI CERTIFIED COILS, AIWCA RATED FANS, AND UL LISTED & LABELED ELECTRICAL COMPONENTS.
- PROVIDE HVAC UNITS WITH FACTORY SUPPLY AND RETURN GRILLES.
- HVAC PROVIDE LEAD/LAG THERMOSTAT CONTROLLER BARD MODEL #MC4001-AC WITH BASE ALARMS AND ETHERNET ACCESS.
- ALL MANUFACTURERS AND PART NUMBERS ARE FOR REFERENCE. THE CONTRACTOR SHALL PROVIDE CALCULATIONS FOR HVAC AND HEATING SYSTEM BASED ON BUILDING CONSTRUCTION AND INTERNAL BUILDING LOADS.

| ELECTRICAL ROOM |          |          |          |                   |                     |             |              |               |              |                |                |                      |                            |              |                |                      |                           |                 |    |    |                            |         |
|-----------------|----------|----------|----------|-------------------|---------------------|-------------|--------------|---------------|--------------|----------------|----------------|----------------------|----------------------------|--------------|----------------|----------------------|---------------------------|-----------------|----|----|----------------------------|---------|
| MARK            | LOCATION | SERVES   | NOM. TON | TOTAL AIRFLOW CFM | OUTSIDE AIRFLOW CFM | ESP (IN WG) | REFRIG. TYPE | COOLING DATA  |              |                |                |                      |                            | HEATING DATA |                |                      |                           | ELECTRICAL DATA |    |    | MANUFACTURER/ MODEL NUMBER | REMARKS |
|                 |          |          |          |                   |                     |             |              | TOTAL CAP MBH | SENS CAP MBH | EAT (DEG F) DB | EAT (DEG F) WB | OUTDOOR TEMP (DEG F) | MIN. EER AT ARI CONDITIONS | CAP MBH      | EAT (DEG F) DB | OUTDOOR TEMP (DEG F) | SUPPLEMENTAL HEATING (KW) | VOLTS           | PH | HZ |                            |         |
| HVAC-01         | OUTSIDE  | BUILDING | 4        | 1500              | -                   | 0.15        | R454B A2L    | 45.5          | 34.0         | 75             | 62             | 90                   | 11                         | 17.1         | 70             | 0                    | 5                         | 240             | 1  | 60 | BARD W5SAF0A05ZPXXXJ       |         |
| HVAC-02         | OUTSIDE  | BUILDING | 4        | 1500              | -                   | 0.15        | R454B A2L    | 45.5          | 34.0         | 75             | 62             | 90                   | 11                         | 17.1         | 70             | 0                    | 5                         | 240             | 1  | 60 | BARD W5SAF0A05ZPXXXJ       |         |

| EXHAUST FAN AND DAMPERS |                |           |       |             |     |              |            |               |            |             |   |
|-------------------------|----------------|-----------|-------|-------------|-----|--------------|------------|---------------|------------|-------------|---|
| MARK                    | LOCATION       | MAKE      | MODEL | TYPE        | CFM | ESP<br>IN WG | FAN<br>RPM | DRIVE<br>TYPE | MOTOR DATA |             | NOTES   |
|                         |                |           |       |             |     |              |            |               | HP         | V / PH / HZ |   |
| EF-1                    | GENERATOR ROOM | GREENHECK | SE1   | EXHAUST FAN | 750 | 0.25         | 1307       | DIRECT        | 1/8        | 115/ 1/ 60  | WITH MOTORIZED LOUVERS AND GALV. HOUSING, THERMOSTAT CONTROLLED |

| EXHAUST FAN AND DAMPERS |                |                |                  |           |          |           |              |   |
|-------------------------|----------------|----------------|------------------|-----------|----------|-----------|--------------|---|
| MARK                    | LOCATION       | DESCRIPTION    | TYPE             | MAKE      | MODEL    | SIZE      | ELECTRICAL   | NOTES   |
|                         |                |                |                  |           |          |           | V / PH / HZ  |   |
| DMPR-01                 | GENERATOR ROOM | SUPPLY DAMPER  | MOTORIZED DAMPER | GREENHECK | VCD-23   | 48" x 48" | 115/ 1/ 60   | LOUVERS FAIL OPEN ON LOSS OF POWER, INSTALL HOOD WITH SS MESH FILTER ON EXTERIOR        |
| DMPR-02                 | GENERATOR ROOM | EXHAUST DAMPER | MOTORIZED DAMPER | GREENHECK | 135 TLCD | 48" x 48" | 460 / 3 / 60 | LOUVERS FAIL OPEN ON LOSS OF POWER, INSTALL PARTIAL HOOD WITH STAINLESS STEEL WIRE GRID |

| ELECTRIC UNIT HEATER SCHEDULE (UH) |           |         |       |              |               |     |             |                    |
|------------------------------------|-----------|---------|-------|--------------|---------------|-----|-------------|--------------------|
| MARK                               | ROOM      | MAKE    | MODEL | TYPE         | CAPACITY (KW) | CFM | V / PH / HZ | NOTES              |
| UH-1                               | GENERATOR | INDEECO | ULI   | WALL MOUNTED | 2KW/1.5KW     | 300 | 240/ 1 / 60 | INCLUDE DISCONNECT |

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTE TO DESIGNER


THE ESTIMATED EQUIPMENT BUILDING LOADS FOR EQUIPMENT IS 19,000 BTU/HR. THE DESIGNER SHALL SIZE THE HVAC SYSTEMS ACCORDINGLY.



MECHANICAL PLAN - MAIN PLAZA



NOTES:




LEGEND:


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.





**BUILDING ELECTRICAL GROUNDING LAYOUT**  
NOT TO SCALE



**FACILITY - GROUNDING OF LIGHTNING PROTECTION SYSTEM**  
NOT TO SCALE

**NOTES:**


1. SEE CABLE/CONDUIT SCHEDULE SHEET FOR CABLE TAGS.
2. NOT USED
3. DETAIL SHOWS INSTALLATION IN UNPAVED AREA. WHEN INSTALLING IN A PAVED AREA, INCORPORATE GROUND WELL IN THE POUR.
4. GROUND WELLS ARE REQUIRED AT EVERY GROUND ROD.
5. SEE GROUNDING SCHEMATIC SHEET FOR MORE DETAILS.
6. PROVIDE 1" SCHEDULE 40 PVC CONDUIT FOR GROUND CABLES UNDER BUILDING (TYP.).
7. ALL COPPER GROUND BARS SHALL BE OF HARD DRAWN, COMMERCIALY PURE, ELECTROLYTIC COPPER, FOR USE AS AN ELECTRICAL CONDUCTOR AND SHALL COMPLY WITH ASTM SPEC. B-187 OF LATEST DATE.
8. BOLTS, NUTS, & WASHERS USED FOR CONNECTION TO GROUND BUSBARS SHALL BE SOLID COPPER.
9. WELD PER MANUFACTURER SPECIFICATION (ERICO PRODUCTS OR BURNDY CORP.).
10. THE COPPER GROUND BUSBAR SHALL BE MOUNTED TO THE CABLE TRAY ABOVE EQUIPMENT RACKS.
11. PROVIDE A #2 AWG GROUND CABLE FROM THE FRAME OF EACH EQUIPMENT RACK TO THE GROUND BUS AS SHOWN. THE CABLE SHALL BE BOLTED TO THE RACK USING A SEAMLESS HEAVY DUTY COMPRESSION TERMINAL.
12. A FOUR INCH GAP SHALL BE PROVIDED BETWEEN THE ENDS OF THE TWO CONDUCTORS THAT MAKE UP THE INTERNAL PERIMETER GROUND BUS CONDUCTOR.
13. ALL EQUIPMENT LOCATED INSIDE THE BUILDING SHALL BE BONDED TO THE MAIN GROUND BUS OR THE INTERNAL PERIMETER GROUND CONDUCTOR WITH A #2 AWG GROUND CABLE. ALL CONNECTIONS MUST BE EXOTHERMICALLY WELDED.
14. THE INTERNAL PERIMETER GROUND BUS CONDUCTOR MUST BE INSTALLED HORIZONTALLY ALONG THE WALL APPROXIMATELY 8 FEET ABOVE FINISHED FLOOR. THE CONDUCTOR SHALL BE SUPPORTED 2 INCHES FROM THE WALL SURFACE ON INSULATED STANDOFFS. THE STANDOFFS SHALL BE INSTALLED AT INTERVALS AS NECESSARY TO KEEP THE CONDUCTOR SECURELY IN PLACE WITHOUT NOTICEABLE SAGS AND BENDS.
15. THE GROUND BUSBARS MUST BE MOUNTED APPROXIMATELY 8 FEET ABOVE FINISHED FLOOR AND MOUNTED TO WALL USING A MOUNTING BRACKET WITH INSULATOR.

**NOTE TO DESIGNER**


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




**CONTROL BUILDING  
GROUNDING DETAILS - MAIN  
PLAZA**




**GROUND WELL ELEVATION DETAIL**  
NOTE 3



**MASTER GROUND BUSBAR  
SUPPORT SPACING DETAIL**



**MASTER GROUND BUSBAR  
CONNECTION DETAIL**  
(NOT TO SCALE)



**GROUND WELL PLAN DETAIL**

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



**CONTROL BUILDING  
GROUNDING DETAILS - MAIN  
PLAZA**

| PANELBOARD <u>MDP-1</u>  |    |            |              |       |       |                      |         |  |         | MAINS <u>250A. MCB</u>  |              |      |      |                                 |                              |  |  |  |  |
|--------------------------|----|------------|--------------|-------|-------|----------------------|---------|--|---------|-------------------------|--------------|------|------|---------------------------------|------------------------------|--|--|--|--|
| VOLTAGE <u>120/208V</u>  |    |            |              |       |       |                      |         |  |         | BUS RATING <u>300A.</u> |              |      |      |                                 |                              |  |  |  |  |
| PHASE/WIRE <u>3/4</u>    |    |            |              |       |       |                      |         |  |         | MOUNTING <u>SURFACE</u> |              |      |      |                                 |                              |  |  |  |  |
| DESCRIPTION              |    | CKT NO.    | LOAD (WATTS) |       |       | AMPS/ POLES          | CKT BKR |  | CKT BKR | AMPS/ POLES             | LOAD (WATTS) |      |      | CKT NO.                         | DESCRIPTION                  |  |  |  |  |
|                          |    |            | A            | B     | C     |                      |         |  |         |                         | A            | B    | C    |                                 |                              |  |  |  |  |
| PANEL MDP-2              | 1  | 11450      |              |       |       | 100/3                |         |  |         | 30/1                    |              |      |      | 2                               | SPARE                        |  |  |  |  |
|                          | 3  |            | 11960        |       |       |                      |         |  |         | 20/1                    |              | 200  |      | 4                               | LIGHTING CONTACTOR (CONTROL) |  |  |  |  |
|                          | 5  |            |              | 7470  |       |                      |         |  |         | 30/3                    |              |      | 2000 | 6                               | HVAC UNITS                   |  |  |  |  |
| EMERGENCY LIGHT          | 7  | 200        |              |       | 20/1  |                      |         |  | 2000    |                         |              |      | 8    |                                 |                              |  |  |  |  |
| INTERIOR LIGHTS          | 9  |            | 400          |       | 20/1  |                      |         |  |         |                         | 2000         |      | 10   |                                 |                              |  |  |  |  |
| EXTERIOR BUILDING LIGHTS | 11 |            |              | 400   | 20/1  |                      |         |  | 60/2    |                         |              | --   | 12   | SPARE                           |                              |  |  |  |  |
| MOTORIZED DAMPERS        | 13 | 180        |              |       | 20/1  |                      |         |  |         | --                      |              |      | 14   |                                 |                              |  |  |  |  |
| GEN. BATTERY CHARGER     | 15 |            | 160          |       | 20/1  |                      |         |  | 20/1    |                         | 400          |      | 16   | EXHAUST FAN                     |                              |  |  |  |  |
| GEN. JACKET WATER HTR.   | 17 |            |              | 1500  | 20/1  |                      |         |  | 20/1    |                         |              | --   | 18   | SPARE                           |                              |  |  |  |  |
| EXTERIOR RECEPTACLE      | 19 | 400        |              |       | 20/1  |                      |         |  | 20/1    | 400                     |              |      | 20   | INTERIOR RECEPTACLES            |                              |  |  |  |  |
| EXTERIOR RECEPTACLE      | 21 |            | 400          |       | 20/1  |                      |         |  | 20/1    |                         | 400          |      | 22   | INTERIOR RECEPTACLES            |                              |  |  |  |  |
| SPARE                    | 23 |            |              | --    | 20/1  |                      |         |  | 20/1    |                         |              | 400  | 24   | INTERIOR RECEPTACLES            |                              |  |  |  |  |
| SPARE                    | 25 | --         |              |       | 20/2  |                      |         |  | 20/2    | 375                     |              |      | 26   | ELECTRIC CEILING MOUNTED HEATER |                              |  |  |  |  |
|                          | 27 |            | --           |       |       |                      |         |  |         |                         | 375          |      | 28   |                                 |                              |  |  |  |  |
| VES WASH SYSTEM (LOC 1)  | 29 |            |              | 2500  | 30/1  |                      |         |  | 30/2    |                         |              | --   | 30   | UPS-1 (TOLLING)                 |                              |  |  |  |  |
| SPARE                    | 31 |            |              |       | 40/1  |                      |         |  |         | --                      |              |      | 32   |                                 |                              |  |  |  |  |
| ROADWAY LTG TRANSFORMER  | 33 |            | 960          |       | 20/2  |                      |         |  | 30/2    |                         | --           |      | 34   | SPARE                           |                              |  |  |  |  |
|                          | 35 |            |              | 960   |       |                      |         |  |         |                         |              | 1252 | 36   | UPS-ITS-1 (5 KVA)               |                              |  |  |  |  |
| SPARE                    | 37 |            | --           |       | 30/1  |                      |         |  |         | 1252                    |              |      | 38   |                                 |                              |  |  |  |  |
| SPARE                    | 39 |            |              |       | 20/1  |                      |         |  | 20/1    |                         | --           |      | 40   | SPARE                           |                              |  |  |  |  |
| SPARE                    | 41 |            |              |       | 20/1  |                      |         |  | 20/1    |                         |              | --   | 42   | SPARE                           |                              |  |  |  |  |
|                          |    |            |              |       |       |                      |         |  |         |                         |              |      |      |                                 |                              |  |  |  |  |
| "A"                      |    |            | 15830        |       |       | SUBTOTAL "A" = 22257 |         |  |         |                         | 6427         |      |      |                                 | "A"                          |  |  |  |  |
| "B"                      |    |            |              | 13880 |       | SUBTOTAL "B" = 17255 |         |  |         |                         |              | 3375 |      |                                 | "B"                          |  |  |  |  |
| "C"                      |    |            |              |       | 12830 | SUBTOTAL "C" = 16682 |         |  |         |                         |              |      | 3852 |                                 | "C"                          |  |  |  |  |
| TOTAL WATTS "A,B,C"      |    | = 56.19 KW |              |       |       |                      |         |  |         |                         |              |      |      |                                 |                              |  |  |  |  |

| PANELBOARD                 |  |    |              | UPS-1       |         |  | MAINS      |             |              |         | 30A. 2P. MCB                          |  |  |
|----------------------------|--|----|--------------|-------------|---------|--|------------|-------------|--------------|---------|---------------------------------------|--|--|
| VOLTAGE                    |  |    |              | 120V./208V. |         |  | BUS RATING |             |              |         | 60A.                                  |  |  |
| PHASE/WIRE                 |  |    |              | 1/3         |         |  | MOUNTING   |             |              |         | SURFACE                               |  |  |
| DESCRIPTION                |  |    | LOAD (WATTS) | AMPS/ POLES | CKT NO. |  | CKT NO.    | AMPS/ POLES | LOAD (WATTS) | CKT NO. | DESCRIPTION                           |  |  |
| SPARE                      |  | 1  | —            | 20/1        |         |  |            | 20/1        | 400          | 2       | RACK RECEPTACLE (LCC)                 |  |  |
| SPARE                      |  | 3  | —            | 20/1        |         |  |            | 20/1        | 400          | 4       | RACK RECEPTACLE (I-PASS)              |  |  |
| SPARE                      |  | 5  | —            | 20/1        |         |  |            | 20/1        | 400          | 6       | RACK RECEPTACLE (FIBER)               |  |  |
| SPARE                      |  | 7  | —            | 20/1        |         |  |            | 20/1        | 200          | 8       | CARD READER PANEL                     |  |  |
| VIDEO POWER JUNCTION BOX 1 |  | 9  | 500          | 20/1        |         |  |            | 20/1        | —            | 10      | SPARE                                 |  |  |
| VIDEO POWER JUNCTION BOX 2 |  | 11 | 400          | 20/1        |         |  |            | 20/1        | 65           | 12      | VIDEO POWER JUCTION BOX (DATA LOGGER) |  |  |
| SUBTOTAL "A"               |  |    | 900          |             |         |  |            |             | 1465         |         |                                       |  |  |
| TOTAL WATTS "A,B"          |  |    | = 2.4 KW     |             |         |  |            |             |              |         |                                       |  |  |


|                   |  |   |              |             |         |            |         |             |              |              |                      |
|-------------------|--|---|--------------|-------------|---------|------------|---------|-------------|--------------|--------------|----------------------|
| PANELBOARD        |  |   |              | ITS 1       |         | MAINS      |         |             |              | 30A. 2P. MCB |                      |
| VOLTAGE           |  |   |              | 120V / 208V |         | BUS RATING |         |             |              | 60A.         |                      |
| PHASE/WIRE        |  |   |              | 1/3         |         | MOUNTING   |         |             |              | SURFACE      |                      |
| DESCRIPTION       |  |   | LOAD (WATTS) | AMPS/ POLES | CKT NO. |            | CKT NO. | AMPS/ POLES | LOAD (WATTS) | CKT NO.      | DESCRIPTION          |
| 5 KVA TRANSFORMER |  | 1 | —            | 30/2P       |         |            |         | 10/1P       | 200          | 2            | ITS RACK RECEPTACLES |
|                   |  | 3 |              |             |         |            |         | 10/1P       | —            | 4            | SPARE                |
| SPARE             |  | 5 | —            | 10/1P       |         |            |         | 10/1P       |              | 6            | SPARE                |
| SPARE             |  | 7 | —            | 10/1P       |         |            |         | 10/1P       |              | 8            | SPARE                |
|                   |  |   |              |             |         |            |         |             |              |              |                      |
|                   |  |   |              |             |         |            |         |             |              |              |                      |
| SUBTOTAL = ---    |  |   | —            |             |         |            |         |             | 200          |              |                      |
| TOTAL WATTS "A,B" |  |   | = 0.2 KW     |             |         |            |         |             |              |              |                      |

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



PANELBOARD SCHEDULES  
- MAIN PLAZA



FRONT & REAR VES CAMERA VIDEO POWER  
JUNCTION BOX - MAIN PLAZA  
ALTERNATIVE LAYOUT  
NOT TO SCALE

NOTES TO DESIGNER


- THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.
- THE DESIGNER SHALL ADJUST DETAIL AND QUANTITIES AS REQUIRED FOR NUMBER OF VES CAMERAS.
- THE DESIGNER SHALL INCLUDE VIDEO POWER JUNCTION BOX DETAILS (MHTS-2100 SERIES BASE SHEETS) FOR SECURITY CAMERAS AND DATA LOGGER CAMERA.

EQUIPMENT LEGEND - VIDEO POWER JUNCTION BOX  
(ALTERNATIVE LAYOUT)


| ITEM | QUANTITY<br>(SAMPLE) | DESCRIPTION   |
|------|----------------------|---|
| ①    | 1                    | 48"H X 24"W X 8"D NEMA 1 ENCLOSURE WITH 44"H X 22 1/2"W BACK PANEL, HOFFMAN CATALOG NO. A-48N24BLP, WITH A-48N24MP PANEL.   |
| ②    | 2                    | POWER SUPPLY, 24VDC, TDK-LAMBDA NO. QM7FSDL 24/24DMS 24/24DMS 24/24DMS 24/24DMS 24/24DMS.   |
| ③    | 12                   | TERMINAL BLOCKS, FUSE SWITCH TYPE WITH BLOWN FUSE INDICATOR COMPLETE WITH 5 AMP FUSE, MOUNTING RAIL, ANCHORS, BARRIERS, MARKING STRIPS AND JUMPERS, ALLEN BRADLEY CATALOG NO. 1492-FB1M30-D1. |
| ④    | 21                   | TERMINAL BLOCKS, ON POLE PANEL MOUNT BLOCK SCREW TERMINAL WITH WIRE CLAMP, ALLEN BRADLEY CATALOG NO. 1492-CD6.  |
| ⑤    | 1                    | GROUND BAR SYSTEM WITH INSULATED MOUNTING BRACKET, HOFFMAN CATALOG NO. PGS2K.   |
| ⑥    | LOT                  | PANDUIT PLASTIC WIRING DUCT SNAP-IN SLOT DESIGN AND NON-SLIP COVER, 1"W X 1"H, CATALOG NO. F1X1LG6 WITH COVER C1LG6.  |
| ⑦    | 1                    | POWER DISTRIBUTION BLOCK MARATHON NO. 1322580.  |
| ⑧    | 4                    | SQUARE D, QOU 115 1P/15A BREAKER.   |
| ⑨    | 10                   | SURGE SUPPRESSOR MTL MODEL ZB24580.   |
| ⑩    | 1                    | SQUARE AXIAL FAN 4 1/16" x 4 1/16", 1 1/2" IN DEPTH, 115 CFM, IP20, CAST ALUMINUM FRAME, 115V AC, AND COMPACT AXIAL FAN GUARD 4 1/16" x 4 1/16"   |

EQUIPMENT LEGEND -  
VIDEO POWER JUNCTION BOX


| ITEM | QUANTITY | DESCRIPTION   |
|------|----------|---|
| ①    | 1        | 48"H X 24"W X 8"D NEMA 1 ENCLOSURE WITH 44"H X 22 1/2"W BACK PANEL, HOFFMAN CATALOG NO. A-48N24BLP, WITH A-48N24MP PANEL.   |
| ②    | 4        | POWER SUPPLY 24VDC, MEANWELL MODEL NO. SDR-240-24   |
| ③    | 24       | TERMINAL BLOCKS, FUSE SWITCH TYPE WITH BLOWN FUSE INDICATOR COMPLETE WITH 5 AMP FUSE, MOUNTING RAIL, ANCHORS, BARRIERS, MARKING STRIPS AND JUMPERS, ALLEN BRADLEY CATALOG NO. 1492-FB1M30-D1. |
| ④    | 42       | TERMINAL BLOCKS, ON POLE PANEL MOUNT BLOCK SCREW TERMINAL WITH WIRE CLAMP, ALLEN BRADLEY CATALOG NO. 1492-CD6.  |
| ⑤    | 1        | GROUND BAR SYSTEM WITH INSULATED MOUNTING BRACKET, HOFFMAN CATALOG NO. PGS2K.   |
| ⑥    | LOT      | PANDUIT PLASTIC WIRING DUCT SNAP-IN SLOT DESIGN AND NON-SLIP COVER, 1"W X 1"H, CATALOG NO. F1X1LG6 WITH COVER C1LG6.  |
| ⑦    | 1        | POWER DISTRIBUTION BLOCK MARATHON NO. 1322580.  |
| ⑧    | 4        | SQUARE D, QOU 115 1P/15A BREAKER.   |
| ⑨    | 20       | SURGE SUPPRESSOR MTL MODEL ZB24580.   |
| ⑩    | 1        | SQUARE AXIAL FAN 4 1/16" x 4 1/16", 1 1/2" IN DEPTH, 115 CFM, IP20, CAST ALUMINUM FRAME, 115V AC, AND COMPACT AXIAL FAN GUARD 4 1/16" x 4 1/16".  |



BOTTOM PLATE  
VENTILATION HOLE DETAIL



SIDE PLATE  
VENTILATION HOLE DETAIL



FRONT & REAR VES CAMERA  
VIDEO POWER JUNCTION BOX  
N.T.S.  
VIDEO POWER JUNCTION BOX REMOTE PLAZA

NOTES:


- LABEL JUNCTION BOX, TERMINAL STRIPS, AND ALL WIRE AND CABLES.
- ROUTE 1-2/C #12 POWER CABLE TO EACH CAMERA.
- ALL ELECTRICAL CABLES TO CAMERA SHALL HAVE SURGE PROTECTION.
- CAT6 CABLE SHALL BE SURGE PROTECTED ON THE TSIC.



VIDEO POWER JUNCTION BOX  
DETAIL - MAIN PLAZA

NOTES:

1. SEE CABLE AND CONDUIT SCHEDULE. SHEET FOR CABLE TAGS.
2. SEE AET WIRING DIAGRAMS SHEET FOR MONOTUBE WIRING.
3. NOT USED.
4. CAP ALL CONDUIT STUBS FOR FUTURE USE.
5. FINAL LOCATION OF ALL HANDHOLES AND JUNCTION BOXES SHALL BE APPROVED BY THE ENGINEER.
6. NOT USED.
7. ROUTE PLAZA ROADWAY LIGHTING CIRCUITS TO LIGHTING CONTRACTOR. THESE STAY ON PLAZA CIRCUITS, THAT ARE POWERED FROM PLAZA EMERGENCY GENERATOR. ROUTE 2-1/C #8 AND 1/C #8 GROUND WIRE FROM LIGHTING CONTRACTOR LOCATED IN THE POWER CABINET TO THE LIGHT POLE FOR PLAZA LIGHTING CONTROL CIRCUIT. PROVIDE PHOTOCELL ON SAME POLE.
8. ALL EXCESS (SLACK) POWER AND DATA CABLES MUST BE COILED IN THE HANDHOLE. NO EXCESS CABLE WILL BE COILED INSIDE THE BUILDING.
9. EXOTHERMICALLY WELD THE GROUND WIRE TO THE MONOTUBE'S BASE.
10. REFER TO TSIC TERMINAL BLOCK LAYOUT SHEET. LOW VOLTAGE WIRE FROM VES AND SECURITY CAMERAS LAND ON SURGE PROTECTION DEVICES.
11. PVC CONDUIT SHALL BE USED WHEN THE CONDUIT IS EITHER COVERED OR ENCASED IN CONCRETE. ANY EXPOSED CONDUIT SHALL BE PVC COATED RGS. SLEEVES SHALL BE USED WHEN CROSSING WALL FOUNDATIONS.
12. LOCATION OF LANE STUB UPS TO BE APPROVED BY THE ILLINOIS TOLLWAY PRIOR TO CONCRETE POUR. FINAL LOCATION OF EQUIPMENT TO BE APPROVED BY THE ENGINEER.
13. PROVIDE (2) 4" PVC COATED RGS 5FT PAST RETAINING WALL UP TO ComEd TRANSFORMER FOR ComEd INCOMING PRIMARY CABLES. INSTALL SLEEVE IN COORDINATION WITH STRUCTURAL AND STUB UP NEAR ComEd TRANSFORMER LOCATION. PROVIDE WATER PROOF SEALING AT RETAINING WALL.
14. RIGID METALLIC CONDUIT PVC COATED FOR MONOTUBE POWER/DATA/ANTENNA CABLING SHALL RUN IN OVERHEAD CONDUIT TRAY. SEE OVERHEAD CONDUIT TRAY DETAILS..
15. SEE VES CAMERA WASH SYSTEM SHEETS FOR DETAILS. THIS WORK WILL BE PAID UNDER PAY ITEM JT132701 "VES CAMERA HIGH PRESSURE WASH SYSTEM, LOCATION 2".
16. FOR LIGHT POLE AND FOUNDATION DETAILS, SEE ILLINOIS TOLLWAY STANDARD DRAWINGS H1 AND H2.
17. NOT USED.
18. PROVIDE (2) 6" SDR 11 HDPE SLEEVES, EACH SLEEVE SHALL HAVE;  
(1) 1 1#2" CNC DUCT (SOLID GREEN)  
(1) 1 1#2" CNC DUCT (GREEN/WHITE STRIPE)  
(1) 1 1#2" CNC DUCT (BLACK/RED STRIPE)




NOT TO SCALE

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



UNDERGROUND CONDUIT  
PLAN - REMOTE PLAZA



NOTES:

1. MINIMUM CONDUIT SIZE IS 1-1/2".
2. LOOP WIRE SPLICES ARE MADE IN JUNCTION BOXES.
3. CONDUITS FOR LOOPS ARE TO BE 1-1/2" RIGID GALVANIZED STEEL PVC COATED.
4. LOOPS PROVIDED AND INSTALLED BY THE ILLINOIS TOLLWAY. LOOPS PULLED BACK TO JUNCTION BOXES IN BARRIER WALL. SEE LOOP INSTALLATION DETAILS. CONTRACTOR SHALL COORDINATE WITH ILLINOIS TOLLWAY FOR PROVIDING SLOT OPENING, SAW CUTTING AND OTHER MISCELLANEOUS WORK REQUIRED FOR COMPLETE LOOP INSTALLATION.
5. VERIFY THE CONDUIT, MONOTUBES AND VES CAMERA POLE LOCATIONS WITH THE ILLINOIS TOLLWAY PRIOR TO BARRIER CONSTRUCTION.
6. EQUIPMENT LOCATIONS MUST BE VERIFIED BY THE ILLINOIS TOLLWAY PRIOR TO ANY CONSTRUCTION STARTING. LOCATION OF ALL LANE LOOPS AND LANE STUB UPS SHALL BE APPROVED BY THE ILLINOIS TOLLWAY BEFORE CONCRETE POUR CONTRACTOR TO COORDINATE WITH THE ENGINEER.
7. SEE CONDUIT ROUTING DETAILS.
8. CONTRACTOR IS TO PROVIDE ALL CONDUIT AND LOOP LEAD IN CABLE FROM BUILDING TO JUNCTION BOX IN BARRIER WALL. 3 FEET OF CABLE COILED IN JUNCTION BOX AT BARRIER WALL.
9. ALL LOOP DETECTORS SHALL BE IN THE CENTER OF THE STRIPED LANES.
10. CONDUITS AND CONDUIT STUB UPS SHOWN SHALL BE INSTALLED IN ALL LANES (TRAVEL LANES AND SHOULDERS).
11. LEAD EDGE OF LOOP 2 SHALL BE 6" DOWNSTREAM OF MONOTUBE CENTERLINE.
12. PIEZO AND QUANTUM SYSTEM LOOPS SHALL BE INSTALLED IN TRAVEL LANES ONLY.

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.


**NOTE TO DESIGNER**

DSE TO CONFIRM THE CORRECT NUMBER OF DETECTOR LEAD-IN CABLES (DLCs) ROUTED TO THE BARRIER JUNCTIONBOXES, BASED ON THE LAYOUT SHOWN HERE.

- A. SHOULDERS - (4) DLCs EACH SHOULDER FOR MAIN LOOPS.
- B. TRAVEL LANES - (6) DLCs EACH TRAVEL LANE: (4) MAIN LOOPS + (1) PIEZO ANGLE LOOP + (1) SPARE



LOOP PLAN - AET 3-LANE LAYOUT



1-LANE AET EQUIPMENT AND LOOP LAYOUT

LEGEND:  
A - ANTENNA  
M - MAINLINE LOOP  
N - NARROW LOOP  
P - BL PIEZO SENSOR

NOTES:

1. MINIMUM CONDUIT SIZE IS 1-1/2".
2. LOOP WIRE SPLICES ARE MADE IN JUNCTION BOXES.
3. CONDUITS FOR LOOPS ARE TO BE 1-1/2" RIGID GALVANIZED STEEL PVC COATED.
4. LOOPS PROVIDED AND INSTALLED BY THE ILLINOIS TOLLWAY. LOOPS PULLED BACK TO JUNCTION BOXES IN BARRIER WALL. SEE LOOP INSTALLATION DETAILS. CONTRACTOR SHALL COORDINATE WITH ILLINOIS TOLLWAY FOR PROVIDING SLOT OPENING, SAW CUTTING AND OTHER MISCELLANEOUS WORK REQUIRED FOR COMPLETE LOOP INSTALLATION.
5. VERIFY THE CONDUIT, MONOTUBES AND VES CAMERA POLE LOCATIONS WITH THE ILLINOIS TOLLWAY PRIOR TO BARRIER CONSTRUCTION.
6. EQUIPMENT LOCATIONS MUST BE VERIFIED BY THE ILLINOIS TOLLWAY PRIOR TO ANY CONSTRUCTION STARTING. LOCATION OF ALL LANE LOOPS AND LANE STUB UPS SHALL BE APPROVED BY THE ILLINOIS TOLLWAY BEFORE CONCRETE POUR CONTRACTOR TO COORDINATE WITH THE ENGINEER.
7. SEE CONDUIT ROUTING DETAILS.
8. CONTRACTOR IS TO PROVIDE ALL CONDUIT AND LOOP LEAD IN CABLE FROM BUILDING TO JUNCTION BOX IN BARRIER WALL. 3 FEET OF CABLE COILED IN JUNCTION BOX AT BARRIER WALL.
9. ALL LOOP DETECTORS SHALL BE IN THE CENTER OF THE STRIPED LANES.
10. CONDUITS AND CONDUIT STUB UPS SHOWN SHALL BE INSTALLED IN ALL LANES (TRAVEL LANES AND SHOULDERS).
11. LEAD EDGE OF LOOP 2 SHALL BE 6" DOWNSTREAM OF MONOTUBE CENTERLINE.
12. PIEZO AND QUANTUM SYSTEM LOOPS SHALL BE INSTALLED IN TRAVEL LANES ONLY.




NOTE TO DESIGNER  
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTE TO DESIGNER  
DSE TO CONFIRM THE CORRECT NUMBER OF DETECTOR LEAD-IN CABLES (DLCs) ROUTED TO THE BARRIER JUNCTION BOXES, BASED ON THE LAYOUT SHOWN HERE.  
A. SHOULDERS - (4) DLCs EACH SHOULDER FOR MAIN LOOPS.  
B. TRAVEL LANES - (6) DLCs EACH TRAVEL LANE: (4) MAIN LOOPS + (1) PIEZO ANGLE LOOP + (1) SPARE



LOOP PLAN - AET 1-LANE LAYOUT





**NOTES:**

1. REFER TO TOLL EQUIPMENT WIRING DIAGRAM.
2. VIOLATION CAMERAS SHALL BE INSTALLED BY THE TOLLWAY.
3. USE GALVANIZED STEEL SHIMS UNDER THE BASE PLATE TO PLUMB THE CAMERA PEDESTAL.
4. THE GROUND WIRE MUST BE EXOTHERMICALLY WELDED OR MECHANICALLY BONDED TO THE CAMERA PEDESTAL AS DIRECTED BY THE ENGINEER.
5. NEW STROBE ILLUMINATOR.

**EQUIPMENT LEGEND**


| ITEM | DESCRIPTION                                    |
|------|--|
| ①    | CAMERA FURNISHED AND INSTALLED BY THE TOLLWAY. |
| ②    | 4" ALUMINIUM POST.                             |
| ③    | TRAFFIC WHITE LIGHT ILLUMINATOR                |



**GROUND MOUNTED VES CAMERA WITH VES WASH TUBING**

NOTES:

1. SEE CABLE/CONDUIT SCHEDULE AND NOTES SHEET FOR CABLE TAGS.
2. FRONT AND REAR VES CAMERA CABLES ARE PULLED BY THE CONTRACTOR INTO MONOTUBE AND POLE ARM. THE CONTRACTOR WHIPS UP ABOUT 10 FEET OF CABLE, LEAVING THE MAJORITY INSIDE THE MONOTUBE/POLE ARM. THE ILLINOIS TOLLWAY WILL PULL FROM THE JB/POLE ARM TO THE CAMERAS AND THEN TERMINATE.
3. VES CAMERA NUMBERING SCHEME BEGIN AT RIGHT SHOULDER AND ARE ORDERED SEQUENTIALLY (1, 2, 3, ... ETC) TO LEFT SHOULDER.
4. ALL CABINETS AND POWER PANEL LOCATED IN CONTROL BUILDING.
5. COAX FOR AVI ANTENNAS ROUTE THROUGH 2" TO 1" COUPLER (IF REQUIRED), THEN RUN IN 1" SEALTITE CONDUIT TO ANTENNA.
6. EQUIPMENT LOCATIONS MUST BE VERIFIED BY THE ILLINOIS TOLLWAY PRIOR TO CONSTRUCTION AND INSTALLATION.
7. IF VES CAMERAS ARE MOUNTED 18' ABOVE THE ROADWAY, THEN THE CAMERAS SHALL BE PLACED 33' HORIZONTAL FROM THE TRIGGER.
8. THIS CABLING IS USED TO POWER THE VES CAMERAS. THESE CABLES WILL RUN FROM A 24V DC POWER SUPPLY LOCATED IN THE VPJB.
9. DATA LOGGER CAMERA SHALL BE PLACED DOWNSTREAM OF THE EXITING MONOTUBE ON A NON-BREAKAWAY DEDICATED ITS POLE. DATA LOGGER CAMERA POWER AND SIGNAL WILL GO THROUGH CAT 6 ETHERNET CABLE. MOUNT DATA LOGGER CAMERA AT 20'.
10. 1.5" SEALTITE AND FITTINGS ARE FURNISHED BY THE CONTRACTOR AND INSTALLED BY THE ILLINOIS TOLLWAY.
11. ALL WIRING FROM CAMERAS/I-PASS ANTENNAS SHALL BE SURGE PROTECTED AS IT ENTERS PLAZA BUILDING. SURGE PROTECTION SHALL BE IN VES VPJB FOR CAMERAS AND IN COMMUNICATION ROOM FOR ANTENNA CABLE.
12. PROVIDE 14 FT PERPENDICULAR OUTRIGGER SUPPORT FOR VES CAMERA POLE AND THE ANTENNA POLE DUE TO THE NEEDS OF MULTIPROTOCOL READERS ONLY. MAINTAIN THE POSITION OF THE VES SUPPORT POLE SO THE LONGER OUTRIGGER WILL NEED TO CANTILEVER MORE TOWARDS THE DEPARTURE SIDE OF THE MONOTUBE.
13. NOT USED.
14. CONTRACTOR SHALL FURNISH AND INSTALL JUNCTION BOX 12"x12"x6" TYPE NEMA 4X, (HOFFMAN A1212CHNFSS) ON DOWNSTREAM SIDE OF THE ENTRANCE AND EXIT MONOTUBES FOR TERMINATION OF POWER AND COMMUNICATION CABLES. SEE STRUCTURAL DRAWINGS FOR LOCATION.
15. REAR PLATE CAMERAS ARE MOUNTED 2'-6" UPSTREAM FROM C/L OF MONOTUBE AND AVI ANTENNAS ARE MOUNTED 2'-6" DOWNSTREAM FROM C/L OF MONOTUBE.



FRONT - REAR PLATE VES BLOCK WIRING DIAGRAM

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

**NOTE TO DESIGNER**

VES CAMERAS ON SHOULDERS ARE NOT TYPICALLY INSTALLED. SHOWN HERE FOR COMPLETION, BUT SHOULD BE REMOVED BY DESIGNER UNLESS THEY ARE SPECIFICALLY REQUESTED BY ILLINOIS TOLLWAY.

LEGEND:

- \* INDICATES EQUIPMENT FURNISHED BY THE ILLINOIS TOLLWAY AND INSTALLED BY THE CONTRACTOR.
- \*\* INDICATES EQUIPMENT FURNISHED AND INSTALLED BY THE ILLINOIS TOLLWAY.
- INDICATES EQUIPMENT FURNISHED AND INSTALLED BY THE CONTRACTOR.



WIRING DIAGRAM - AET  
3-LANE LAYOUT

NOTES:

1. SEE CABLE/CONDUIT SCHEDULE AND NOTES SHEET FOR CABLE TAGS.

2. FRONT AND REAR VES CAMERA CABLES ARE PULLED BY THE CONTRACTOR INTO MONOTUBE AND POLE ARM. THE CONTRACTOR WHIPS UP ABOUT 10 FEET OF CABLE, LEAVING THE MAJORITY INSIDE THE MONOTUBE/POLE ARM. THE ILLINOIS TOLLWAY WILL PULL FROM THE JB/POLE ARM TO THE CAMERAS AND THEN TERMINATE.

3. VES CAMERA NUMBERING SCHEME BEGIN AT RIGHT SHOULDER AND ARE ORDERED SEQUENTIALLY (1, 2, 3, ... ETC) TO LEFT SHOULDER.

4. ALL CABINETS AND POWER PANEL LOCATED IN CONTROL BUILDING.

5. COAX FOR AVI ANTENNAS ROUTE THROUGH 2" TO 1" COUPLER (IF REQUIRED), THEN RUN IN 1" SEALTITE CONDUIT TO ANTENNA.
6. EQUIPMENT LOCATIONS MUST BE VERIFIED BY THE ILLINOIS TOLLWAY PRIOR TO CONSTRUCTION AND INSTALLATION.

7. IF VES CAMERAS ARE MOUNTED 18' ABOVE THE ROADWAY, THEN THE CAMERAS SHALL BE PLACED 33' HORIZONTAL FROM THE TRIGGER.

8. THIS CABLING IS USED TO POWER THE VES CAMERAS. THESE CABLES WILL RUN FROM A 24V DC POWER SUPPLY LOCATED IN THE VPJB.

9. DATA LOGGER CAMERA SHALL BE PLACED DOWNSTREAM OF THE EXITING MONOTUBE ON A NON-BREAKAWAY DEDICATED ITS POLE. DATA LOGGER CAMERA POWER AND SIGNAL WILL GO THROUGH CAT 6 ETHERNET CABLE. MOUNT DATA LOGGER CAMERA AT 20'.

10. 1.5" SEALTITE AND FITTINGS ARE FURNISHED BY THE CONTRACTOR AND INSTALLED BY THE ILLINOIS TOLLWAY.
11. ALL WIRING FROM CAMERAS/I-PASS ANTENNAS SHALL BE SURGE PROTECTED AS IT ENTERS PLAZA BUILDING. SURGE PROTECTION SHALL BE IN VES VPJB FOR CAMERAS AND IN COMMUNICATION ROOM FOR ANTENNA CABLE.

12. PROVIDE 14 FT PERPENDICULAR OUTRIGGER SUPPORT FOR VES CAMERA POLE AND THE ANTENNA POLE DUE TO THE NEEDS OF MULTIPROTOCOL READERS ONLY. MAINTAIN THE POSITION OF THE VES SUPPORT POLE SO THE LONGER OUTRIGGER WILL NEED TO CANTILEVER MORE TOWARDS THE DEPARTURE SIDE OF THE MONOTUBE.

13. NOT USED.

14. CONTRACTOR SHALL FURNISH AND INSTALL JUNCTION BOX 12"x12"x6" TYPE NEMA 4X, HOFFMAN A1212CHNFSS ON DOWNSTREAM SIDE OF THE ENTRANCE AND EXIT MONOTUBES FOR TERMINATION OF POWER AND COMMUNICATION CABLES (EXCEPT AVI CABLES). SEE STRUCTURAL DRAWINGS FOR LOCATION.

15. REAR PLATE CAMERAS ARE MOUNTED 2'-6" UPSTREAM FROM C/L OF MONOTUBE AND AVI ANTENNAS ARE MOUNTED 2'-6" DOWNSTREAM FROM C/L OF MONOTUBE.

NOTE TO DESIGNER


SHOULDER VES CAMERAS ARE SHOWN FOR COMPLETION, BUT TYPICALLY NOT INSTALLED. DELETE IF NOT SPECIFICALLY REQUESTED BY ILLINOIS TOLLWAY BUSINESS SYSTEMS.

LEGEND:

- \* INDICATES EQUIPMENT FURNISHED BY THE ILLINOIS TOLLWAY AND INSTALLED BY THE CONTRACTOR.
- \*\* INDICATES EQUIPMENT FURNISHED AND INSTALLED BY THE ILLINOIS TOLLWAY.
- INDICATES EQUIPMENT FURNISHED AND INSTALLED BY THE CONTRACTOR.

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




FRONT / REAR PLATE VES BLOCK WIRING DIAGRAM




WIRING DIAGRAM - AET  
1-LANE LAYOUT




**SECTION A-A**  
NOT TO SCALE  
M-BUS-2521



**SECTION C-C**  
NOT TO SCALE



**SECTION B-B**  
NOT TO SCALE  
M-BUS-2521



**SECTION D-D**  
NOT TO SCALE

**NOTE FOR DESIGNER:**  
AIR TERMINAL RODS ARE TO BE INSTALLED AND FIXED TO ROOF WITHOUT INTERFERING WITH THE INTEGRITY OF THE STRUCTURE.



**EXTERIOR ELEVATIONS - REMOTE PLAZA**

NOTES:

- SEE CABLE/CONDUIT SCHEDULES SHEET FOR CABLE TAGS.
- SEE SYSTEM POWER SINGLE LINE DIAGRAM SHEET FOR DETAILS.
- DOOR ALARM SWITCH, SEE DETAIL ON DOOR ALARMS DETAILS SHEET.
- PROVIDE A 3 PAIR #22 SHIELDED CABLE FOR ATS ALARMS AND ROUTE TO TSIC BOARD. ALL CONTACT CLOSURES SHALL BE ROUTED TO TSIC.
- THE LIGHTNING PROTECTION SYSTEM DEVICE SHALL BE CONNECTED TO THE LOAD SIDE OF THE MAIN BREAKER.
- FOR ROADWAY LIGHTING. ROUTE TO 30A. CIRCUIT BREAKER
- ALL EXCESS (SLACK) POWER AND DATA CABLES MUST BE COILED IN THE HANDHOLE. NO EXCESS CABLES WILL BE COILED INSIDE THE CABINET.
- NOT USED.
- PVC SCH-80 CONDUIT INSIDE BUILDING SHALL BE USED WHEN THE CONDUIT IS EITHER COVERED OR ENCASED IN CONCRETE. TRANSITION SHALL BE ALLOWED. ANY EXPOSED CONDUIT SHALL BE PVC COATED RGS. SLEEVES SHALL BE USED WHEN DEEMED NECESSARY.
- THE CABLE LENGTH FROM THE ANTENNA TO THE I-PASS READER SHALL NOT EXCEED 150 FEET.
- PROVIDE A 3 PAIR #22 SHIELDED CABLE FOR SMOKE DETECTOR ALARM CONTACT AND ROUTE TO CARD READER EQUIPMENT.
- PROVIDE AN ETHERNET CABLE FROM UPS AND FROM CARD READER PANEL TO LOCAL BACKBONE RACK. NETWORK SWITCHES TO BE PROCURED BY OTHERS.
- TERMINATE ALARM CABLES ON TERMINAL BLOCK ON TSIC BOARD.
- NOT USED.
- POWER FRONT AND REAR VES CAMERAS FROM 24V DC VIDEO JUNCTION BOX #3 AND DATA LOGGER CAMERA FROM SECURITY VIDEO JUNCTION BOX #4 ALL POWER TO BE SURGE PROTECTED.
- ALL COPPER COMMUNICATIONS AND CONTROL CABLES SHALL ENTER BUILDING ALONG OUTSIDE WALL AND BE CONNECTED TO A SURGE PROTECTION THAT IS GROUNDED TO GROUND BUS IN BUILDING.
- LOCATION OF (6) RACKS BE IN THE MIDDLE OF THE ROOM.
- FOR SECURITY CAMERA, CONTRACTOR TO VERIFY CLEAR UNOBSTRUCTED LINE OF SIGHT TO THE ENTRANCE DOORS.
- INSTALL TRANSFORMER ON 6" CONCRETE PAD 1 FT AWAY FROM EXTERIOR WALL. ALL FEED TO THIS TRANSFORMER SHALL BE UNDERGROUND.
- PROVIDE (2) 6" SDR 11 HDPE SLEEVES EACH, SEE BASE SHEET \$M-BUS-2547 FOR DETAILS  
SLEEVE SHALL HAVE:  
(1) 1 1/2" CNC DUCT (SOLID GREEN)  
(1) 1 1/2" CNC DUCT (GREEN / WHITE STRIPE)  
(1) 1 1/2" CNC DUCT (BLACK / RED STRIPE)

LEGEND

|    |   |    |  |    |   |    |                   |
|----|---|----|--|----|---|----|-------------------|
| 1  | BUILDING DISCONNECT WP-NEMA 4X                                  | 14 | ELECTRICAL PANEL MDP-2   | 25 | CABLE TRAY  | 35 | SMOKE DETECTOR    |
| 2  | NOT USED.   | 15 | 19" RACK LOCAL AND BACKBONE FIBER  | 26 | VIDEO JB POWER #4                                 | 36 | NOT USED.         |
| 3  | LIGHTING TRANSFORMER, CONTRACTOR, AND CIRCUIT BREAKER           | 16 | 19" RACK ITS FIBER   | 27 | TSIC BOARD  | 37 | MAGNETIC LOCK     |
| 4  | NOT USED.   | 17 | 19" RACK I-PASS READER REMOTE PLAZA  | 28 | SMF DISTRIBUTION PANEL                            | 38 | NOT USED.         |
| 5  | VIDEO JB POWER #3   | 18 | 19" RACK LANE CONTROL REMOTE PLAZA   | 29 | NOT USED.   | 39 | ITS 2-1 PANEL     |
| 6  | BYPASS SWITCH   | 19 | NOT USED.  | 30 | NOT USED.   | 40 | FIRE EXTINGUISHER |
| 7  | UPS-2 PANEL.  | 20 | NOT USED.  | 31 | DISCONNECT SWITCH 60A/1P, 250V FOR AIR COMPRESSOR | 41 | HVAC UNIT - 1     |
| 8  | SPD LIGHTNING PROTECTION SYSTEM                                 | 21 | CARD READER  | 32 | VES WASH CABINET                                  | 42 | HVAC UNIT - 2     |
| 9  | SECURITY CAMERA   | 22 | UPS/LINE CONDITIONER. CONTRACTOR SHALL INSTALL THE 3KVA UPS ABOVE GROUND, ON A SHELVING SYSTEM AS DIRECTED BY THE ENGINEER | 33 | PANEL UPS-2                                       | 43 | 30A/2P C/B        |
| 10 | CARD READER PANEL   | 23 | BYPASS SWITCH LINE CONDITIONER ITS POWER   | 34 | PULL STATION                                      |    |                   |
| 11 | HVAC CONTROL PANEL  | 24 | BYPASS SWITCH CABINET ITS POWER  |    |   |    |                   |
| 12 | UPS-ITS-2 (5 KVA)   |    |  |    |   |    |                   |
| 13 | 5 KVA, 208V/480V OUTDOOR TYPE SINGLE PHASE TRANSFORMER, NEMA 4X |    |  |    |   |    |                   |


CONTROL BUILDING REMOTE TOLL PLAZA EQUIPMENT LAYOUT  
NOT TO SCALE


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTE TO DESIGNER

IF DISTANCE BETWEEN MAIN AND REMOTE PLAZA ANTENNAS IS LESS THAN 500 FT., PROVIDE CONDUIT AND SYNC CABLE TO CONNECT ANTENNA READERS IN THE MAIN AND REMOTE CONTROL BUILDINGS.





EQUIPMENT LEGEND

| ITEM | DESCRIPTION  |
|------|--|
| ③    | LIGHTING CONTRACTOR 120V, 30A, 1 PHASE, 4-POLE IN A NEMA 1 ENCLOSURE WITH A THREE POSITION SELECTOR SWITCH HAND-OFF-AUTO MOUNTED ON THE COVER. TRANSFORMER DRY TYPE, 2KVA, 120V PRIMARY, 480V SECONDARY, 1-PHASE, 3-WIRE ROADWAY LIGHTING. |
| ⑤    | VIDEO JB POWER #3  |
| ⑥    | BYPASS SWITCH  |
| ⑦    | UPS-2 PANEL.   |
| ⑧    | LIGHTNING ARRESTOR SYSTEM  |
| ⑭    | MAIN DISTRIBUTION PANEL (MDP-2), 208Y/120V, 3 PHASE, 4W 100 AMP, MAIN CIRCUIT BREAKER  |
| ②②   | UPS/LINE CONDITIONER. CONTRACTOR SHALL INSTALL THE 3KVA UPS ABOVE GROUND, ON A SHELVING SYSTEM AS DIRECTED BY THE ENGINEER   |
| ②⑥   | VIDEO JB POWER #4  |
| ③⑨   | ITS 2-1 PANEL  |

NOTES:


- CONTRACTOR SHALL ROUTE ALL CONDUIT AS REQUIRED TO ALL PANELS, EQUIPMENT AND CONTROL DEVICES.
- THE WALL ELEVATIONS FOR THE MAIN RAMP CONTROL BUILDING ARE SHOWN ON THIS DRAWING. THE WALL ELEVATIONS (NOT SHOWN) FOR THE REMOTE RAMP CONTROL BUILDING ARE SIMILAR.
- MINIMUM CLEARANCE BETWEEN CABINETS SHALL ALLOW THE DOORS TO OPEN 90 DEGREES MINIMUM.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



INTERIOR ELEVATIONS -  
REMOTE PLAZA



BUILDING MECHANICAL PLAN

- NOTES:
- 1. UNIT SHALL HAVE ARI CERTIFIED COILS, AIWCA RATED FANS, AND UL LISTED & LABELED ELECTRICAL COMPONENTS.
  - 2. PROVIDE HVAC UNITS WITH FACTORY SUPPLY AND RETURN GRILLES.
  - 3. HVAC PROVIDE LEAD/LAG THERMOSTAT CONTROLLER BARD MODEL #MC4001-AC WITH BASE ALARMS AND ETHERNET ACCESS.
  - 4. ALL MANUFACTURERS AND PART NUMBERS ARE FOR REFERENCE. THE CONTRACTOR SHALL PROVIDE CALCULATIONS FOR HVAC AND HEATING SYSTEM BASED ON BUILDING CONSTRUCTION AND INTERNAL BUILDING LOADS.

NOTE TO DESIGNER

THE ESTIMATED EQUIPMENT BUILDING LOADS FOR EQUIPMENT IS 19,000 BTU/HR. THE DESIGNER SHALL SIZE THE HVAC SYSTEMS ACCORDINGLY.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

| ELECTRICAL ROOM |          |          |          |                   |                     |             |              |               |              |                |                |                      |                            |              |                |                      |                           |                 |    |    |                            |         |
|-----------------|----------|----------|----------|-------------------|---------------------|-------------|--------------|---------------|--------------|----------------|----------------|----------------------|----------------------------|--------------|----------------|----------------------|---------------------------|-----------------|----|----|----------------------------|---------|
| MARK            | LOCATION | SERVES   | NOM. TON | TOTAL AIRFLOW CFM | OUTSIDE AIRFLOW CFM | ESP (IN WG) | REFRIG. TYPE | COOLING DATA  |              |                |                |                      |                            | HEATING DATA |                |                      |                           | ELECTRICAL DATA |    |    | MANUFACTURER/ MODEL NUMBER | REMARKS |
|                 |          |          |          |                   |                     |             |              | TOTAL CAP MBH | SENS CAP MBH | EAT (DEG F) DB | EAT (DEG F) WB | OUTDOOR TEMP (DEG F) | MIN. EER AT ARI CONDITIONS | CAP MBH      | EAT (DEG F) DB | OUTDOOR TEMP (DEG F) | SUPPLEMENTAL HEATING (KW) | VOLTS           | PH | HZ |                            |         |
| HVAC-01         | OUTSIDE  | BUILDING | 4        | 1500              | -                   | 0.15        | R454B A2L    | 45.5          | 34.0         | 75             | 62             | 90                   | 11                         | 17.1         | 70             | 0                    | 5                         | 208/240         | 1  | 60 | BARD W5SAF0A05ZPXXXJ       |         |
| HVAC-02         | OUTSIDE  | BUILDING | 4        | 1500              | -                   | 0.15        | R454B A2L    | 45.5          | 34.0         | 75             | 62             | 90                   | 11                         | 17.1         | 70             | 0                    | 5                         | 208/240         | 1  | 60 | BARD W5SAF0A05ZPXXXJ       |         |

ABBREVIATION LEGEND


CFM - CUBIC FEET PER MINUTE



MECHANICAL PLAN - REMOTE PLAZA

NOTES:

1. SEE CABLE/CONDUIT SCHEDULES SHEET FOR CABLE TAGS.
2. RECEPTACLE AND LIGHTING CONDUIT SHALL BE ¾" WITH 2-1/C #12 AND 1/C #12 GRD, UNLESS OTHERWISE NOTED.
3. FOR PANEL SCHEDULES, SEE PANELBOARD SCHEDULES SHEET.
4. PROVIDE CONNECTION TO RECEPTACLES FOR THE EQUIPMENT RACKS AS SPECIFIED. THE PLUG STRIP SHALL BE MOUNTED TO THE SIDE OF THE CABINET AS DIRECTED BY THE ENGINEER.
5. FOR LIGHTING FIXTURE SCHEDULE, ELECTRICAL SYMBOLS, LEGEND, AND ABBREVIATIONS, SEE LEGEND SHEET.
6. LIGHTING AND RECEPTACLES SHALL BE FED FROM PANEL MDP-2.
7. CONNECT EMERGENCY BATTERY PACK AHEAD OF LIGHT CIRCUIT.
8. COMMUNICATION AND EQUIPMENT RACKS SHALL BE APPROVED BY THE ENGINEER. A SAMPLE IS SHOWN BELOW.  
SAMPLE:  
I-PASS READER  
LANE CONTROL  
ITS FIBER  
LOCAL AND BACKBONE FIBER
9. CONTRACTOR SHALL COORDINATE FINAL RACK LAYOUT WITH THE ENGINEER AND THE ILLINOIS TOLLWAY.
10. NETWORK SWITCHES PROCURED BY OTHERS.




REMOTE TOLL PLAZA - BUILDING LIGHTING  
AND RECEPTACLE PLAN  
NOT TO SCALE

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

LEGEND:


- ① FIBER-OPTIC CORNING RACK INTERCONNECT CENTER CCH-04U (4 RU)
- ② FIBER-OPTIC CORNING RACK INTERCONNECT CENTER CCH-04U (4 RU)
- ③ FUTURE NETWORK SWITCHES - (1 RU) NOTE 10
- ④ FUTURE NETWORK SWITCHES - (1 RU) NOTE 10
- ⑤ COMMSCOPE MODULAR PATCH PANEL - (2 RU)



COMMUNICATIONS AND EQUIPMENT RACK ELEVATION  
NOT TO SCALE



CONTROL BUILDING LIGHTING  
AND RECEPTACLE PLAN -  
REMOTE PLAZA




**BUILDING ELECTRICAL GROUNDING LAYOUT**  
NOT TO SCALE


MONOTUBE (TYP)

**NOTES:**


1. SEE CABLE/CONDUIT SCHEDULE FOR CABLE TAGS.
2. SEE CONTROL BUILDING EQUIPMENT LAYOUT SHEET FOR MORE DETAIL.
3. DETAIL SHOWS INSTALLATION IN UNPAVED AREA. WHEN INSTALLING IN A PAVED AREA, INCORPORATE GROUND WELL IN THE POUR.
4. GROUND WELLS ARE REQUIRED AT EVERY GROUND ROD.
5. NOT USED
6. PROVIDE 1" PVC CONDUIT FOR GROUND CABLES UNDER BUILDING (TYP.).
7. ALL COPPER GROUND BARS SHALL BE OF HARD DRAWN, COMMERCIALY PURE, ELECTROLYTIC COPPER, FOR USE AS AN ELECTRICAL CONDUCTOR AND SHALL COMPLY WITH ASTM SPEC. B-187 OF LATEST DATE.
8. BOLTS, NUTS, & WASHERS USED FOR CONNECTION TO GROUND BUSBARS SHALL BE SOLID COPPER.
9. WELD PER MANUFACTURER SPECIFICATION (ERICO PRODUCTS OR BURNDY CORP.).
10. THE COPPER GROUND BUSBAR SHALL BE MOUNTED TO THE CABLE TRAY ABOVE EQUIPMENT RACKS.
11. PROVIDE A #2 AWG GROUND CABLE FROM THE FRAME OF EACH EQUIPMENT RACK TO THE GROUND BUS AS SHOWN. THE CABLE SHALL BE BOLTED TO THE RACK USING A SEAMLESS HEAVY DUTY COMPRESSION TERMINAL.
12. A FOUR INCH GAP SHALL BE PROVIDED BETWEEN THE ENDS OF THE TWO CONDUCTORS THAT MAKE UP THE INTERNAL PERIMETER GROUND BUS CONDUCTOR.
13. ALL EQUIPMENT LOCATED INSIDE THE BUILDING SHALL BE BONDED TO THE MAIN GROUND BUS OR THE INTERNAL PERIMETER GROUND CONDUCTOR WITH A #2 AWG GROUND CABLE. ALL CONNECTIONS MUST BE EXOTHERMICALLY WELDED.
14. THE INTERNAL PERIMETER GROUND BUS CONDUCTOR MUST BE INSTALLED HORIZONTALLY ALONG THE WALL APPROXIMATELY 7'-6" ABOVE FINISHED FLOOR. THE CONDUCTOR SHALL BE SUPPORTED 2 INCHES FROM THE WALL SURFACE ON INSULATED STANDOFFS. THE STANDOFFS SHALL BE INSTALLED AT INTERVALS AS NECESSARY TO KEEP THE CONDUCTOR SECURELY IN PLACE WITHOUT NOTICEABLE SAGS AND BENDS.
15. THE GROUND BUSBARS MUST BE MOUNTED APPROXIMATELY 7'-6" ABOVE FINISHED FLOOR AND MOUNTED TO WALL USING A MOUNTING BRACKET WITH INSULATOR.




**GROUND WELL PLAN DETAIL**  
NOT TO SCALE (NOTE 3)



**GROUND WELL ELEVATION DETAIL**  
NOT TO SCALE (NOTE 3)



**MASTER GROUND BUSBAR  
SUPPORT SPACING DETAIL**  
NOT TO SCALE



**MASTER GROUND BUSBAR  
CONNECTION DETAIL**  
NOT TO SCALE









**NOTE TO DESIGNER**  
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



**CONTROL BUILDING  
GROUNDING DETAILS -  
REMOTE PLAZA**

| PANELBOARD               |  |            |              |      |                      |             |         |  |  | MDP-2    |             | MAINS        |      |      |         |                               |       |  |  |  |  | 100A. MCB |  |
|--------------------------|--|------------|--------------|------|----------------------|-------------|---------|--|--|----------|-------------|--------------|------|------|---------|-------------------------------|-------|--|--|--|--|-----------|--|
| VOLTAGE                  |  |            |              |      |                      |             |         |  |  | 120/208V |             | BUS RATING   |      |      |         |                               |       |  |  |  |  | 100A.     |  |
| PHASE/WIRE               |  |            |              |      |                      |             |         |  |  | 3/4      |             | MOUNTING     |      |      |         |                               |       |  |  |  |  | SURFACE   |  |
| DESCRIPTION              |  | CKT NO.    | LOAD (WATTS) |      |                      | AMPS/ POLES | CKT BKR |  |  |          | AMPS/ POLES | LOAD (WATTS) |      |      | CKT NO. | DESCRIPTION                   |       |  |  |  |  |           |  |
|                          |  |            | A            | B    | C                    |             |         |  |  |          |             | A            | B    | C    |         |                               |       |  |  |  |  |           |  |
| SPARE                    |  | 1          | --           |      |                      | 20/1        |         |  |  |          | 20/1        | -            |      |      | 2       | SPARE                         |       |  |  |  |  |           |  |
| SPARE                    |  | 3          |              | -    |                      | 20/1        |         |  |  |          | 20/1        |              | 200  |      | 4       | LIGHTING CONTRACTOR (CONTROL) |       |  |  |  |  |           |  |
| SPARE                    |  | 5          |              |      | --                   | 20/1        |         |  |  |          | 30/3        |              |      | 2000 | 6       | HVAC UNITS                    |       |  |  |  |  |           |  |
| EMERGENCY LIGHT          |  | 7          | 100          |      |                      | 20/1        |         |  |  |          |             | 2000         |      |      | 8       |                               |       |  |  |  |  |           |  |
| INTERIOR LIGHTS          |  | 9          |              | 200  |                      | 20/1        |         |  |  |          |             |              | 2000 |      | 10      |                               |       |  |  |  |  |           |  |
| EXTERIOR BUILDING LIGHTS |  | 11         |              |      | 240                  | 20/1        |         |  |  |          | 30/1        |              |      | --   | 12      | SPARE                         |       |  |  |  |  |           |  |
| VES WASH SYSTEM (LOC 2)  |  | 13         | 2500         |      |                      | 30/1        |         |  |  |          | 30/2        | 2500         |      |      | 14      | UPS-2 (5 KVA)                 |       |  |  |  |  |           |  |
| SPARE                    |  | 15         |              | -    |                      | 20/1        |         |  |  |          |             |              | 2500 |      | 16      |                               |       |  |  |  |  |           |  |
| SPARE                    |  | 17         |              |      | --                   | 20/1        |         |  |  |          | 20/1        |              |      | -    | 18      | SPARE                         |       |  |  |  |  |           |  |
| EXTERIOR RECEPTACLE      |  | 19         | 200          |      |                      | 20/1        |         |  |  |          | 20/1        | 400          |      |      | 20      | INTERIOR RECEPTACLES          |       |  |  |  |  |           |  |
| EXTERIOR RECEPTACLE      |  | 21         |              | 200  |                      | 20/1        |         |  |  |          | 20/1        |              | 400  |      | 22      | INTERIOR RECEPTACLES          |       |  |  |  |  |           |  |
| SPARE                    |  | 23         |              |      | -                    | 20/1        |         |  |  |          | 30/2        |              |      | -    | 24      | UPS-2 (TOLLING)               |       |  |  |  |  |           |  |
| SPARE                    |  | 25         |              |      |                      | 30/2        |         |  |  |          |             | -            |      |      | 26      |                               |       |  |  |  |  |           |  |
| SPARE                    |  | 27         |              |      |                      |             | 20/1    |  |  |          |             | 20/1         |      | -    |         | 28                            | SPARE |  |  |  |  |           |  |
| SPARE                    |  | 29         |              |      | --                   | 30/1        |         |  |  |          | 30/2        |              |      |      | 30      | SPARE                         |       |  |  |  |  |           |  |
| SPARE                    |  | 31         | -            |      |                      | 20/1        |         |  |  |          |             |              |      |      | 32      |                               |       |  |  |  |  |           |  |
| ROADWAY LTG TRANSFORMER  |  | 33         |              | 960  |                      | 20/2        |         |  |  |          | 20/1        |              | -    |      | 34      | SPARE                         |       |  |  |  |  |           |  |
| ROADWAY LTG TRANSFORMER  |  | 35         |              |      | 960                  |             |         |  |  |          | 40/1        |              |      |      | 36      | SPARE                         |       |  |  |  |  |           |  |
| "A"                      |  | 5300       |              |      | SUBTOTAL "A" = 11450 |             |         |  |  |          | 6150        |              |      |      |         |                               | "A"   |  |  |  |  |           |  |
| "B"                      |  |            | 3860         |      | SUBTOTAL "B" - 11960 |             |         |  |  |          |             | 8100         |      |      |         |                               | "B"   |  |  |  |  |           |  |
| "C"                      |  |            |              | 3700 | SUBTOTAL "C" = 7470  |             |         |  |  |          |             |              | 3770 |      |         |                               | "C"   |  |  |  |  |           |  |
| TOTAL WATTS "A,B,C"      |  | = 28.38 KW |              |      |                      |             |         |  |  |          |             |              |      |      |         |                               |       |  |  |  |  |           |  |

| PANELBOARD <u>UPS-2</u>    |  |         |              |             |         |  |         |             |              | MAINS <u>30A. 2P. MCB</u> |                                  |  |  |  |  |  |  |  |  |
|----------------------------|--|---------|--------------|-------------|---------|--|---------|-------------|--------------|---------------------------|----------------------------------|--|--|--|--|--|--|--|--|
| VOLTAGE <u>120V./208V.</u> |  |         |              |             |         |  |         |             |              | BUS RATING <u>60A.</u>    |                                  |  |  |  |  |  |  |  |  |
| PHASE/WIRE <u>1/3</u>      |  |         |              |             |         |  |         |             |              | MOUNTING <u>SURFACE</u>   |                                  |  |  |  |  |  |  |  |  |
| DESCRIPTION                |  | CKT NO. | LOAD (WATTS) | AMPS/ POLES | CKT BKR |  | CKT BKR | AMPS/ POLES | LOAD (WATTS) | CKT NO.                   | DESCRIPTION                      |  |  |  |  |  |  |  |  |
| SPARE                      |  | 1       | —            | 20/1        |         |  |         | 20/1        | 300          | 2                         | RACK RECEPTACLE (LCC) RAMP L1    |  |  |  |  |  |  |  |  |
| SPARE                      |  | 3       | —            | 20/1        |         |  |         | 20/1        | 300          | 4                         | RACK RECEPTACLE (I-PASS) RAMP L1 |  |  |  |  |  |  |  |  |
| VIDEO POWER JUNCTION BOX 3 |  | 5       | 400          | 20/1        |         |  |         | 20/1        | 400          | 6                         | RACK RECEPTACLE (FIBER)          |  |  |  |  |  |  |  |  |
| VIDEO POWER JUNCTION BOX 4 |  | 7       | 400          | 20/1        |         |  |         | 20/1        | 200          | 8                         | CARD READER PANEL                |  |  |  |  |  |  |  |  |
| SPARE                      |  | 9       | —            | 20/1        |         |  |         | 20/1        | —            | 10                        | SPARE                            |  |  |  |  |  |  |  |  |
| SPARE                      |  | 11      | —            | 20/1        |         |  |         | 20/1        | —            | 12                        | SPARE                            |  |  |  |  |  |  |  |  |
| SUBTOTAL "A"               |  |         | 800          |             |         |  |         |             | 1200         |                           |                                  |  |  |  |  |  |  |  |  |
| TOTAL WATTS "A,B,C"        |  |         | = 2.0 KW     |             |         |  |         |             |              |                           |                                  |  |  |  |  |  |  |  |  |

|                   |  |          |              |             |   |  |   |             |              |         |                      |              |  |
|-------------------|--|----------|--------------|-------------|---|--|---|-------------|--------------|---------|----------------------|--------------|--|
| PANELBOARD        |  |          |              |             | ITS 2   |  | MAINS   |             |              |         |                      | 30A. 2P. MCB |  |
| VOLTAGE           |  |          |              |             | 120V / 208V   |  | BUS RATING  |             |              |         |                      | 60A.         |  |
| PHASE/WIRE        |  |          |              |             | 1/3   |  | MOUNTING  |             |              |         |                      | SURFACE      |  |
| DESCRIPTION       |  | CKT NO.  | LOAD (WATTS) | AMPS/ POLES | CKT BKR   |  | CKT BKR   | AMPS/ POLES | LOAD (WATTS) | CKT NO. | DESCRIPTION          |              |  |
| SPARE             |  | 1        | --           | 30/2P       |  |  |  | 10/1P       | 200          | 2       | ITS RACK RECEPTACLES |              |  |
|                   |  | 3        |              |             |  |  |  | 10/1P       | --           | 4       | SPARE                |              |  |
| SPARE             |  | 5        | --           | 10/1P       |  |  |  | 10/1P       | --           | 6       | SPARE                |              |  |
| SPARE             |  | 7        | --           | 10/1P       |  |  |  | 10/1P       | --           | 8       | SPARE                |              |  |
|                   |  |          |              |             |   |  |   |             |              |         |                      |              |  |
|                   |  |          |              |             |   |  |   |             |              |         |                      |              |  |
| SUBTOTAL = --     |  |          | --           |             |   |  |   |             | 200          |         |                      |              |  |
| TOTAL WATTS "A,B" |  | = 0.2 KW |              |             |   |  |   |             |              |         |                      |              |  |

|||||


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

|||||




PANELBOARD SCHEDULES - REMOTE PLAZA AET LANES



FRONT & REAR VES CAMERA  
VIDEO POWER JUNCTION BOX - REMOTE PLAZA  
ALTERNATIVE LAYOUT  
NOT TO SCALE

NOTES TO DESIGNER

- THIS BASE SHEET SHOWS TYPICAL NEW CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.
- THE DESIGNER SHALL ADJUST DETAIL AND QUANTITIES AS REQUIRED FOR NUMBER OF VES CAMERAS.
- THE DESIGNER SHALL INCLUDE VIDEO POWER JUCTION BOX DETAILS (M-ITS-2100 SERIES BASE SHEETS) FOR SECURITY CAMERAS AND DATA LOGGER CAMERA.




EQUIPMENT LEGEND -  
VIDEO POWER JUNCTION BOX  
(ALTERNATIVE LAYOUT)

| ITEM | QUANTITY<br>(SAMPLE) | DESCRIPTION   |
|------|----------------------|---|
| ①    | 1                    | 48"H X 24"W X 8"D NEMA 1 ENCLOSURE WITH 44"H X 22 1/2"W BACK PANEL, HOFFMAN CATALOG NO. A-48N24BLP, WITH A-48N24MP PANEL.   |
| ②    | 2                    | POWER SUPPLY 24VDC, TDK-LAMBDA NO. QM7FSDL 24/24DMS 24/24DMS 24/24DMS 24/24DMS.   |
| ③    | 12                   | TERMINAL BLOCKS, FUSE SWITCH TYPE WITH BLOWN FUSE INDICATOR COMPLETE WITH 5 AMP FUSE, MOUNTING RAIL, ANCHORS, BARRIERS, MARKING STRIPS AND JUMPERS, ALLEN BRADLEY CATALOG NO. 1492-FB1M30-D1. |
| ④    | 21                   | TERMINAL BLOCKS, ON POLE PANEL MOUNT BLOCK SCREW TERMINAL WITH WIRE CLAMP, ALLEN BRADLEY CATALOG NO. 1492-CD6.  |
| ⑤    | 1                    | GROUND BAR SYSTEM WITH INSULATED MOUNTING BRACKET, HOFFMAN CATALOG NO. PGS2K.   |
| ⑥    | LOT                  | PANDUIT PLASTIC WIRING DUCT SNAP-IN SLOT DESIGN AND NON-SLIP COVER, 1"W X 1"H, CATALOG NO. F1X1LG6 WITH COVER C1LG6.  |
| ⑦    | 1                    | POWER DISTRIBUTION BLOCK MARATHON NO. 1322580.  |
| ⑧    | 4                    | SQUARE D, QOU 115 1P/15A BREAKER.   |
| ⑨    | 10                   | SURGE SUPPRESSOR MTL MODEL ZB24580.   |
| ⑩    | 1                    | SQUARE AXIAL FAN 4 1/16" x 4 1/16", 1 1/2" IN DEPTH, 115 CFM, IP20, CAST ALUMINUM FRAME, 115V AC, AND COMPACT AXIAL FAN GUARD 4 1/16" x 4 1/16".  |

EQUIPMENT LEGEND -  
VIDEO POWER JUNCTION BOX

| ITEM | QUANTITY | DESCRIPTION   |
|------|----------|---|
| ①    | 1        | 48"H X 24"W X 8"D NEMA 1 ENCLOSURE WITH 44"H X 22 1#2"W BACK PANEL, HOFFMAN CATALOG NO. A-48N24BLP, WITH A-48N24MP PANEL.   |
| ②    | 4        | POWER SUPPLY 24VDC, MEANWELL MODEL NO. SDR-240-24   |
| ③    | 24       | TERMINAL BLOCKS, FUSE SWITCH TYPE WITH BLOWN FUSE INDICATOR COMPLETE WITH 5 AMP FUSE, MOUNTING RAIL, ANCHORS, BARRIERS, MARKING STRIPS AND JUMPERS, ALLEN BRADLEY CATALOG NO. 1492-FB1M30-D1. |
| ④    | 42       | TERMINAL BLOCKS, ON POLE PANEL MOUNT BLOCK SCREW TERMINAL WITH WIRE CLAMP, ALLEN BRADLEY CATALOG NO. 1492-CD6.  |
| ⑤    | 1        | GROUND BAR SYSTEM WITH INSULATED MOUNTING BRACKET, HOFFMAN CATALOG NO. PGS2K.   |
| ⑥    | LOT      | PANDUIT PLASTIC WIRING DUCT SNAP-IN SLOT DESIGN AND NON-SLIP COVER, 1"W X 1"H, CATALOG NO. F1X1LG6 WITH COVER C1LG6.  |
| ⑦    | 1        | POWER DISTRIBUTION BLOCK MARATHON NO. 1322580.  |
| ⑧    | 4        | SQUARE D, QOU 115 1P/15A BREAKER.   |
| ⑨    | 20       | SURGE SUPPRESSOR MTL MODEL ZB24580.   |
| ⑩    | 1        | SQUARE AXIAL FAN 4 1/16" x 4 1/16", 1 1/2" IN DEPTH, 115 CFM, IP20, CAST ALUMINUM FRAME, 115V AC, AND COMPACT AXIAL FAN GUARD 4 1/16" x 4 1/16".  |




FRONT & REAR VES CAMERA  
VIDEO POWER JUNCTION BOX  
N.T.S.  
VIDEO POWER JUNCTION BOX REMOTE PLAZA

NOTES:


- LABEL JUNCTION BOX, TERMINAL STRIPS, AND ALL WIRE AND CABLES.
- ROUTE 1-2/C #12 POWER CABLE TO EACH CAMERA.
- ALL ELECTRICAL CABLES TO CAMERA SHALL HAVE SURGE PROTECTION.
- CAT6 CABLE SHALL BE SURGE PROTECTED ON THE TSIC.




VIDEO POWER JUNCTION BOX  
DETAIL - REMOTE PLAZA




SECTION A-A  
(LANE LOOP LAYOUT)  
NOT TO SCALE




ELEVATION B-B  
EMBEDDED JUNCTION BOX IN  
BARRIER WALL ELEVATION  
NOT TO SCALE




SECTION C-C  
LOOP INSTALLATION DETAILS  
NOT TO SCALE



DETAIL OF  
DETECTOR LOOP SLOT  
NOT TO SCALE



SECTION C-C  
PRIOR TO ROAD OR  
ISLAND CONSTRUCTION  
NOT TO SCALE



SECTION C-C  
EQUIPMENT ENDS AFTER  
CABLE INSTALLATION  
NOT TO SCALE

#### NOTES:


1. SEE LOOP LAYOUT SHEETS FOR MORE DETAILS.
2. THE REINFORCEMENT IS NOT SHOWN FOR CLARITY.
3. CONDUITS THAT STUB UP IN THE PAVEMENT ARE 1 1/2" FOR QUANTUM AND PIEZO STRIPS, 1 1/2" FOR ALL OTHERS UNLESS NOTED OTHERWISE. SEE LOOP LAYOUT DETAIL. CONDUIT BETWEEN JUNCTION BOXES SHALL BE 4" DIA.
4. ELECTRICAL CONTRACTOR MUST COORDINATE WITH ILLINOIS TOLLWAY AND PAVEMENT CONTRACTOR. NO CONCRETE POUR SHALL BE DONE BEFORE CONDUIT IS LAID OUT AND APPROVED BY THE ENGINEER.
5. JUNCTION BOXES MUST BE INSTALLED A MINIMUM OF 12" APART.

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



#### LOOP JUNCTION BOX DETAIL



The diagram illustrates the wiring for a 3000VA/2400W UPS unit. It shows the following components and connections:


- TO UPS PANELBOARD:** Provides input power to the UPS unit.
- TO 3000VA/2400W UPS UNIT:** The main power input to the UPS.
- 30A PLUG:** A 30-ampere plug connected to the UPS unit.
- 30A RECEPT.** A 30-ampere receptacle connected to the UPS unit.
- FROM TP PANELBOARD:** A transfer panelboard connected to the UPS unit.
- FROM L/C 30A PLUG:** A load center 30-ampere plug connected to the UPS unit.
- BYPASS SWITCH:** A switch used to bypass the UPS unit for maintenance or testing.
- AC LINE SWITCH:** A switch used to control the AC power supply.
- TERMINAL STRIP:** A strip of terminals used for connecting the various components.
- NOTES 1, 2, 3, & 7:** Reference to specific notes in the accompanying document.

The diagram shows the following wiring connections:

- The **TO UPS PANELBOARD** and **TO 3000VA/2400W UPS UNIT** lines are connected to the **TERMINAL STRIP**.
- The **30A PLUG** and **30A RECEPT.** are connected to the **TERMINAL STRIP**.
- The **FROM TP PANELBOARD** and **FROM L/C 30A PLUG** lines are connected to the **TERMINAL STRIP**.
- The **BYPASS SWITCH** is connected to the **TERMINAL STRIP**.
- The **AC LINE SWITCH** is connected to the **TERMINAL STRIP**.



|                     |                           |                  |
|---------------------|---------------------------|------------------|
| VERSION:<br>2021-03 | BASE SHEET:<br>M-BUS-2529 | SHEET:<br>1 OF 1 |
|---------------------|---------------------------|------------------|



DOOR ALARM JUNCTION BOX DETAIL- SINGLE DOOR  
NOT TO SCALE

EQUIPMENT LEGEND - DOOR ALARM

| ITEM | DESCRIPTION  |
|------|--|
| ①    | NORMALLY CLOSED (N.C. WHEN THE DOOR IS CLOSED) MAG REED CONTACT BUILT INTO DOOR FRAME. SENTROL 1078C OR 1078 SERIES. COIL CONTACT LEADS AND COMMUNICATION CABLE IN JUNCTION BOX. |
| ②    | JUNCTION BOX, 4" X 4" WITH BLANK COVER PLATE, AND ¾" CONDUIT TO CABLE TRAY.  |
| ③    | MOTION DETECTOR  |
| ④    | MAGNETIC DOOR LOCK   |
| ⑤    | DOOR RELEASE BUTTON  |
| ⑥    | CARD READER (EXTERIOR)   |

NOTES:


- COIL 2 FEET CABLE IN BOX FOR TERMINATION BY THE ILLINOIS TOLLWAY UNLESS OTHERWISE NOTED.
- ROUTE TO CARD READER PANEL, TERMINATION BY THE ILLINOIS TOLLWAY. 4-1PR #22 SHLD. CABLE IN ¾" CONDUIT.
- MECHANICAL LOCKS SHALL BE SCHLAGE BRAND (OR APPROVED EQUAL) AND SECURED WITH A CONSTRUCTION KEY WITH THREE COPIES PROVIDED TO ILLINOIS TOLLWAY BUSINESS SYSTEMS.

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



DOOR ALARMS DETAIL



**SCHEMATIC WIRING DIAGRAM  
EMERGENCY ROADWAY PLAZA LIGHTING**



**LIGHTING CONTRACTOR WIRING DIAGRAM**

**NOTES:**

1. SEE SYMBOLS AND ABBREVIATIONS SHEET FOR LEGEND.
2. SEE PLANS FOR CABLE AND CONDUIT ROUTING.


|||||  
NOTE TO DESIGNER  
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




**MISCELLANEOUS SCHEMATIC  
DIAGRAMS**

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



BUILDING ALARMS TERMINAL STRIP  
NOT TO SCALE



TERMINAL STRIP INTERCONNECT CENTER (TSIC)  
NOT TO SCALE (SEE NOTE 1)

NOTES:

1. TERMINAL STRIP INTERCONNECT CENTER (TSIC) IS LOCATED IN THE CONTROL BUILDING. SEE BUILDING EQUIPMENT LAYOUT DRAWINGS, FOR LOCATION.
2. ROUTE #6 COPPER GROUND CABLE FROM GROUND BUSBAR TO INTERNAL PERIMETER GROUND BUS CONDUCTOR.
3. ALL EQUIPMENT SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR UNLESS OTHERWISE NOTED.
4. PROVIDE WIRE DUCT AS SHOWN ON THE DRAWING. WIRE DUCT SHALL BE PANDUIT PART NUMBER E2X3LG6 WITH COVER PART NUMBER C2LG6 AND CORNER STRIP PART NUMBER CSP3LG-Q.


| 3 PAIR DATA/COMMUNICATIONS<br>CABLE COLOR CODE CHART  |  |
|---|--|
| PAIR NO.  | MFGR'S COLOR CODE CHART<br>COLOR COMBINATION |
| CABLE-1   |  |
| 1   | BLACK PAIRED WITH RED                        |
| 2   | BLACK PAIRED WITH WHITE                      |
| 3   | BLACK PAIRED WITH GREEN                      |
| 3 PR. #22 CABLE WITH INDIVIDUALLY SHIELDED<br>PAIRS SHALL BE BELDEN #88777 OR<br>MANHATTAN #M43103. |  |

| 6 PAIR DATA/COMMUNICATIONS<br>CABLE COLOR CODE CHART   |  |
|--|--|
| PAIR NO.   | MFGR'S COLOR CODE CHART<br>COLOR COMBINATION |
| CABLE-2  |  |
| 1  | BLACK PAIRED WITH RED                        |
| 2  | BLACK PAIRED WITH WHITE                      |
| 3  | BLACK PAIRED WITH GREEN                      |
| 4  | BLACK PAIRED WITH BLUE                       |
| 5  | BLACK PAIRED WITH YELLOW                     |
| 6  | BLACK PAIRED WITH BROWN                      |
| 6 PR. #22 CABLE WITH INDIVIDUALLY SHIELDED<br>PAIRS SHALL BE BELDEN #88778 OR<br>MANHATTAN #M43106 |  |


| 9 CONDUCTOR ALARM CABLE<br>COLOR CODE CHART               |  |
|---|--|
| CONDUCTOR<br>NO.  | MFGR'S COLOR CODE CHART<br>COLOR COMBINATION |
| CABLE-3   |  |
| 1   | BLACK  |
| 2   | WHITE  |
| 3   | RED  |
| 4   | GREEN  |
| 5   | ORANGE                                       |
| 6   | BLUE   |
| 7   | WHITE/BLACK                                  |
| 8   | RED/BLACK                                    |
| 9   | GREEN/BLACK                                  |
| 9 CONDUCTOR #22 SHIELDED CABLE SHALL BE<br>BELDEN #83559. |  |



TSIC TERMINAL BLOCK  
LAYOUT MAIN AND REMOTE  
PLAZAS - AET LANES



DATA CAMERA LAYOUT  
NOT TO SCALE



DATA LOGGER INSTALLATION


NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.


- NOTES:
- SEE CABLE/CONDUIT SCHEDULES SHEET FOR CABLE TAGS.
  - INSTALL CABLES BETWEEN THE PLAZA AND CAMERA PER MANUFACTURER'S RECOMMENDATIONS.
  - THE CAMERA'S FINAL MOUNTING LOCATION SHALL BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
  - THE COST FOR THE WORK TO FURNISH AND INSTALL THE CAMERA, CABLES, CONDUIT, AND ASSOCIATED MOUNTING HARDWARE ON THE POLE SHALL BE INCLUDED IN THE LUMP SUM PAY ITEM FOR ELECTRICAL WORK FOR THE PLAZA.
  - LOOP 3' OF CABLE FOR CAMERA IN POLE TO FACILITATE CAMERA MAINTENANCE.




DATA LOGGER CAMERA



DETAIL FOR FIBER STUB UP




DETAIL FOR COMED LINE STUB UP




DETAIL FOR GAS LINE STUB UP

NOTES:


1. DETAILS ARE ONLY SCHEMATICS FOR GUIDANCE, AND CONTRACTOR MUST COORDINATE WITH COMED AND NICOR GAS SERVICE LINES.
2. CONTRACTOR SHALL COORDINATE WITH STRUCTURAL FOR LOCATION OF OPENINGS THROUGH RETAINING WALL. THE HOLE DIA./SLOT SHALL BE LARGE ENOUGH SO THAT IT DOES NOT CAUSE ANY STRAIN ON UTILITY DUE TO SETTLEMENT OF THE WALL.
3. SUPPORTS ARE REQUIRED TO HOLD THE SLEEVES VERTICALLY BEFORE FILL UP ONLY. THIS HAS TO BE COORDINATED WITH COMED AND NICOR UTILITIES. PROVIDE CONDUIT CLAMP/ANCHOR BOLT OF POWER STRUT, B-LINE OR UNISTRUT AND MOUNTING HARDWARE.
4. ALL DIMENSIONS AND REINFORCEMENT SHALL BE PER ILLINOIS TOLLWAY STANDARD DRAWING H8 FOR TYPE 1 CENTERED CAISSON, 42" BARRIER.



PLAN - DOUBLE FACE BARRIER



SECTION A-A



ELEVATION


CONDUIT DETAIL AT LIGHT POLE FOUNDATION  
INTEGRAL WITH BARRIER WALL  
(NOT TO SCALE)

NOTE TO DESIGNER  
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTE TO DESIGNER  
THIS BASE SHEET REFLECTS THE USE OF PERFORMANCE BASED RETAINING WALL. THE DESIGNER SHALL MODIFY THE BASE SHEETS ACCORDINGLY FOR DESIGNED RETAINING WALLS.



MISCELLANEOUS CROSS SECTION DETAILS




© Notice: The information contained on this page is the sole property of EXELON and is to be used only in conjunction with electric service provided by EXELON.

**Exelon**  
Energy Delivery  
**SYSTEM STANDARD**


NOTE:

CONCRETE PAD DETAIL FOR PROPOSED 480/240 V, SINGLE PHASE TRANSFORMER FOR ROADWAY LIGHTING CONTROLLER.



© Notice: The information contained on this page is the sole property of EXELON and is to be used only in conjunction with electric service provided by EXELON.

**Exelon**  
Energy Delivery  
**SYSTEM STANDARD**



© Notice: The information contained on this page is the sole property of EXELON and is to be used only in conjunction with electric service provided by EXELON.

**Exelon**  
Energy Delivery  
**SYSTEM STANDARD**


**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




**COMED TRANSFORMER PAD DETAIL**

VERSION: 2021-03  
BASE SHEET: M-BUS-2535  
SHEET: 1 OF 1




**NOTES:**



1. INSTALL CONDUIT TRAY PER MANUFACTURERS RECOMMENDATIONS.
2. SECURE CONDUIT TO CABLE TRAY.



**HSS COLUMN FOUNDATION**



**BASE PLATE LAYOUT**



**NOTE TO DESIGNER**

ALL VALUES DESIGNATED "X" ARE REQUIRED AND SHALL BE PROVIDED BY THE DESIGNER. HSS COLUMN SECTION, FOUNDATION SIZE, AND REINFORCEMENT TO BE DETERMINED AND SHOWN BY DESIGNER.

**NOTE TO DESIGNER**

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



**OVERHEAD CONDUIT TRAY**

GENERAL NOTES:

1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND ELEVATION ON THE PLANS PRIOR TO CONSTRUCTION.
2. ALL MANUFACTURED ITEMS SHALL BE INSTALLED AND USED IN ACCORDANCE WITH MANUFACTURER'S GUIDELINES.

DESIGN SPECIFICATIONS:

1. ILLINOIS TOLLWAY STRUCTURE DESIGN MANUAL, LATEST EDITION.
2. AASHTO LRFD SPECIFICATION FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS LUMINARIES AND TRAFFIC SIGNALS, LATEST EDITION WITH CURRENT INTERIMS.
3. AASHTO LFRD BRIDGE DESIGN SPECIFICATION, LATEST EDITION.
4. ILLINOIS DEPARTMENT OF TRANSPORTATION BRIDGE MANUAL, LATEST EDITION.
5. ILLINOIS TOLLWAY GEOTECHNICAL ENGINEER MANUAL, LATEST EDITION.

DESIGN LOADING:

WIND LOAD CRITERIA:


|  |            |
|--|------------|
| BASIC WIND SPEED:  | 120 M.P.H. |
| G:   | 1.14       |
| I <sub>F</sub> (FATIGUE IMPORTANCE FACTOR):                | 1.0        |
| KZ:  | 1.0        |
| WIND PRESSURE ON STRUCTURAL AND NON STRUCTURAL COMPONENTS: | 62 P.S.F.  |
| ICE LOAD (APPLIED WITH A FACTOR OF 1 FOR STRENGTH I ONLY): | 3.0 P.S.F. |

EQUIPMENT LOADS:

|                             |            |
|-----------------------------|------------|
| CONDUIT LOAD:               | XXX P.L.F. |
| MAXIMUM NUMBER OF CONDUITS: | X          |


DESIGN STRESSES FOR REINFORCED CONCRETE:

|   |              |
|---|--------------|
| f <sub>c</sub> (COMPRESSIVE STRENGTH OF CLASS DS CONCRETE):     | 4,000 P.S.I  |
| f <sub>y</sub> (YIELD STRENGTH OF GRADE 60 REINFORCEMENT BARS): | 60,000 P.S.I |



12" GRIP-SPAN ICE BRIDGE KITS  
WITH 2-LEVEL Z-BRACKET TRAPEZE  
BASE SHOE

| PARTS LIST |          |  |
|------------|----------|--|
| ITEM       | PART NO. | PART DESCRIPTION                             |
| 1          | X-SP126  | BASE SHOE PLATE PIPE COLUMN                  |
| 2          | GRS12    | 12" WIDE GRIP STRUT                          |
| 3          | HHD12    | 12" CANTILEVER WELDMENT                      |
| 4          | ZB12     | 1/2" MILL PLATE (F <sub>y</sub> =35 Ksi Min) |
| 5          | X-UB1358 | XX" x XX" x XX" x XX" U-BOLT (HDG.)          |
| 6          | SWA585   | XX" x XX" STAINLESS WEDGE ANCHOR             |
| 7          | PC312    | XX" FENCE POST CAP                           |
| 8          | SS38R-18 | XX" x XX" THREADED ROD (STAINLESS STEEL)     |
| 9          | SPLICE   | SPLICE FOR GRIP STRUT                        |
| 10         | SQW38    | XX" SQUARE WASHER (GALV.)                    |
| 11         | G3803    | XX" x 3" HDG HEX BOLT GR5                    |
| 12         | G12NUT   | XX" HDG HEAVY 2H HEX NUT                     |
| 13         | G38NUT   | XX" HDG HEAVY 2H HEX NUT                     |
| 14         | G12FW    | XX" HDG USS FLATWASHER                       |
| 15         | SS38NUT  | XX" SS HEX NUT                               |
| 16         | SS38LW   | XX" SS LOCKWASHER                            |
| 17         | SS38FW   | XX" STAINLESS FLATWASHER                     |
| 18         | G38LW    | XX" HDG LOCKWASHER                           |
| 19         | G38FW    | XX" HDG USS FLATWASHER                       |
| 20         | G12LW    | XX" HDG LOCKWASHER                           |




| PARTS LIST |          |                                     |
|------------|----------|-------------------------------------|
| ITEM       | PART NO. | PART DESCRIPTION                    |
| 1          | HHD12    | 12" CANTILEVER WELDMENT             |
| 2          | X-UB1358 | XX" x XX" x XX" x XX" U-BOLT (HDG.) |
| 3          | G12FW    | XX" HDG USS FLATWASHER              |
| 4          | G12LW    | XX" HDG LOCKWASHER                  |
| 5          | G12NUT   | XX" HDG HEAVY 2H HEX NUT            |
| 6          | SPLICE   | SPLICE FOR GRIP STRUT               |
| 7          | G38FW    | XX" HDG USS FLATWASHER              |
| 8          | G3803    | XX" x XX" HDG HEX BOLT GR5          |
| 9          | G38LW    | XX" HDG LOCKWASHER                  |
| 10         | G38NUT   | XX" HDG HEAVY 2H HEX NUT            |

12" COMPLETE  
CANTILEVER KIT

NOTE TO DESIGNER  
THICKNESS OF PLATE TO BE SPECIFIED BY DSE.



OVERHEAD CONDUIT TRAY




NOTES:

1. IDENTIFICATION SIGN MATERIAL SHALL MEET THE REQUIREMENTS OF ARTICLE 720.02 OF THE STANDARD SPECIFICATIONS.
2. IDENTIFICATION SIGNS SHALL BE MOUNTED ONTO THE BUILDING USING BOLTS AND WASHERS ACCORDING TO ARTICLE 720.04 OF THE STANDARD SPECIFICATIONS.



**TOLL PLAZA  
IDENTIFICATION SIGN**




LEFT SIDE VIEW

MAIN ENCLOSURE

SCALE: 1 1/2"=1'-0"

RIGHT SIDE VIEW



\*\*\*FOR COMPLETE ASSEMBLY USE ECD # NS-GEN-SY-Y-0300 (OR APPROVED EQUAL)\*\*\*

VES WASH SYSTEM SINGLE CABINET  
INSIDE DETAILS

NOT TO SCALE

| BILL OF MATERIALS COMPONENTS (OR APPROVED EQUAL) |      |       |   |
|--|------|-------|---|
| MARK NO.   | QTY. | SPARE | DESCRIPTION   |
| A  | 1    |       | NEMA 4 STAINLESS STEEL ENCLOSURE - 16"H X 16"W X 8"D (HOFFMAN)  |
| B  | 1    |       | SUBPANEL FOR ENCLOSURE (HOFFMAN CATALOG No. CP3024)   |
| D  | 1    |       | GROUNDING BAR (HOFFMAN CATALOG No. PGS2K) (NOT ILLUSTRATED ON DRAWING)  |
| E  | 1    |       | NEMA 1 ENCLOSURE - 60"H X 48"W X 19"D (HOFFMAN CATALOG No. HN4FM604818S16) WITH MOUNTING BRACKETS (HOFFMAN CAT. No. CMFKSS) FOR OUTDOOR CABINET INSTALLATION: USE NEMA 4X HOFFMAN CABINET OF SAME DIMENSION. THE MANUFACTURER OF THE VES WASH CABINET WILL KNOW WHICH HOFFMAN CABINET MODEL TO USE. |
| F  | 1    |       | SUBPANEL FOR NEMA 1 ENCLOSURE (HOFFMAN CATALOG No. A49P32N)   |
| G  | 1    |       | FLUORESCENT LIGHT FIXTURE FOR ENCLOSURE WITH 120VAC OUTLET (HOFFMAN CATALOG No. LF120V15) WITH DOOR SWITCH (HOFFMAN CATALOG No. ALFSWD)   |
| H  | 1    |       | SS VENT DRAIN HOFFMAN CATALOG No. AVDR4SS4  |

NOTES:


- EXACT OPERATING PRESSURE TO BE DETERMINED.
- FOR PRODUCT SUBSTITUTIONS SEE THE SPECIFICATIONS.
- ALL CONDUITS, FITTINGS AND ENTRY POINTS INTO EACH OF THE ENCLOSURES SHALL BE PROPERLY SEALED WITH DUCT SEAL TO PREVENT MOISTURE ENTRY.
- THIS DETAIL IS APPLICABLE TO VES WASH SYSTEM MAIN ENCLOSURE INSIDE THE BUILDINGS. FOR OUTSIDE INSTALLATION OF MAIN VES WASH SYSTEM ENCLOSURE, USE NEMA 4X ENCLOSURE - 60"H X 36"W X 16"D, NO. WS603616SS, & PAD LOCKING HANDLE KIT.

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



VES WASH SYSTEM SINGLE  
CABINET DETAIL



NOTES:

1. 20A ,115VAC SERVICE REQUIRED.
2. WILL REQUIRE: LOCATION, IP ADDRESS AND LANE CONFIGURATION.
3. PNEUMATIC FITTINGS TO BE BRASS IN CONSTRUCTION AND MEET SOCIETY OF AUTOMOTIVE ENGINEERS (SAE) SPECIFICATIONS.
4. THE 3/8" NYLON TUBING MAY HAVE TO BE LONGER THAN 100'. TUBING MUST RUN CONTINUOUS FROM THE MANIFOLD VALVES IN THE VES CABINET TO THE CAMERA NOZZLE, WITHOUT ANY INTERMEDIATE SPLICES. CONTRACTOR TO DETERMINE THE ACTUAL LENGTH OF THE TUBING REQUIRED FOR EACH OF THE VES CAMERAS AT THE SITE. THE NYLON TUBES ARE INSIDE OF RGS CONDUIT.
5. ALL CONDUIT FITTINGS AND ENTRY POINTS INTO THE ENCLOSURE SHALL BE PROPERLY SEALED WITH DUCT SEAL TO PREVENT MOISTURE ENTRY.
6. EXHAUST TO FREE AIR.
7. THE VES WASH SYSTEM WITH NITROGEN GENERATOR IS PRODUCED BY ECD COMPANY WITH THE MODEL NUMBER: NS-GEN-SY-Y-0300, AS ASSIGNED BY ECD (OR APPROVED EQUAL MODEL BY THE ILLINOIS TOLLWAY BUSINESS SYSTEMS). CONTRACTOR TO FABRICATE THE VES WASH SINGLE CABINET SYSTEM WITH NITROGEN GENERATOR IN COORDINATION WITH THE SYSTEM VENDOR, TO PROVIDE A COMPLETE FUNCTIONAL SYSTEM, AS SPECIFIED IN THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL VERIFY WITH THE VENDOR THAT ALL REQUIRED SYSTEM COMPONENTS FIT IN THE MAIN VES WASH CABINET AS SHOWN, IN COMPLIANCE WITH APPLICABLE CODES.
8. CONTRACTOR SHALL VERIFY THE NUMBER OF VES CAMERAS AT EACH INSTALLATION SITE, AS SHOWN ON THE PLANS, AND COORDINATE WITH THE SYSTEM VENDOR TO PROVISION THE VES WASH SYSTEM WITH THE REUIRED NUMBER OF NITROGEN AND FLUID VALVES AT EACH INSTALLATION SITE.
9. OUTDOOR INSTALLATION WILL REQUIRE OPTIONAL HEATER.

| MATERIALS LIST   |                                |        |          |
|------------------|--------------------------------|--------|----------|
| PART NO.         | DESCRIPTION                    | MANUAL | QUANTITY |
| NS-GEN-SY-Y-0300 | COMPLETE ASSEMBLY              | ECD    | 1        |
| NS-SUB-SY-L-0100 | NITROGEN GENERATOR             | ECD    | 1        |
| NG-ECD-00100     | REPLACEMENT PARTICULATE FILTER | ECD    | 1        |
| NG-ECD-00200     | NITROGEN VALVE SYSTEM          | ECD    | 1        |
| NG-ECD-00201     | LIQUID VALVE SYSTEM            | ECD    | 1        |
| NG-ECD-00300     | LIQUID PUMP                    | ECD    | 1        |
| NG-ECD-00314     | LIQUID TANK                    | ECD    | 1        |
| NG-ECD-01101     | SYSTEM CONTROL                 | ECD    | 1        |
| NG-ECD-00310     | PNEUMATIC PUMP                 | ECD    | 1        |
| NG-ECD-00311     | NITROGEN TANK                  | ECD    | 1        |

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



VES WASH SYSTEM PANEL  
DETAIL



| BILL OF MATERIAL COMPONENTS (OR APPROVED EQUAL) |                             |                            |  |
|---|-----------------------------|----------------------------|--|
| MARK NO.  | QTY.                        | SPARE                      | DESCRIPTION  |
| (A)   | AS REQUIRED<br>PER CONTRACT | 2 SPOOLS<br>OF 150<br>FEET | SILICONE HOSE SLEEVE CONTINUOUS TUBING FROM VES<br>WASH CABINET TO CAMERA, NO SPLICING ALLOWED.<br>McMASTER-CARR CATALOG No. 7453K49 |
| (B)   | AS REQUIRED<br>PER CONTRACT | 3                          | SPRAY NOZZLE<br>GRAINGER CATALOG No. 1MDH2   |
| (C)   | AS REQUIRED<br>PER CONTRACT | 3                          | MINIATURE CORROSION RESISTANT STRAIN RELIEF<br>HUBBELL CATALOG No. SHC1021CR   |
| (D)   | AS REQUIRED<br>PER CONTRACT | 3                          | ADJUSTABLE MOUNTING STRAP<br>McMASTER-CARR CATALOG No. 7572K12 (50 PER PACK)   |
| (E)   | AS REQUIRED<br>PER CONTRACT | 3                          | NOZZLE BULKHEAD FITTING (10 PACK)<br>SMC FITTING CATALOG No. KQ2E07-35   |



## NOTES


1. CAMERA NOZZLE BRACKET SHALL BE FABRICATED USING 12 GA. STAINLESS STEEL. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR APPROVAL.
2. CAMERA NOZZLE BRACKET SHALL BE ADJUSTABLE. STAINLESS STEEL NUT-BOLT COMBINATION SHALL BE USED FOR MOUNTING THE CAMERA NOZZLE BRACKET TO THE CAMERA LENS HOUSING. CONTRACTOR TO VERIFY THAT THE MOUNTING HARDWARE SECURELY HOLDS THE BRACKET BUT ALSO ALLOWS EASY ADJUSTMENT. CONTRACTOR SHALL SUBMIT INSTALLATION DRAWINGS CLEARLY IDENTIFYING PART NUMBERS USED FOR MOUNTING HARDWARE. INSTALLATION DRAWINGS SHALL ALSO INDICATE THE POSITION OF THE MOUNTING HARDWARE ON THE CAMERA NOZZLE BRACKET. THE INSTALLATION DRAWINGS SHALL BE APPROVED BY THE ILLINOIS TOLLWAY BEFORE INSTALLATION IN THE FIELD.

NOTE TO DESIGNER


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS **NOT** A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




## VES WASH SYSTEM FLOW DIAGRAM AND SYSTEM




**PARTIAL SECTION A-A**  
NOT TO SCALE




**COLLECTION STRUCTURE CONDUIT DETAIL**



**SECTION B-B**  
NOT TO SCALE




**TYPICAL PLAN VIEW**  
NOT TO SCALE



**MAIN ENCLOSURE MOUNTING DETAIL  
(OUTDOOR INSTALLATION ONLY)**  
NOT TO SCALE

2.5" DIA. PVC COATED RGS UNDERGROUND CONDUIT EXTEND (IF INSTALLED INSIDE) FROM BUILDING UP TO JUNCTION BOX OUTSIDE FOR VES WASH TUBING TO VES CAMERAS; (IF INSTALLED OUTSIDE) FROM CABINET TO JUNCTION BOX.



**OVERHEAD TOLL LAYOUT**

**NOTES:**


- ALL CONDUIT ROUTING AND EQUIPMENT PLACEMENT IS THE RESPONSIBILITY OF THE CONTRACTOR. THE ROUTING AND PLACEMENT DEPICTED IS SUGGESTED ONLY. ACTUAL ENCLOSURE LOCATION WILL VARY BASED ON SITE CONDITIONS. THE CONTRACTOR SHALL COORDINATE EQUIPMENT LOCATION AND CONDUIT ROUTING WITH CONSTRUCTION ENGINEER AND ILLINOIS TOLLWAY ENGINEER.
- THE POWER CONDUIT WILL RUN TO THE POWER PANEL INSIDE THE PLAZA BUILDING. THE NORMAL BREAKER PANEL WILL BE UTILIZED FOR THE VES WASH POWER SOURCE.
- UNLESS OTHERWISE NOTED ALL CONDUIT IS PVC COATED RGS.
- ONE (1) NEMA 4X 12"X12"X6" ENCLOSURE WILL BE PLACED ON THE REAR AND FRONT VES CAMERA MONOTUBE AND ONE (1) NEMA 4X 16"X14"X8" WILL BE PLACED ON THE BARRIER WALL AT EACH AET ZONE.
- MONOTUBE MOUNTED NEMA 4X PULL BOXES LOCATION TO BE DETERMINED IN FIELD. PULL BOX TO BE SECURELY FASTENED TO THE CONCRETE BARRIER. AT LEAST 1' OF SPOOLED UP VINYL TUBING FOR EACH CAMERA WILL BE PLACED IN THE MONOTUBE PULL BOXES.
- NOT USED.
- CONDUITS FOR SPRAY TUBING SHALL BE SEALED ON BOTH ENDS TO PREVENT WATER FROM PENETRATING.
- CONTRACTOR SHALL PROVIDE STRAIN RELIEF FOR WASHER TUBING IN POLES/MONOTUBES.
- FINAL POSITION AND NUMBER OF VES CAMERAS INSTALLED TO BE DETERMINED IN THE FIELD. NUMBER OF REAR VES CAMERAS SHOWN IS FOR ILLUSTRATION PURPOSES ONLY.
- 16"X14"X6" NEMA 4X PULL BOXES FOR THE REAR AND FRONT VES CAMERA MONOTUBE SHALL BE SURFACE MOUNTED ON THE RIGHT SHOULDER BARRIER WALL, AWAY FROM TRAFFIC.
- ALL CONDUITS, FITTINGS AND PENETRATIONS INTO EACH OF THE ENCLOSURES IN THE SYSTEM SHALL BE PROPERLY SEALED WITH ELECTRICAL PUTTY OR OTHER APPROVED SEALING METHODS TO PREVENT MOISTURE AND RODENT ENTRY.
- CONTRACTOR MUST VERIFY THAT THERE SHALL BE SUFFICIENT ROOM FOR CABINET DOOR TO OPEN.

**NOTE TO DESIGNER**


THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.




**VES WASH SYSTEM  
SUGGESTED CONDUIT  
ROUTING**



ELECTRIC HEATER WITH THERMOSTAT  
(OUTDOOR INSTALLATION ONLY)  
NOTE 4



ELECTRICAL DUAL OUTLET GFCI 20A



CABINET LIGHTING AND GFI OUTLET


NOTES:

1. ALL CABLING ON THIS DRAWING IS #12 AWG
2. MAIN BREAKER IS 25A. ILLUSTRATED ON VES WASH PANEL DETAIL ITEM U . LOCATED ON TOP DIN RAIL.
3. THREE 1-C #10 CABLES WILL BE ROUTED FROM THE MDP TO THE VES POWER WASH ENCLOSURE. THE POWER FEED WILL BE INITIATED FROM THE NORMAL BREAKER PANEL. THE CONTRACTOR TO SUPPLY AND INSTALL A 30A BREAKER IN THE MDP PANEL. POWER IS 120VAC WITH A HOT, NEUTRAL AND GROUND. THIS POWER FEED WILL THEN TERMINATE ON THE MAIN 25A BREAKER IN THE VES POWER WASH ENCLOSURE.
4. TO BE USED FOR OUTDOOR INSTALLATION ONLY

NOTE TO DESIGNER  
THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.



VES WASH SYSTEM  
MISCELLANEOUS POWER  
WIRING DIAGRAM



SWITCH CONFIGURATION

NOTE TO DESIGNER

THIS BASE SHEET SHOWS TYPICAL CONSTRUCTION BUT IT IS NOT A STANDARD DRAWING. IT REQUIRES COMPLETION BY THE DESIGNER PRIOR TO INSERTION INTO A CONTRACT. MICROSTATION FILES AND THE "CADD STANDARDS MANUAL" ARE AVAILABLE ON THE ILLINOIS TOLLWAY WEBSITE. THE DESIGNER SHALL ACCEPT THE RESPONSIBILITY OF THE DESIGN OF THIS SHEET UPON ITS COMPLETION AND INSERTION INTO A CONTRACT. ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.

NOTES:

1. SCHEMATIC ILLUSTRATES ONE (1) LANE PLAZA WITH SIX (6) VES CAMERAS INSTALLED (3 REAR AND 3 FRONT VES).



VES WASH SYSTEM CONTROL SWITCH SCHEMATIC

GENERAL NOTES:

1. ALL EXPOSED CONCRETE EDGES SHALL HAVE A ¾" x 45° CHAMFER, EXCEPT WHERE SHOWN OTHERWISE. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVEL.

REINFORCEMENT BARS:

1. REINFORCEMENT BARS, INCLUDING REINFORCEMENT BARS, EPOXY-COATED SHALL CONFORM TO THE REQUIREMENTS OF IDOT STANDARD SPECIFICATIONS SECTION 508 AND ARTICLE 1006.10.
2. REINFORCEMENT BARS DESIGNATED "(E)" SHALL BE EPOXY-COATED.
3. REINFORCEMENT BENDING DETAILS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF ACI 315, "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES".
4. REINFORCEMENT BAR BENDING DIMENSIONS ARE OUT-TO-OUT.
5. COVER FROM THE FACE OF CONCRETE TO FACE OF REINFORCEMENT BARS SHALL BE 3" FOR SURFACES FORMED AGAINST EARTH AND 2" FOR ALL OTHER SURFACES UNLESS OTHERWISE SHOWN.

CONSTRUCTION SPECIFICATIONS:

1. ILLINOIS TOLLWAY SUPPLEMENTAL SPECIFICATIONS ISSUED MARCH, 2023 TO THE ILLINOIS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
2. ILLINOIS DEPARTMENT OF TRANSPORTATION SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS ADOPTED JANUARY 1, 2023.
3. ILLINOIS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION ADOPTED JANUARY 1, 2022.

DESIGN LOADING:

LIVE LOAD, CONTROLLING CASE OF THE FOLLOWING:  
100 P.S.F.  
2,000 LB. CONCENTRATED FORCE OR  
KNOWN LOADING PROVIDED BY ITS

SNOW LOAD: 50 P.S.F.

WIND SPEED: 120 M.P.H. APPLIED TO BUILDING WALLS, PER ASCE 7-16


DEAD LOAD: 30,000 POUNDS (12'x30' BUILDING) OR 20,000 POUNDS (12'x20' BUILDING) SELF WEIGHT OF SLAB

DESIGN STRESSES FOR REINFORCED CONCRETE:

$f_c$  = COMPRESSIVE STRENGTH OF CONCRETE (CLASS SI) = 3,500 P.S.I.  
 $f_y$  = YIELD STRENGTH OF REINFORCEMENT BARS (GRADE 60) = 60,000 P.S.I.


DESIGN SPECIFICATIONS:

1. ILLINOIS TOLLWAY STRUCTURE DESIGN MANUAL ISSUED MARCH, 2023.
2. INTERNATIONAL BUILDING CODE, 2021.
3. ASCE 7-16 MINIMUM DESIGN LOADS AND ASSOCIATED CRITERIA FOR BUILDINGS AND OTHER STRUCTURES, 2017.
4. ACI 318-19 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, 2022.
5. ILLINOIS DEPARTMENT OF TRANSPORTATION BRIDGE MANUAL, JANUARY 2023.
6. ILLINOIS TOLLWAY GEOTECHNICAL ENGINEER MANUAL DATED MARCH 2022.




| FOUNDATION LENGTH TABLE                      |           |
|--|-----------|
| TOLL PLAZA BUILDING TYPE                     | DIMENSION |
| MAIN TOLL PLAZA BUILDING WITH GENERATOR      | A = 32'   |
| REMOTE TOLL PLAZA BUILDING WITHOUT GENERATOR | A = 22'   |

PLAN VIEW



SECTION A-A



SECTION B-B

NOTE TO DESIGNER

- ALL "NOTE TO DESIGNER" BOXES SHALL BE REMOVED BY THE DESIGNER PRIOR TO INSERTION OF THE SHEET INTO THE PLAN SET.
- THIS DRAWING IS A CONCEPT FOUNDATION FROM A BUILDING MANUFACTURER. THE FOUNDATION MUST HAVE A FLAT TOP SLAB AS SHOWN IN THE DRAWING TO SUPPORT THE BUILDING FRAME.
- THE DESIGNER SHALL DESIGN THE TOP SLAB, FOOTERS, WALLS AND REINFORCING DETAILS AS NECESSARY TO SUPPORT THE BUILDING AND MEET LOCAL CODES.
- LOADS SHOWN ARE MINIMUM. IF ACTUAL LOADS ARE LARGER, REPLACEMENT MINIMUM LOADS SHOWN.
- THE DESIGN IS BASED ON AN ALLOWABLE SOIL BEARING PRESSURE OF 2,000 P.S.F.



PLAZA CONTROL BUILDING  
CONCRETE FOUNDATION